



**US Army Corps  
of Engineers**

Construction Engineering  
Research Laboratory

USACERL Special Report P-91/17  
May 1991

2

# **Building Maintenance and Repair Data for Life-Cycle Cost Analyses: Architectural Systems**

by

Edgar S. Neely  
Robert D. Neathammer  
James R. Stirn  
Robert P. Winkler

This research project has provided improved maintenance resource data for use during facility planning, design, and maintenance activities. Data bases and computer systems have been developed to assist planners in preparing DD Form 1391 documentation, designers in life-cycle cost component selection, and maintainers in resource planning. The data bases and computer systems are being used by U.S. Army Corps of Engineers (USACE) designers at the District and installation levels and by resource programmers at USACE Headquarters, and Army Major Commands and installations. These research products may also be useful to other Government agencies and the private sector.

This report describes the building task maintenance and repair data base development and gives examples of its application. It is one of a series of special reports on the maintenance and repair data base. While this report describes architectural systems, other reports in the series cover heating, ventilation, and air-conditioning (HVAC) systems, plumbing systems, and electrical systems.

Approved for public release; distribution is unlimited.

DTIC  
ELECTE  
AUG 27 1991  
S B D

91 8 26 021

**91-08879**



The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official indorsement or approval of the use of such commercial products. The findings of this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.

*DESTROY THIS REPORT WHEN IT IS NO LONGER NEEDED*

*DO NOT RETURN IT TO THE ORIGINATOR*

REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.				
1. AGENCY USE ONLY (Leave Blank)	2. REPORT DATE May 1991	3. REPORT TYPE AND DATES COVERED Final		
4. TITLE AND SUBTITLE  Building Maintenance and Repair Data for Life-Cycle Cost Analyses: Architectural Systems			5. FUNDING NUMBERS  RDTE dated 1980 REIMB 1984 - 1989	
6. AUTHOR(S)  Edgar S. Neely, Robert D. Neathammer, James R. Stim, and Robert P. Winkler				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)  U.S. Army Construction Engineering Research Laboratory (USACERL) P. O. Box 9005 Champaign, IL 61826-9005			8. PERFORMING ORGANIZATION REPORT NUMBER  SR P-91/17	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)  HQUSACE ATTN: CEMP-EC 20 Massachusetts Avenue, NW Washington DC 20001			10. SPONSORING/MONITORING AGENCY REPORT NUMBER  Office of the Chief of Engineers ATTN: DAEN-ZCF-R Pentagon Washington DC 20310	
11. SUPPLEMENTARY NOTES  Copies are available from the National Technical Information Service, 5285 Port Royal Road, Springfield, VA 22161				
12a. DISTRIBUTION/AVAILABILITY STATEMENT  Approved for public release; distribution is unlimited.			12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words)  This research project has provided improved maintenance resource data for use during facility planning, design, and maintenance activities. Data bases and computer systems have been developed to assist planners in preparing DD Form 1391 documentation, designers in life-cycle cost component selection, and maintainers in resource planning. The data bases and computer systems are being used by U.S. Army Corps of Engineers (USACE) designers at the District and installation levels and by resource programmers at USACE Headquarters, and Army Major Commands and installations. These research products may also be useful to other Government agencies and the private sector.  This report describes the building task maintenance and repair data base development and gives examples of its application. It is one of a series of special reports on the maintenance and repair data base. While this report describes architectural systems, other reports in the series cover heating, ventilation, and air-conditioning (HVAC) systems, plumbing systems, and electrical systems.				
14. SUBJECT TERMS data bases                      facilities                      maintenance life-cycle costs                      cost analysis			15. NUMBER OF PAGES 94	
			16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT Unclassified	18. SECURITY CLASSIFICATION OF THIS PAGE Unclassified	19. SECURITY CLASSIFICATION OF ABSTRACT Unclassified	20. LIMITATION OF ABSTRACT  SAR	

## FOREWORD

This research was conducted for the Directorate of Military Programs, Headquarters, U.S. Army Corps of Engineers (HQUSACE) and the Office of the Assistant Chief of Engineers under various research, development, testing, and evaluation (RDTE) and reimbursable funding documents. Work began under RDTE in 1980 and continued in reimbursable projects during 1984 through 1989. The technical monitor for the RDTE part was Dr. Larry Schindler (CEMP-EC) and for the reimbursable part was Ms. Val Corbridge (DAEN-ZCF-R).

The work was performed by the Facility Systems Division (FS), U.S. Army Construction Engineering Research Laboratory (USACERL). The Principal Investigators were Dr. Edgar Neely and Mr. Robert Neathammer (USACERL-FS). The primary contractor for much of the data development was the Department of Architectural Engineering, Pennsylvania State University. Dr. Michael O'Connor is Chief of USACERL-FS.

COL Everett R. Thomas is Commander and Director of USACERL, and Dr. L.R. Shaffer is Technical Director.

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A-1	

DTIC  
COPY  
INSPECTED  
6

## CONTENTS

	<b>SF298</b>	<b>1</b>
	<b>FOREWORD</b>	<b>2</b>
	<b>LIST OF TABLES AND FIGURES</b>	<b>4</b>
<b>1</b>	<b>INTRODUCTION</b> .....	<b>5</b>
	Background	5
	Research Performed and Reports Published	6
	Objectives	10
	Approach	10
	Scope	10
	Mode of Technology Transfer	10
<b>2</b>	<b>PROBLEM DEFINITION</b> .....	<b>11</b>
<b>3</b>	<b>DATA BASE DEVELOPMENT</b> .....	<b>12</b>
	Introduction	12
	Historical Data Review	12
	Engineered Performance Standards	12
	Committee Reviews	13
	Building Subdivision	13
	Task Data Development	13
	Significance of the Task Data	17
	Component Summary Tables	18
	Life-Cycle Cost Analysis Tables	25
<b>4</b>	<b>DATA BASE APPLICATION EXAMPLES</b> .....	<b>29</b>
	Introduction	29
	Terminology	29
	Examples	31
	<b>REFERENCES</b>	<b>45</b>
	<b>LIST OF ACRONYMS</b>	<b>47</b>
	<b>APPENDIX A: Life-Cycle Cost Analysis (7 Percent)</b>	<b>49</b>
	<b>APPENDIX B: Life-Cycle Cost Analysis (10 Percent)</b>	<b>65</b>
	<b>APPENDIX C: Technical Bulletin Index for Engineered</b>	
	Performance Standards	79
	<b>APPENDIX D: Geographical Location Adjustment Factors</b>	<b>82</b>
	<b>DISTRIBUTION</b>	

## TABLES

Number		Page
1	Typical Task Data Form	7
2	Typical Component Summary	8
3	Life-Cycle Cost Analysis	9
4	Task CT-159	15
5	Task CT-416	16
6	Tasks for a Shingle Roof	19
7	Task Summary Data for Shingle Roof	23
8	Shingle Roof Spreadsheet—Labor Hours	24
9	Seven Percent Discount Factors From Date of Study	26
	Ten Percent Discount Factors From Date of Study	27
11	Calculation Sheet - Example 1	33
12	Calculation Sheet - Example 2	36
13	Calculation Sheet - Example 3	38
14	Calculation Sheet - Example 6	42
15	Calculation Sheet - Example 7	44

## FIGURE

1	DOS, BOD, EOS Relationship	30
---	----------------------------	----

# **BUILDING MAINTENANCE AND REPAIR DATA FOR LIFE-CYCLE COST ANALYSES: ARCHITECTURAL SYSTEMS**

## **1 INTRODUCTION**

### **Background**

Maintenance\* and repair (M&R) cost estimates are needed during planning, design, and operations/maintenance of Army facilities. During planning, life-cycle costs are needed to evaluate alternative ways of meeting requirements (e.g., lease, new construction, renovate existing facilities). During design, M&R requirements for various types of components, such as built-up or shingle roofs, are needed so that the total life-cycle cost of different designs can be minimized. Finally, once the facility has been constructed, outyear predictions of maintenance and repair costs are needed so that enough funds can be programmed to ensure that Army facilities are maintained properly and do not deteriorate due to lack of maintenance.

The Directorate of Engineering and Construction (EC), Headquarters, U.S. Army Corps of Engineers (HQUSACE)\*\*, asked the U.S. Army Construction Engineering Research Laboratory (USACERL) to coordinate the assembly of a single centralized maintenance and repair data base for use by Corps designers. This research was required because designers were not able to obtain reliable maintenance and repair data to support their life-cycle cost (LCC) analysis from installations or from the technical literature. One of the first tasks in the research effort was to determine if reliable data bases, which could be adapted for Corps use, existed in government or private industry. Comprehensive data bases of maintenance costs for government and private sector facilities did not exist. The little data available always depended on widely varying standards of maintenance used to maintain the facilities for which the data was collected and thus was unreliable for prediction purposes. Recognizing this, HQUSACE asked USACERL to develop a maintenance and repair cost data base. This data is for use by U.S. Army Corps of Engineers (USACE) designers in performing life-cycle cost analyses during the design of new facilities. Initial results were presented in several USACERL reports.<sup>1</sup>

Soon after this request, the Facilities Programming and Budgeting Branch of the Facilities Engineering Directorate asked USACERL to develop prediction models for outyear maintenance requirements of the Army facility inventory. The Programming Office of EC, responsible for Military Construction, Army (MCA) planning, also requested that USACERL provide methods and automated tools to help installations perform economic analyses. Part of the objective was to allow analysts to obtain future maintenance cost data.

---

\*Maintenance in this report means all work required to keep a facility in good operating condition; it includes all maintenance, repair, and replacement of components required over the life of a facility.

\*\*At the time of this request, EC was part of the Office of the Chief of Engineers, which has since reorganized. In addition, EC has now become the Directorate of Military Programs.

<sup>1</sup> R.D. Neathammer, *Life-Cycle Cost Database Design and Sample Cost Data Development*, Interim Report P-120/ADA0997222 (U.S. Army Construction Engineering Research Laboratory [USACERL], February 1981); R.D. Neathammer, *Life-Cycle Cost Database: Vol I, Design*, and *Vol II, Sample Data Development*, Technical Report P-139/ADA126644 and ADA126645 (USACERL, January 1983), Appendices E through G.

In response to these requests, USACERL began a multiyear effort to develop a comprehensive maintenance and repair cost research program for buildings. This coordinated program is the key to all detailed estimation of future maintenance costs for Army facilities.

## Research Performed and Reports Published

This is one of several interrelated reports addressing maintenance resource prediction in the facility life-cycle process. The total research effort is described in a USACERL Technical Report.<sup>2</sup>

The first research product was a data base containing maintenance tasks related to every building construction component. This data base provides labor, material, and equipment resource information. The frequency of task occurrence is also included. This information is published in a series of four USACERL Special Reports by engineering systems: (1) architectural, (2) heating, ventilating, and air-conditioning (HVAC), (3) plumbing, and (4) electrical. The title for the series is *Maintenance Task Data Base for Buildings* (the present report covers architectural systems for this series).<sup>3</sup> Table 1 shows an example from this data base. This data is also available in electronic form. The data base is used in a personal computer (PC) system under the Disk Operating System (DOS). This computer program allows a facility to be defined by entering the components and component quantities comprising the facility. The tasks are used to determine the resources required annually to keep the facility maintained.

The second research product was a component resource summary for the first 25 years of a facility. The tasks for the component were scheduled and combined into one set of annual resource requirements. This annual resource information is published in a series of four USACERL Special Reports titled *Building Component Maintenance and Repair Data Base*.<sup>4</sup> An example from this data base is shown in Table 2. The data base is also available in electronic form. This data can be used to perform special economic analyses such as one for a 20-year life using a 10 percent discount rate.

The third research product was a set of 25-year present worth factor tables for use by designers in selecting components for discount rates of 7 and 10 percent. The annual component resource values were multiplied by the appropriate present worth factor and added for the 25 years to produce one set of resource values. This information is published in a series of four USACERL Special Reports titled

---

<sup>2</sup> E.S. Neely, R.D. Neathammer, J.R. Stirn, and R.P. Winkler, *Maintenance Resource Prediction in the Facility Life-Cycle Process*, Technical Report P-91/10 (USACERL, March 1991).

<sup>3</sup> E.S. Neely, R.D. Neathammer, J.R. Stirn, and R.P. Winkler, *Maintenance Task Data Base for Buildings. Heating, Ventilation, and Air Conditioning Systems*, Special Report P-91/21 (USACERL, May 1991), E.S. Neely, R.D. Neathammer, J.R. Stirn, and R.P. Winkler, *Maintenance Task Data Base for Buildings. Plumbing Systems*, Special Report P-91/18 (USACERL, May 1991), E.S. Neely, R.D. Neathammer, J.R. Stirn, and R.P. Winkler, *Maintenance Task Data Base for Buildings. Electrical Systems*, Special Report P-91/25 (USACERL, May 1991).

<sup>4</sup> E.S. Neely, R.D. Neathammer, J.R. Stirn, and R.P. Winkler, *Building Component Maintenance and Repair Data Base for Buildings. Architectural Systems*, Special Report P-91/27 (USACERL, May 1991), E.S. Neely, R.D. Neathammer, J.R. Stirn, and R.P. Winkler, *Building Component Maintenance Data Base for Buildings. Heating, Ventilation, and Air-Conditioning Systems*, Special Report P-91/22 (USACERL, May 1991), E.S. Neely, R.D. Neathammer, J.R. Stirn, and R.P. Winkler, *Building Component Maintenance and Repair Data Base for Buildings. Plumbing Systems*, Special Report P-91/30 (USACERL, May 1991); E.S. Neely, R.D. Neathammer, J.R. Stirn, and R.P. Winkler, *Building Component Maintenance and Repair Data Base for Buildings. Electrical Systems*, Special Report P-91/19 (USACERL, May 1991).



Table 1

## Typical Task Data Form

Task Code: 0311356

Component: SHINGLES System: ROOFING Subsystem: ROOF COVERING  
 Task Description: REPLACE NEW OVER EXISTING - SHINGLED ROOF  
 Unit of Measure: SQUARE FEET Frequency of Occurrence: H: 18.00 A: 20.00 L: 22.00  
 Persons per Team: 2 Task Duration: 0.0150 hours Once every (H,A,L) years  
 Trade: ROOFER Task Classification: 1

## Labor Resources

Subtask Description	Labor Hours
1. SET UP/SECURE/TAKE DOWN LADDER	0.000160
2. REPLACE WITH NEW SHINGLE	0.012887
3. CLEAN UP	0.010000

## Material Resources

Description	Quantity	Unit Cost
SHINGLE	1.0 SF	0.2600
MASTIC	1.0 SF	0.1500
		0.4100

SUMMARY

Resources	Direct	Indirect	Total
Labor Hours	0.023047	0.006914	0.029961
Material Cost \$	0.410000		0.410000
Equipment Hours			0.014981

Table 2

## Typical Component Summary

CACES No.: 031134 - Roll Roofing				031135 - Shingles		
Labor Hours	Materials \$	Equipment Hours	YR	Labor Hours	Materials \$	Equipment Hours
0.0076	0.0165	0.0039	1	0.0024	0.0220	0.0013
0.0076	0.0165	0.0039	2	0.0024	0.0220	0.0013
0.0090	0.0165	0.0046	3	0.0026	0.0220	0.0014
0.0076	0.0165	0.0039	4	0.0024	0.0220	0.0013
0.0076	0.0165	0.0039	5	0.0032	0.0330	0.0017
0.0090	0.0165	0.0046	6	0.0026	0.0220	0.0014
0.0076	0.0165	0.0039	7	0.0024	0.0220	0.0013
0.0076	0.0165	0.0039	8	0.0024	0.0220	0.0013
0.0090	0.0165	0.0046	9	0.0026	0.0220	0.0014
0.0414	0.7496	0.0207	10	0.0032	0.0330	0.0017
0.0076	0.0165	0.0039	11	0.0024	0.0220	0.0013
0.0076	0.0165	0.0039	12	0.0026	0.0220	0.0014
0.0090	0.0165	0.0046	13	0.0024	0.0220	0.0013
0.0076	0.0165	0.0039	14	0.0024	0.0220	0.0013
0.0076	0.0165	0.0039	15	0.0034	0.0330	0.0018
0.0090	0.0165	0.0046	16	0.0024	0.0220	0.0013
0.0076	0.0165	0.0039	17	0.0024	0.0220	0.0013
0.0076	0.0165	0.0039	18	0.0026	0.0220	0.0014
0.0090	0.0165	0.0046	19	0.0024	0.0220	0.0013
0.0414	0.7496	0.0207	20	0.0332	0.4675	0.0167
0.0076	0.0165	0.0039	21	0.0026	0.0220	0.0014
0.0076	0.0165	0.0039	22	0.0024	0.0220	0.0013
0.0090	0.0165	0.0046	23	0.0024	0.0220	0.0013
0.0076	0.0165	0.0039	24	0.0026	0.0220	0.0014
0.0076	0.0165	0.0039	25	0.0032	0.0330	0.0017

All data is per square foot of roof area.

*Building Maintenance and Repair Data for Life-Cycle Cost Analyses.*<sup>5</sup> Table 3 shows an example from this data base. The data base is also available in electronic form. The first three resource columns provide data to allow designers to calculate the life-cycle costs at any location by multiplying by the correct labor rate, equipment rate, and material geographic factor. The multiplication and addition have been performed for the Military District of Washington, DC, and results are given in the fourth column of the table. The right section of the table is information that can be entered into computer systems that perform life-cycle cost analysis.

<sup>5</sup> E.S. Neely, R.D. Neathammer, J.R. Stirn, and R.P. Winkler, *Building Maintenance and Repair Data for Life-Cycle Cost Analyses: Heating, Ventilation, and Air Conditioning Systems*, Special Report P-91/20 (USACERL, May 1991), E.S. Neely, R.D. Neathammer, J.R. Stirn, and R.P. Winkler, *Building Maintenance and Repair Data for Life-Cycle Cost Analyses: Plumbing Systems*, Special Report P-91/24 (USACERL, May 1991), E.S. Neely, R.D. Neathammer, J.R. Stirn, R.P. Winkler, *Building Maintenance and Repair Data for Life Cycle Cost Analyses: Electrical Systems*, Special Report P-91/26 (USACERL, May 1991).

Table 3

## Life-Cycle Cost Analysis

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)												
COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (P=10%)				PRESENT MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS							
	um	By Resources			Washington D.C. Total	Annual Maintenance and Repair			Replacement and High Costs Tasks			
		labor	material	equipment		labor	material	equipment	Yr	labor	material	equipment
ARCHITECTURE												
ROOFING												
ROOF COVERING												
BUILTUP ROOFING												
PLACE NEW MEMBRANE OVER EXISTING-BUILTUP	SF	0.03987	0.37166	0.01994	1.25	0.00487	0.03167	0.00244	28	0.04938	0.70490	0.02469
MOD. BIT./THERMOPLASTIC THERMOSETTING	SF	0.02415	0.33069	0.01208	0.86	0.00245	0.03218	0.00123	20	0.05659	0.85860	0.02829
SLATE	SF	0.01667	0.23941	0.00833	0.61	0.00173	0.02202	0.00086	20	0.03683	0.69960	0.01841
CEMENT ASBESTOS	SF	0.01809	0.10432	0.00904	0.50	0.00253	0.01458	0.00126	70	0.06885	6.04200	0.03442
TILE	SF	0.01760	0.24341	0.00881	0.63	0.00246	0.03403	0.00123	70	0.05437	0.75190	0.02718
ROLL ROOFING	SF	0.01519	0.20982	0.00759	0.54	0.00212	0.02933	0.00106	70	0.10169	3.07400	0.05084
SHINGLES	SF	0.07156	0.42684	0.03578	2.01	0.00757	0.01556	0.00378	10	0.04141	0.74963	0.02070
REPLACE NEW OVER EXISTING-SHINGLED ROOF	SF	0.02222	0.22132	0.01111	0.71	0.00262	0.02383	0.00131	40	0.04118	0.74497	0.02059
METAL									20	0.02996	0.43460	0.01498
FIBERGLASS RIGID STP. ROOF	SF	0.01422	0.11058	0.00711	0.42	0.00199	0.01546	0.00099	30	0.36265	2.17300	0.18132
CONCRETE, SEALED PANEL ROOF	SF	0.02161	1.15262	0.01080	1.63	0.00228	0.06266	0.00114	20	0.04543	6.01550	0.02272
CONCRETE, SEALED PANEL RF4	SF	0.04260	0.11748	0.02131	1.05	0.00596	0.01642	0.00298	60	0.06123	24.07419	0.03061
CONCRETE, SEALED POURED	SF	0.03950	0.06408	0.01974	0.96	0.00552	0.01175	0.00276	300	0.04342	24.07419	0.02171
FIBERGLASS, RIGID ROOF	SF	0.09872	0.62996	0.04936	2.81	0.01380	0.06807	0.00690	500	3.81056	18.03219	1.90528
	SF	0.03832	1.15262	0.01915	2.00	0.00468	0.06266	0.00234	20	0.04133	6.01550	0.02066

A fourth research product was a PC system that allows facilities to be modeled by entering the components that comprise the facility. Future years resource predictions are produced by applying the individual tasks and then forming resource summaries by subsystems, systems, facilities, installations, reporting installations, Major Commands (MACOMS) and Army. A summary level computer system was also developed for use by the Department of the Army (DA) and MACOMS. The summary level system applies the most basic data contained in the current facility real property inventory files: (1) current facility use, (2) floor area, and (3) construction date. Users and systems manuals will be published as USACERL ADP Reports.

## Objectives

The objective of this report is to describe the task development process for architectural systems and give examples for using these tasks.

## Approach

The first activity in the research was to survey the literature for available maintenance data. No comprehensive task resource data base was located. The Navy has developed a series of manuals dealing with labor hours required to perform several basic maintenance tasks. This work has been adopted by the Department of Defense (DOD) for triservice use. A series of Technical Bulletins (TBs) under the general title *Engineered Performance Standards* (EPS) has been published.

The next activity was to survey USACE District offices to solicit their input for a data base. A guiding committee composed of District personnel, installation representatives, and private sector consultants met and agreed upon a general data base design. More importantly, they recommended that the data base be developed using the EPS rather than historical data.

Once the data base was developed, component summaries were created by summing all tasks for a component. These summaries were then input into a program that computed present worth values for each component.

The calculation procedures described in this report were performed and summarized for standard Army life-cycle analysis of 25 years with a 7 or 10 percent present worth factor. Final results are published in the USACERL special report series *Building Maintenance and Repair Data Base for Life-Cycle Cost Analyses*.

## Scope

The task data base is for DOD designers and can also be used by those in the private sector.

## Mode of Technology Transfer

The tables pertinent to designer use will be issued as a supplement to Technical Manual (TM) 5-802-1, *Economic Studies for Military Construction Design—Applications*.

## 2 PROBLEM DEFINITION

In the facility life-cycle process, costs are incurred in construction, operation, maintenance, and disposal of a facility. Past emphasis during the planning, design, and construction phases has been on estimating initial construction costs. The impact of operating and maintaining facilities has always been a secondary consideration. In many cases, the operation and maintenance (O&M) costs are far greater than initial construction costs. Building owners are concerned with the total ownership costs of facilities rather than just the initial construction costs.

The Army has realized the importance of performing total life-cycle cost analyses for facilities at the design stage, and of accurately forecasting these costs for funds programming. HQUSACE asked USACERL in 1980 to develop a method of estimating future maintenance costs for buildings. In 1982, the programming branch of the former Facilities Engineering Directorate asked USACERL to develop effective models for forecasting facility maintenance resource requirements based on the actual facility.

Life-cycle cost economic studies are an integral part of facility design in the MCA program. Requirements for performing these studies are given in:

- Statutes, Code of Federal Regulations, and Executive Orders for performing analyses when energy is a key cost and for wastewater treatment plants
- USACE *Architectural and Engineering Instructions: Design Criteria*
- Army Regulation (AR) 11-28, *Economic Analysis and Program Evaluation for Resource Management* for general economic analyses.
- TM 5-802-1, *Economic Studies for Military Construction Design--Applications*

The main purpose of these studies is to minimize the life-cycle costs of Army facilities.

To perform life-cycle cost analyses on facility designs, three categories of costs are needed: initial, operating, and maintenance. Initial costs are usually easy to estimate through existing cost estimating systems such as the Corps of Engineers Computer Assisted Cost Estimating System (CACES) and standard publications such as Means or Dodge. Operating costs can be estimated by using energy consumption models such as the Corps of Engineers Building Loads Analysis and System Thermodynamics (BLAST) program or the Trane Company's Trace program. However, accurate estimates of maintenance costs are not available.

There are no comprehensive data bases of maintenance costs for building components either in the private sector or State/Federal Governments. Some historical data is available from the Building Owners' and Managers' Association reports. Within the Army, the Integrated Facilities System (IFS) contains some historical data; however, it does not have a feature for retaining several types of a building component (e.g., having brick and wood exteriors or three types of floor covering). Moreover, the data in IFS has not been kept current. For example, at one installation several family housing units were shown as having wood siding when, in fact, they had been covered with aluminum siding several years earlier.

## 2 PROBLEM DEFINITION

In the facility life-cycle process, costs are incurred in construction, operation, maintenance, and disposal of a facility. Past emphasis during the planning, design, and construction phases has been on estimating initial construction costs. The impact of operating and maintaining facilities has always been a secondary consideration. In many cases, the operation and maintenance (O&M) costs are far greater than initial construction costs. Building owners are concerned with the total ownership costs of facilities rather than just the initial construction costs.

The Army has realized the importance of performing total life-cycle cost analyses for facilities at the design stage, and of accurately forecasting these costs for funds programming. HQUSACE asked USACERL in 1980 to develop a method of estimating future maintenance costs for buildings. In 1982, the programming branch of the former Facilities Engineering Directorate asked USACERL to develop effective models for forecasting facility maintenance resource requirements based on the actual facility.

Life-cycle cost economic studies are an integral part of facility design in the MCA program. Requirements for performing these studies are given in:

- Statutes, Code of Federal Regulations, and Executive Orders for performing analyses when energy is a key cost and for wastewater treatment plants
- USACE *Architectural and Engineering Instructions: Design Criteria*
- Army Regulation (AR) 11-28, *Economic Analysis and Program Evaluation for Resource Management* for general economic analyses.
- TM 5-802-1, *Economic Studies for Military Construction Design--Applications*

The main purpose of these studies is to minimize the life-cycle costs of Army facilities.

To perform life-cycle cost analyses on facility designs, three categories of costs are needed: initial, operating, and maintenance. Initial costs are usually easy to estimate through existing cost estimating systems such as the Corps of Engineers Computer Assisted Cost Estimating System (CACES) and standard publications such as Means or Dodge. Operating costs can be estimated by using energy consumption models such as the Corps of Engineers Building Loads Analysis and System Thermodynamics (BLAST) program or the Trane Company's Trace program. However, accurate estimates of maintenance costs are not available.

There are no comprehensive data bases of maintenance costs for building components either in the private sector or State/Federal Governments. Some historical data is available from the Building Owners' and Managers' Association reports. Within the Army, the Integrated Facilities System (IFS) contains some historical data; however, it does not have a feature for retaining several types of a building component (e.g., having brick and wood exteriors or three types of floor covering). Moreover, the data in IFS has not been kept current. For example, at one installation several family housing units were shown as having wood siding when, in fact, they had been covered with aluminum siding several years earlier.

estimates, and, more seriously, the production of accurate estimates. About this time, the Department of Defense directed that standards for work should be developed to the maximum feasible extent and applied throughout the military establishment. As a result of that directive, EPS were developed.

The Navy undertook a large research program to perform time and motion studies of maintenance personnel as they performed their maintenance tasks. After several years of effort, the Navy published the results under the title "Engineered Performance Standards." Both Army and Air Force maintenance personnel reviewed this set of manuals and adopted it for official use. Today, the EPS are used by all DOD agencies and are published as one set of reports carrying three different publication numbers for the Army, Navy, and Air Force.

### **Committee Reviews**

At the beginning of this research project HQUSACE and USACERL formed an advisory committee composed of representatives from all offices involved in performing life-cycle cost analysis. The basic objective of the advisory committee was to involve as many appropriate and knowledgeable people as possible in deciding how to solve the M&R data base problem. The advisory committee reviewed the historical information research results and the EPS research program and reports. After lengthy discussion of all possible alternatives, the advisory committee decided to develop a maintenance task data base using the EPS as the basis for the labor resources. The advisory committee was active for the first 2 years of the project.

A second maintenance steering committee was formed that was composed of one representative from each HQDA office involved in maintenance resource programming and planning, six major commands, and 10 installations. This maintenance steering committee had the same basic objective as the first advisory committee. In addition, the steering committee wanted to use the data developed to predict actual maintenance resource requirements at installations.

### **Building Subdivision**

The UNIFORMAT method of dividing a building into systems, subsystems, and components was adopted because it is used by all Federal construction agencies and many private organizations. Systems requiring little maintenance such as foundations and superstructure were not considered.

The level of component detail was determined by the members of the maintenance steering committee. This level varied, depending on the facility classification and the costs versus the benefit of collecting and maintaining data. For example, in the typical building the steering committee voted to stop at the door level and not define hardware requirements because the hardware was not a costly item, but for historical family housing, where one hinge could cost \$200, all door hardware had to be defined.

### **Task Data Development**

A task is defined as the work performed by a single trade. Each task is divided into the labor, material, and equipment resources required to perform the work. By separating the tasks in this manner the data can also be used to determine manpower staffing requirements and equipment requirements.

The following procedures have been used to develop the tasks for this research project. Identical procedures can be applied to develop new tasks not currently covered in the task data base.

The task development procedures can be demonstrated by using the existing task number 03111356, REPLACE NEW OVER EXISTING SHINGLED ROOF, shown in Table 1. This task involves gaining access to the roof, placing a new layer of shingles over an existing single-layer shingle roof, and cleaning up the area.

The first step is to obtain a copy of DA Pamphlet 25-30, *Consolidated Index of Army Publications and Blank Forms*. A list of the current TBs covering EPS is given in Appendix C. Review this list to determine which TBs seem to address the task to be developed. The TBs can be obtained from your library or from:

Naval Publications and Forms Center  
5801 Tabor Ave.  
Philadelphia, PA 19120.

Once the TBs are available, the second step is to review the Table of Contents of each to determine if tasks related to the component are covered in the bulletin. If the tasks to be developed are covered by the bulletin, review the tasks to determine if the data given can be applied to the task under development. When tasks related to the new component tasks under development are not covered by EPS, other sources such as estimating books and manuals, national standards, trade publications, and manufacturer data must be researched. It is important to provide a complete list of such materials. A reference librarian can provide resources addressing a specific component.

The roofs of most one to three story buildings are accessed by ladder. A review of the EPS subtasks revealed a standard EPS subtask that covers moving the ladder and moving up and down the ladder. One reference to this standard subtask is in TB 420-4 (p 180), Task CT-159, subtask 9, move, climb up and down ladder, as duplicated in Table 4. The labor rate is given as 0.207 hr/job. It was assumed that the ladder would be moved every 1300 sq ft to provide faster access to the work area. Transforming this number into a rate per square foot of roof area would produce  $0.207 \text{ hr/job} / 1300 \text{ sq ft} = 0.000160 \text{ hr/sq ft}$ .

TB 420-4 contains no single task for placing a new layer of shingles over an old layer. However, Task CT-416, subtask 3 (p 295 in the TB), shown in Table 5, would be almost the same duration. The labor rate would therefore be 0.012887 hr/sq ft.

Some cleanup will be required after placing the shingles. The EPS showed no subtask directly related to this type of cleanup, but a cleanup subtask was found in the masonry handbook, TB 420-14 (p 112), DT-213, subtask 4. The cleanup was estimated to be approximately 20 percent of the resources listed for this subtask, or 0.01 hr/sq ft.

The total direct labor hours to perform the entire job would be the sum of all subtasks, or 0.02305 hr/sq ft. The indirect time or the time to plan the work, load the truck at the beginning of the day, unload



Table 4

## Task CT-159\*

No.	Reference	Work Unit Description	Hours	Units
1	PWMU-1-8352	Measure, mark and check measurement	0.13120	Job
2	PWC-19-XXI	Remove and reinstall cement shingles No. of locations = 1 No. of shingles removed = 6 No. of shingles installed = 6	0.02374 0.14430 0.20040	Job Job Job
3	PWC-15-II	Drill holes for cutting wall No. of holes drilled = 2	0.03080 0.03328	Job Job
4	PWC-15-I	Measure, mark and cut in opening and framing lumber No. of 8 sq. in. cuts = 47	0.15426 0.70406	Job Job
5	PWMU-1-8107	Position framing lumber, trim and rain cap	0.19720	Job
6	PWC-16-XV	Level and align framing	0.10224	Job
7	PWC-16-XXVI	Nail pieces (framing, trim, rain cap) No. of nails = 72	0.00765 0.18000	Job Job
8	PWC-16-XXXII	Caulk around exterior frame No. lin. ft. of caulking = 9	0.00327 0.01530	Job Job
9	PWMU-1-8052	Move, climb up and down ladder	0.20700	Job
10	PWA-5-II	Material handling	0.10359	Job

\*CT-159: Air Conditioner, Opening for, Cut in and Frame Opening in Exterior Wall. Wall has cement shingle and gypsum wallboard interior. CT-159 = 2.23828 hr/job.

Table 5  
Task CT-416\*

No.	Reference	Work Unit Description	Hours	Units
1	PWU-30X	Remove asphalt shingles	0.65795	100 sq ft
2	PWU-3-I	Install one layer 30# felt on wood deck	0.20499	100 sq ft
3	PWU-3-II	Install asphalt shingles with adhesive on wood deck, shingles 12" x 36" with 5" exposure	1.28871	100 sq ft

\*CT-416: Shingles (Asphalt), Remove and Install with 30# Felt. No. of Squares; 1 Square = 100 sq ft.  
CT-416 - 2,15165 hr/100 sq ft.

the truck at the end of the day, personal time, delay time, and material handling time must be included to obtain the total onsite labor time. In EPS, this value is expressed as a percentage of the direct labor. When all factors have been considered, the direct labor should be increased by 30 percent or 0.00691 hr/sq ft.

The steering committee wanted to apply the same material costs for all planning, programming, design, construction, and operations activities. For this research project, all material costs were developed using prices in the Washington, DC area. Material prices for exact locations throughout the world can be obtained by multiplying the Washington, DC area costs by the appropriate location adjustment factor published in a Programming, Administration, and Execution System (PAX) Newsletter under the title "Area Cost Factor Indexes." Copies of the 22 September 1988 indexes are given in Appendix D, Geographical Location Adjustment Factors. The *CACES Unit Price Book* for Region II dated July 1, 1985 has been used for all costs and can be obtained from the Corps District Cost Estimating Section.

In reviewing material prices, there will usually be many grades listed for the component in question. Since only one entry for the component task will be made for the maintenance data base, it is important to use the middle grade for pricing. This will produce an average material cost.

When materials are not given in the CACES manuals, other material pricing manuals, such as Means, should be used to determine the cost.

The material cost for the shingles, \$0.26/sq ft, was taken from the *CACES Unit Price Book for Region II* as cited above. The CACES number is 0751-1002. The cost for the mastic was taken from the *1985 Means Handbook*, p 402, circle number 94. This task required 25 percent of the mastic reported in the Means task. The calculation is:  $2.45 \text{ lb/sq ft} \times \$490/\text{ton}/2000 \text{ lb/ton} = \$0.59976/\text{sq ft}$ . For a single-ply roof, this value is  $\$0.59976/4 = \$0.15/\text{sq ft}$ .

The normal equipment cost is for a maintenance truck with all required tools such as ladders and hand tools. The cost for the truck and equipment is usually based on task duration.

Task frequency determination is the most subjective area in the data base. Most frequencies must be determined by the judgment of professional maintenance personnel with many years of experience in performing the maintenance tasks. Some task frequencies are suggested by the manufacturer or professional organizations. Some frequencies, such as for interior wall painting, are set by regulations. There is very little published information in this area.

The data base has been reviewed by 10 installation Directorates of Engineering and Housing (DEHs) and has been determined to accurately represent the resources required to perform the tasks. This data base serves as the foundation for the tables published in this report. The complete data base is too large to be duplicated in this report, but is available in the USACERL Special Report series titled *Maintenance Task Data Base for Buildings*.

The maintenance steering committee asked Forts Leonard Wood and Bragg to use the tasks to produce resource estimates for the past 3 years and then compare the predictions with their actual expenditures on a facility-by-facility basis. After this comparison was performed by both installations, the results were presented to the steering committee. Both installations stated that they were not performing all the tasks that they should, such as annual gutter cleaning and annual roof inspection. For the total installation, the tasks predicted an 8 to 10 percent higher total expenditure than the actual expenditure. This difference was due to the difference between the tasks predicted and actually performed. When comparisons were made at the task level, the task resource predictions were found to be accurate.

Two additional reviews were performed by two independent organizations that had related research work in the Army. The first review was for a research project to determine the maintenance requirements for historical family housing within the Military District of Washington, DC. The second review was a research project which needed an estimate of all resource requirements for the entire Army. This effort is known as the RPLANS research project. Both organizations reviewed the data base in detail and approved the resource requirements stated in the tasks. In addition, both used the data base within their research projects.

### **Significance of the Task Data**

The task data presented in the previous section is based on average resources. Actual resource values for a particular project will vary as discussed below.

The labor hours reported will vary, depending on factors such as the actual productivity of the workers, the weather conditions, and the working space available. The labor hours given in this report are based on the average obtained from performing time and motion studies as tasks were performed.

The Washington, DC, material costs will vary, depending on factors such as the grade of material actually used, the manufacturer, and the quantity of material actually purchased. The figures given are the averages for all material prices found in the unit price books.

Task frequencies are the most subjective feature in the data base. High, average, and low frequency values are given to emphasize the variances. Average frequencies are used in developing the life-cycle analysis tables presented in the following sections.

## Component Summary Tables

A typical component summary is shown in Table 2 (Chapter 1). The development process is illustrated by using the labor resource for the shingle roof component.

All tasks related to the shingle roof component are listed individually in Table 6, with a task summary in Table 7. The task average frequency is used to project times of occurrence of M&R tasks for the first 25-year period as shown in Table 8. All task resources are expressed per square foot of roof surface.

The first task (Task 1 - 0311351 - Debris Removal by Hand and Visual Inspection) has an average frequency (AVE FREQ in Table 6) of 1.00 years; thus, it would be performed each year. The labor hours (0.000754 in Table 6) are listed for each of the 25 years in the second column of Table 8.

The second task (Task 2 - 0311352 - Non-Destructive Moisture Inspection) has an average frequency from Table 6 of 3.00 years; thus, it would be performed once every 3 years. The labor hours (0.000234 in Table 6) are listed for the years 3, 6, 9, 12, 15, 18, 21, and 24 in the third column of Table 8.

The third task (Task 3 - 0311353 - Minor Repairs) has an average frequency of 1 year; thus it would be performed each year. The labor hours (0.001310 in Table 6) are listed for each of the 25 years in the fourth column of Table 8.

The fourth task (Task 4 - 0311354 - Minor Replacement) has an average frequency of 5 years; thus, it would be performed once every 5 years. The labor hours (0.000822) are listed for years 5, 10, 15, 20, and 25 in the fifth column of Table 8.

The fifth task (Task 5 - 0311355 - Flashing Repairs) has an average frequency of 1 year; thus, it would be performed each year. The labor hours (0.000348 in Table 6) are listed for each year in the sixth column of Table 8.

The sixth task (Task 6 - 0311356 - Replace New Over Existing Shingles) has an average frequency of 20 years; thus, it would be performed every 20 years. The labor hours (.029961 in Table 6) are listed for year 20 in the seventh column.

The seventh task (Task 7 - 0311357 - Removal and Replacement of Shingled roof) has an average frequency of 40 years which is beyond the 25-year study period. No entries are made in column eight of Table 8 since this task will never be performed within the study period.

The total column in Table 8 is formed by adding the labor hours for tasks one through seven on a year-by-year basis. For example, during the third year, Tasks 1, 2, 3, and 5 are performed. The total labor hours would be  $.000754 + .000234 + .001310 + .000348$  which equals 0.002646.

The total column in Table 8 is shown in Table 2. The material costs and equipment hours have been developed in the same manner as explained for the labor hours.

Table 6

## Tasks for a Shingle Roof

## TASK DATA FORM

Task Code: 0311351

Component: SHINGLES System: ROOFING Subsystem: ROOF COVERING  
 Task Description: DEBRIS REMOV. BY HAND & VIS. INSP. - SHINGLED ROOF  
 Unit of Measure: SQUARE FEET Frequency of Occurrence: H: 0.90 A: 1.00 L: 1.10  
 Persons per Team: 2 Task Duration: 0.0004 hours Once every (H,A,L) years  
 Trade: ROOFER Task Classification: 0

## Labor Resources

## Material Resources

Subtask Description	Labor Hrs
1.SET UP/SECURE/TAKE DOWN LADDER	0.000080
2.PICK UP TRASH/DEBRIS, INSPECTION	0.000500

Description	Quantity	Unit Cost
		0.0000

## SUMMARY

Resources UOM	Direct	Indirect	Total
Labor Hours	0.000580	0.000174	0.000754
Material Cost \$	0.000000		0.000000
Equipment Hours			0.000377

Components In This Task: 0311350

## TASK DATA FORM

Task Code: 0311352

Component: SHINGLES System: ROOFING Subsystem: ROOF COVERING  
 Task Description: NON-DESTRUCTIVE MOISTURE INSP. - SHINGLED ROOF  
 Unit of Measure: SQUARE FEET Frequency of Occurrence: H: 2.00 A: 3.00 L: 4.00  
 Persons per Team: 2 Task Duration: 0.0001 hours Once every (H,A,L) years  
 Trade: ROOFER Task Classification: 0

## Labor Resources

## Material Resources

Subtask Description	Labor Hrs
1.SET UP/SECURE/TAKE DOWN LADDER	0.000080
2.ONSITE INSPECT.OF ROOF MEMBRANE	0.000100

Description	Quantity	Unit Cost
		0.0000

## SUMMARY

Resources UOM	Direct	Indirect	Total
Labor Hours	0.000180	0.000054	0.000234
Material Cost \$	0.000000		0.000000
Equipment Hours			0.000117

Components In This Task: 0311350

Table 6 (Cont'd)

## TASK DATA FORM

Task Code: 0311353

Component: SHINGLES System: ROOFING Subsystem: ROOF COVERING  
 Task Description: MINOR REPAIRS - SHINGLED ROOF  
 Unit of Measure: SQUARE FEET Frequency of Occurrence: H: 0.75 A: 1.00 L: 1.25  
 Persons per Team: 2 Task Duration: 0.0007 hours Once every (H,A,L) years  
 Trade: ROOFER Task Classification: 0

## Labor Resources

Subtask Description	Labor Hrs
1.SET UP/SECURE/TAKE DOWN LADDER	0.000160
2.REMOVAL OF ADJACENT SHINGLES	0.000570
3.INSTALL SHINGLES	0.000258
4.CLEAN UP	0.000020

## Material Resources

Description	Quantity	Unit Cost
SHINGLES	0.02 SF	0.2600
MASTIC	0.02 SF	0.1500
		0.0082

## SUMMARY

Resources UOM	Direct	Indirect	Total
Labor Hours	0.001008	0.000302	0.001310
Material Cost \$	0.008200		0.008200
Equipment Hours			0.000655

Components In This Task: 311350

## TASK DATA FORM

Task Code: 0311354

Component: SHINGLES System: ROOFING Subsystem: ROOF COVERING  
 Task Description: MINOR REPLACEMENT - SHINGLED ROOF  
 Unit of Measure: SQUARE FEET Frequency of Occurrence: H: 4.00 A: 5.00 L: 6.00  
 Persons per Team: 2 Task Duration: 0.0004 hours Once every (H,A,L) years  
 Trade: ROOFER Task Classification: 0

## Labor Resources

Subtask Description	Labor Hrs
1.SET UP/SECURE/TAKE DOWN LADDER	0.000160
2.REMOVAL OF DAMAGED SHINGLES	0.000130
3.INSTALL SHINGLES	0.000322
4.CLEAN UP	0.000020

## Material Resources

Description	Quantity	Unit Cost
MASTIC	0.025 SF	0.1500
SHINGLES	0.025 SF	0.2600
		0.0103

## SUMMARY

Resources UOM	Direct	Indirect	Total
Labor Hours	0.000632	0.000190	0.000822
Material Cost \$	0.010250		0.010250
Equipment Hours			0.000411

Components In This Task: 0311350

Table 6 (Cont'd)

## TASK DATA FORM

Task Code: 0311355

Component: SHINGLES System: ROOFING Subsystem: ROOF COVERING  
 Task Description: FLASHING REPAIRS - SHINGLED ROOF  
 Unit of Measure: SQUARE FEET Frequency of Occurrence: H: 0.75 A: 1.00 L: 1.25  
 Persons per Team: 2 Task Duration: 0.0002 hours Once every (H,A,L) years  
 Trade: ROOFER Task Classification: 0

## Labor Resources

## Material Resources

Subtask Description	Labor Hrs	Description	Quantity	Unit Cost
1.SET UP/SECURE/TAKE DOWN LADDER	0.000180	FLASHING	0.02 SF	0.6300
2.REMOVE ADJOINING SHINGLES	0.000057			0.0128
3.REMOVE STEP FLASHING	0.000002			
4.INSTALL NEW STEP FLASHING	0.000003			
5.PLACE NEW SHINGLES IN POSITION	0.000026			
6.CLEAN UP	0.000020			

## SUMMARY

Resources UOM	Direct	Indirect	Total
Labor Hours	0.000268	0.000080	0.000348
Material Cost \$	0.012800		0.012800
Equipment Hours			0.000174

Components In This Task: 0311350

## TASK DATA FORM

Task Code: 0311356

Component: SHINGLES System: ROOFING Subsystem: ROOF COVERING  
 Task Description: REPLACE NEW OVER EXISTING - SHINGLED ROOF  
 Unit of Measure: SQUARE FEET Frequency of Occurrence: H: 18.00 A: 20.00 L: 22.00  
 Persons per Team: 2 Task Duration: 0.0150 hours Once every (H,A,L) years  
 Trade: ROOFER Task Classification: 1

## Labor Resources

## Material Resources

Subtask Description	Labor Hrs	Description	Quantity	Unit Cost
1.SET UP/SECURE/TAKE DOWN LADDER	0.000180	SHINGLE	1.0 SF	0.2600
2.REPLACE WITH NEW SHINGLE	0.012887	MASTIC	1.0 SF	0.1500
3.CLEAN UP	0.010000			0.4100

## SUMMARY

Resources UOM	Direct	Indirect	Total
Labor Hours	0.023047	0.008914	0.029961
Material Cost \$	0.410000		0.410000
Equipment Hours			0.014981

Components In This Task: 0311350

Table 6 (Cont'd)

## TASK DATA FORM

Task Code: 0311357

Component: SHINGLES System: ROOFING Subsystem: ROOF COVERING  
 Task Description: REMOVE AND REPLACEMENT OF SHINGLES-SHINGLED ROOF  
 Unit of Measure: SQUARE FEET Frequency of Occurrence: H: 36.00 A: 40.00 L: 44.00  
 Persons per Team: 2 Task Duration: 0.0206 hours Once every (H,A,L) years  
 Trade: ROOFER Task Classification: 1

Labor Resources		Material Resources		
Subtask Description	Labor Hrs	Description	Quantity	Unit Cost
1.SET UP/SECURE/TAKE DOWN LADDER	0.000160	BASE FELT	1.0 SF	0.4428
2.REMOVE EXISTING SHINGLES	0.006580	SHINGLES	1.0 SF	0.2600
3.INSTALL 1 PLY BASE FELT NAILED	0.002050			0.7028
4.INSTALL SHINGLES	0.012887			
5.CLEAN UP	0.010000			

## SUMMARY

Resources UOM	Direct	Indirect	Total
Labor Hours	0.031677	0.009503	0.041180
Material Cost \$	0.702800		0.702800
Equipment Hours			0.020590

Components In This Task: 0311350



Table 7

## Task Summary Data for Shingle Roof

CACES	DESCRIPTION 0311350 SHINGLES	UM	TRD	CLASS	HIGH FREQ	AVE FREQ	LOW FREQ	LABOR HOURS	MATERIAL COSTS	EQUIPMENT HOURS
0311351	DEBRIS REMOV. BY HAND & VIS. INSP. - SHINGLE	2	17	0	0.90	1.00	1.10	0.000754	0.000000	0.000377
0311352	NON-DESTRUCTIVE MOISTURE INSP. - SHINGLE	2	17	0	2.00	3.00	4.00	0.000234	0.000000	0.000117
0311353	MINOR REPAIRS - SHINGLED ROOF	2	17	0	0.75	1.00	1.25	0.001310	0.008200	0.000655
0311354	MINOR REPLACEMENT - SHINGLED ROOF	2	17	0	4.00	5.00	6.00	0.00822	0.010250	0.000411
0311355	FLASHING REPAIRS - SHINGLED ROOF	2	17	0	0.75	1.00	1.25	0.000348	0.012600	0.000174
0311356	REPLACE NEW OVER EXISTING - SHINGLED RFG.	2	17	1	18.00	20.00	22.00	0.029961	0.410000	0.014981
0311357	REMOVAL & REPLACEMENT OF SHINGLED ROOF	2	17	1	36.00	40.00	40.00	0.041180	0.702800	0.020590

Army Wide Task/Basic Task Structure List

UM = Unit of Measure

TRD = Trade Index

Tree id: BF

Class = Task Classification

Group id: B5

TWPMTH = Task Work Performance Method

Table 8

## Shingle Roof Spreadsheet—Labor Hours

YEAR	TASK1 0311351	TASK2 0311532	TASK3 0311353	TASK4 0311354	TASK5 0311355	TASK6 0311356	TASK7 0311357	TOTAL LABOR HRS	10% P.W.F.	P.W. LABOR HOURS
1	0.000754		0.001310		0.000348			0.002412	0.7164	0.001728
2	0.000754		0.001310		0.000348			0.002412	0.6512	0.001571
3	0.000754	0.000234	0.001310		0.000348			0.002646	0.5920	0.001566
4	0.000754		0.001310		0.000348			0.002412	0.5382	0.001298
5	0.000754		0.001310		0.000348			0.003234	0.4893	0.001582
6	0.000754	0.000234	0.001310	0.000822	0.000348			0.002646	0.4448	0.001177
7	0.000754		0.001310		0.000348			0.002412	0.4044	0.000975
8	0.000754		0.001310		0.000348			0.002412	0.3676	0.000887
9	0.000754	0.000234	0.001310		0.000348			0.002646	0.3342	0.000834
10	0.000754		0.001310	0.000822	0.000348			0.003234	0.3038	0.000982
11	0.000754		0.001310		0.000348			0.002412	0.2762	0.000666
12	0.000754	0.000234	0.001310		0.000348			0.002646	0.2511	0.000664
13	0.000754		0.001310		0.000348			0.002412	0.2283	0.000551
14	0.000754		0.001310		0.000348			0.002412	0.2075	0.000500
15	0.000754	0.000234	0.001310	0.000822	0.000348			0.003468	0.1886	0.000654
16	0.000754		0.001310		0.000348			0.002412	0.1715	0.000414
17	0.000754		0.001310		0.000348			0.002412	0.1559	0.000376
18	0.000754	0.000234	0.001310		0.000348			0.002646	0.1417	0.000375
19	0.000754		0.001310		0.000348			0.002412	0.1288	0.000311
20	0.000754		0.001310		0.000348			0.003195	0.1171	0.003887
21	0.000754	0.000234	0.001310	0.000822	0.000348	0.029961		0.002646	0.1065	0.000282
22	0.000754		0.001310		0.000348			0.002412	0.0968	0.000233
23	0.000754		0.001310		0.000348			0.002412	0.0880	0.000212
24	0.000754	0.000234	0.001310		0.000348			0.002646	0.0800	0.000212
25	0.000754		0.001310	0.000822	0.000348			0.003234	0.0727	0.000235
TOTAL										0.022224

The component data base is not printed in this report because of its size. Component summary data tables are published in the USACERL Special Report series titled *Maintenance Component Data Base for Buildings*.

### Life-Cycle Cost Analysis Tables

The main purpose of this report is to provide the designer with easy-to-use tables for the most common life-cycle cost analysis. USACE designers frequently perform life-cycle cost analysis for a 25-year period using a 7 or 10 percent discount rate shown in Tables 9 and 10. Two sets of summary tables have been generated for these cases and are given in Appendices A and B. Table 3 shows typical life-cycle cost analysis data.

Present Worth. The left four columns of Table 3, labeled "Present Worth of All 25-Year Maintenance and Repair Costs," were developed by multiplying the resources in Table 2 by the 7 or 10 percent present worth factors shown in Tables 9 and 10. The 25 individual year resource figures are totaled as shown for labor in Table 8.

The 1988 Washington, DC area labor and equipment rates were applied to this data to produce the totals shown in the column so titled. This column is given to provide one comparative cost figure for easy computation. This column can be used to quickly assess the ranking of various components' total 25-year LCC.

Annual and High Cost. The right section of Table 3 is provided as input data for current life-cycle cost analysis computer programs. Two types of input are usually required: (1) a uniform or annual maintenance figure and (2) high-cost and replacement tasks that occur in specific years.

The data listed under the heading "Annual Maintenance and Repair" was generated by subtracting the present worth of the replacement task, if its occurrence is 25 years or less, and any high-cost tasks from the present worth values given in the "Present Worth" section of the table. The remaining present worth figures for the low-cost task resources are divided by the cumulative 25-year present worth figure to arrive at the "uniform" or "annual" maintenance figures shown under the "Annual Maintenance and Repair" heading.

There are two types of tasks listed under the heading "Replacement and High-Cost Tasks." The first is the replacement task. The replacement task is shown on the same line as the component description. For example, the replacement task for Built-up Roofing shown in Table 3 would occur when the built-up roof is 28 years old. Replacement would require the expenditure of 0.04938 hours of labor per square foot, \$0.70490 of material per square foot, and 0.02469 hours of equipment (roofing maintenance truck) per square foot of roof area. The second type of task is the high-cost task. Each high-cost task is listed on a separate line below the component description line. For example, there is one high-cost task for built-up roofing shown in Table 3. The high-cost task "Place New Membrane Over Existing Built-up Roof" would occur when the roof is 14 years old. This would require the expenditure of 0.02414 hours of labor per square foot, \$0.69960 of material per square foot, and 0.01207 hours of equipment (roofing maintenance truck) per square foot of roof area.

Table 9

## Seven Percent Discount Factors From Date of Study\*

Years from BOD	End of Year	Accumulated End of Year
1	0.9346	0.9346
2	0.8734	1.8080
3	0.8163	2.6243
4	0.7629	3.3872
5	0.7130	4.1002
6	0.6663	4.7665
7	0.6227	5.3893
8	0.5820	5.9713
9	0.5439	6.5152
10	0.5083	7.0236
11	0.4751	7.4987
12	0.4440	7.9427
13	0.4150	8.3576
14	0.3878	8.7455
15	0.3624	9.1079
16	0.3387	9.4466
17	0.3166	9.7632
18	0.2959	10.0591
19	0.2765	10.3356
20	0.2584	10.5940
21	0.2415	10.8355
22	0.2257	11.0612
23	0.2109	11.2722
24	0.1971	11.4693
25	0.1842	11.6536

(Retention value at end  
of 25th year)

\*Date of Study (DOS) is the Beneficial Occupancy Date (BOD)

Table 10

## Ten Percent Discount Factors From Date of Study

Date of Study (DOS) Exactly 3 Years Before the Beneficial Occupancy Date (BOD)

Year from BOD	Factors		Accumulated
	Mid-Year	End of Year	
-3	0.9535		0.0
-2	0.8668		0.0
-1	0.7880		0.0
BOD			
1	0.7164		0.7164
2	0.6512		1.3676
3	0.5920		1.9596
4	0.5382		2.4978
5	0.4893		2.9871
6	0.4448		3.4319
7	0.4044		3.8362
8	0.3676		4.2038
9	0.3342		4.5380
10	0.3038		4.8418
11	0.2762		5.1180
12	0.2511		5.3691
13	0.2283		5.5973
14	0.2075		5.8048
15	0.1886		5.9935
16	0.1715		6.1650
17	0.1559		6.3209
18	0.1417		6.4626
19	0.1288		6.5914
20	0.1171		6.7086
21	0.1065		6.8150
22	0.0968		6.9118
23	0.0880		6.9998
24	0.0800		7.0799
25	0.0727		7.1526
Retention Value at End of 25th Year			0.0693

For example, using the shingle roof labor hours, the total labor hours for the 25-year period shown in Table 3 is 0.02210. The replacement task would occur in year 40 and is not included in the study period. The task of placing one new layer of shingles over the existing roof occurs in year 20. The labor hours value shown in Table 3, 0.02996, is multiplied by the present worth factor for year 20 shown in Table 10, 0.1171, to obtain a present worth labor hour of 0.00351. This value is now subtracted from the total period labor hours:  $0.02210 - 0.00351 = 0.01859$ . This figure represents the combination of all nonreplacement and high-cost tasks. Most computer programs allow the user to input one annual maintenance figure. To convert this present worth back into an equivalent annual figure, the 0.01859 is divided by the accumulated present worth value of 7.1526 shown at the bottom of Table 10 for a uniform value of 0.00259.

## 4 DATA BASE APPLICATION EXAMPLES

### Introduction

This chapter is divided into two sections. The first section defines the terminology used in the report and information needed to apply the labor hour, material cost and equipment hour resource data in this report. The second section gives specific examples using both the 10 percent present worth tables given in Appendix B and the 7 percent present worth tables given in Appendix A.

### Terminology

#### *Economic Studies*

Two basic types of economic studies are covered in this report: (1) general economic studies and (2) special energy-conservation studies.

General economic studies are conducted routinely as part of the design process for all military facilities. Such studies are normally performed for a 25-year period using a 10 percent discount rate and considering tasks to be performed mid-year. The Beneficial Occupancy Date (BOD) occurs approximately 3 years after the Date of Study (DOS) for most MILCON projects, and that is what is assumed in the example provided herein.

Special economic studies for the design of energy-consuming portions of a building are required by statute. Such studies analyze the use of extraordinary energy-saving design initiatives to conserve energy in new Federal facilities. The studies are normally performed for a 25-year period using a 7 percent discount rate considering all tasks to be performed at the end of the year. The BOD is normally assumed to occur on the DOS, in accordance with the provisions of the design criteria.

#### *Installation Labor Rates*

To perform an accurate cost analysis, the current shop effective labor rates and equipment rates per hour must be obtained from the installation. This information can be obtained from the DEH. Telephone numbers for the DEH are listed in the "Director of Engineering and Housing/Facilities, Engineer Assignments Roster" published yearly by the Office of the Chief of Engineers. Most installations maintain this information within their IFS data base; it can be obtained from the IFS data base administrator within the Management Engineering and Systems Branch.

#### *Initial Costs*

The initial construction costs can be obtained from the CACES Regional Unit Cost Manuals. The manuals are available from the district cost estimating section. When this manual is not available the cost estimates can be taken from other publications such as Means and Dodge.

#### *Geographical Location Adjustment Factors*

The Washington, DC-based material costs in the summary tables can be adjusted to a specific installation through the application of a geographical location adjustment factor. The factors are published

in AR 415-17 and updates are available through the PAX computer system (Area Cost Factor Newsletter) and through the Engineering Improvement Recommendation System (EIRS) Bulletin. The 1988 set of factors is given in Appendix D.

### *Inflation Factors*

The material costs and Washington, DC, total costs presented in Appendices A and B are in July 1988 dollars. The costs need to be adjusted to the date of study by applying an approved inflation factor obtained from the District cost estimating office.

### *Timing of Costs*

Figure 1 shows the relationship of DOS, BOD, and the end of the study (EOS) which is assumed to be a 25-year comparison period:




Figure 1. DOS, BOD, EOS relationship.

In Appendix B, costs are discounted 3 years from time of occurrence to DOS. M&R costs occur throughout a year and are costed at mid-year in accordance with established criteria for MILCON design. The basic present worth factor formula is:

$$PWF(BA) = \frac{1}{(1 + DR)^{(B + BA - C)}} \quad [Eq 1]$$

where PWF = present worth factor

BA = building age

DR = discount rate

B = years from DOS to BOD

C = task placement, either 0.5 for mid-year, or 0 for end of year.

The 10 percent present worth factor to bring costs from the mid-year of first year of occupancy to the DOS is  $1/(1.1)^{3.5} = 0.7164$  which is the first value in Table 10. If the DOS is not 3 years before BOD, Appendix B data can be adjusted. For example, if there is only 1 year between BOD and DOS (two less than the 3 years in the appendices), multiply this data by  $(1.1)^2$ . If there are 5 years (2 years more than the 3 years in the appendices), divide by  $(1.1)^2$ .

In Appendix A, the DOS and BOD are identical. M&R costs are assumed to occur at the end of the year as stipulated by regulations. The basic formula is:

$$PWF(BA) = \frac{1}{(1 + DR)^{(BA)}} \quad [Eq 2]$$



where PWF = present worth factor  
BA = building age  
DR = discount rate

### *Disposal Costs/Retention Value*

When disposal costs/retention value is considered, it should be expressed as a percentage of the initial cost occurring at the end of the study period. The present worth of this value can be subtracted from the final net present worth.

## **Examples**

### *Introduction*

This section contains one example for each of the basic uses for this life-cycle cost data. The first two examples demonstrate the procedures for calculating LCC for construction and maintenance and repair when the DOS is exactly 3 years before the BOD; the building is 25 years old at the end of the study; and installation resource costs are available from the installation. The third example demonstrates the procedures for calculating LCC for construction and maintenance and repair when data is not available from the installation and Washington, DC, cost data is to be applied. Examples 4 and 5 show how to adjust data to cover the case for which BOD is not 3 years after DOS. Example 6 shows how to use the data to generate input for other computer programs. Example 7 demonstrates the use for a project containing an extraordinary energy-saving design initiative to conserve energy.

Each example is presented in five sections:

1. Statement of the problem.
2. Identification of all installation-related information.
3. Identification of all component-related information.
4. Description of the present worth calculations.
5. A typical calculation worksheet.

### *Example 1: BOD 3 Years After DOS--Built-up Roof*

**Problem Statement.** This example demonstrates all steps using a built-up roof covering with an area of 10,000 sq ft. An apartment building for family housing is under design at Fort Eustis, VA. The DOS is July 1989. The projected BOD is July 1992. A 25-year life-cycle cost analysis using a 10 percent discount rate is required.

#### Installation-Related Data.

**Geographic Location Adjustment Factor.** The geographic location adjustment factor (LAF) can be obtained from the latest EIRS bulletin or from the Area Cost Factor Newsletter on the PAX computer system, as shown in Appendix D. The factors are indexed by state and then by location within the state. From Appendix D, for Virginia and Fort Eustis, the geographic LAF (or Area Cost Factor [ACF] Index) is 0.96.

**Inflation.** The cost data in Appendix B is expressed in July 1988 dollars. Since the date of the study is July 1989, all cost figures must be adjusted. A telephone conversation with a District cost

estimator has revealed that the costs have risen 2 percent from July 1988 to July 1989. This means that all costs need to be multiplied by a 1.02 cost adjustment factor.

*Resource Rates.* The labor and equipment resources in Appendix B are expressed in hours per unit measure. To obtain accurate cost figures the designer called the Fort Eustis DEH-MES branch. The July 1989 rates of \$13.50/hr for a roofer and \$3.00/hr for a roofing maintenance truck were obtained.

#### Component Information.

*Size.* The designer is considering a built-up roof covering with an area of 10,000 sq ft.

*Initial Costs.* The designer obtained a CACES unit price manual from the cost estimator. For the built-up roofing component, a cost of \$0.998/sq ft was obtained. (Note. if the component is not found in the *CACES Unit Price Manual*, other books such as Means and Dodge can be used.)

*Retention Value.* The average life of a built-up roof is 28 years, as shown for the replacement task in Appendix B. At the end of the 25-year analysis period, the roof covering would still have 3 years of life remaining or  $3/28 = 11$  percent of its useful life. The salvage value can be considered to be 11 percent of the initial cost of \$0.998 per square foot, or \$0.1098/sq ft.

Present Worth Calculations. Three factors must be considered when performing a present worth calculation: initial cost, maintenance costs, and salvage value. Each factor is discussed below.

*Initial Costs.* The average construction project would normally be completed in 1 year. The contractor normally receives progress payments for work completed throughout the construction period. The initial cost of \$0.998/sq ft is assumed to occur at the midpoint of construction during the year before BOD. The present worth factor at midyear for the year before BOD is given in the second column of Table 10 as 0.7880. The present worth of the initial cost would be the initial cost multiplied by the present worth factor 1 year before BOD or  $\$0.998/\text{sq ft} \times 0.7880 = \$0.78642/\text{sq ft}$ .

*25-Year Maintenance Cost.* The total 25-year maintenance cost is composed of three parts: labor, material, and equipment. Labor costs per square foot are equal to the labor hours per square foot obtained from Appendix B, multiplied by the installation labor hourly rate. This would be 0.03987 hr/sq ft multiplied by a labor rate of \$13.50/hr, which is equal to \$0.53824/sq ft.

$$\text{Labor} = 0.03987 \text{ hours/sq ft} \times \$13.50/\text{hr} = \$0.53824/\text{sq ft} \quad [\text{Eq } 3]$$

Material costs per square foot are equal to the material dollars in Washington, DC, base per square foot obtained from Appendix B, multiplied by the geographic LAF from Appendix D and then multiplied by the inflation factor. This would be \$0.37166 DC-based dollars per square foot multiplied by a geographic LAF of 0.96 and a cost escalation factor (CEF) of 1.02 which is equal to \$0.36393/sq ft.

$$\text{Material} = \$0.37166/\text{sq ft} \times 0.96 \times 1.02 = \$0.36393/\text{sq ft} \quad [\text{Eq } 4]$$

Equipment costs per square foot are equal to the equipment hours per square foot obtained from Appendix B, multiplied by the installation equipment hourly rate. This would be 0.01994 hr/sq ft multiplied by an equipment rate of \$3.00/hr which is equal to \$0.05982/sq ft.

$$\text{Equipment} = 0.01994 \text{ hr/sq ft} \times \$3.00/\text{hr} = \$0.05982/\text{sq ft} \quad [\text{Eq } 5]$$

The total maintenance cost per square foot would be the labor cost (\$0.53825/sq ft) plus the material cost (\$0.36393/sq ft) plus the equipment cost (\$0.05982/sq ft) or \$0.96199/sq ft.

$$\text{Total} = \$0.53824/\text{sq ft} + \$0.36393/\text{sq ft} + \$0.05982/\text{sq ft} = \$0.96199/\text{sq ft} \quad [\text{Eq } 6]$$

This total has already been discounted to the DOS since all figures on the left side of the table in Appendix B are expressed in terms of the DOS.

**Retention Value.** The DOS present worth for the retention value would be the expected retention value of \$0.10980/sq ft multiplied by the end-of-year present worth factor for the end of study year (EOS) obtained from Table 10, 0.06930, which produces a cost of \$0.00761/sq ft.

**Total Life Cycle Cost for Construction and Maintenance and Repair.** The total life-cycle cost (LCC) per square foot for the DOS is the sum of the present worth costs for the initial cost of \$0.78642/sq ft plus the 25-year maintenance cost of \$0.96199/sq ft minus the retention value of \$0.00761/sq ft.

$$\text{Total LCC} = \$0.78642/\text{sq ft} + \$0.96199/\text{sq ft} - \$0.00761/\text{sq ft} = \$1.74080/\text{sq ft} \quad [\text{Eq 7}]$$

The total dollar cost would be the LCC per square foot of \$1.74080 multiplied by the roof area of 10,000 sq ft producing a total cost of \$17,408.00.

**Calculation Sheet.** A typical calculation sheet is shown in Table 11.

**Table 11**

**Calculation Sheet - Example 1**

	<u>Calculation Column</u>	<u>Subfactor Cost/sq ft</u>	<u>Factor Cost/sq ft</u>	<u>Total Cost</u>
<u>Initial Cost</u>				
Initial Cost	\$ .998/sq ft			
PWF for BOD-1	x <u>.7880</u>			
Initial cost/sq ft			\$ .78642/sq ft	
<u>25-Year Maintenance Cost</u>				
PW - Labor	.03987hr/sq ft			
Labor Rate	x <u>\$13.50/hr</u>			
Labor cost/sq ft		\$ .53824/sq ft		
PW - Material	\$ .37166/sq ft			
LAF	x .96			
CEF	x <u>1.02</u>			
Material cost/sq ft		\$ .36393/sq ft		
PW - Equipment	.01994 hrs/sq ft			
Equipment Rate	x <u>\$3.00/hr</u>			
Equipment cost/sq ft		\$ .05982/sq ft		
Maintenance cost/sq ft			\$ .96199/sq ft	
<u>Retention Value</u>				
Initial Cost	\$ .998/sq ft			
Remaining Life	x .11			
PWF for EOS	x .06930			
Retention cost/sq ft			- <u>\$ .00761/sq ft</u>	
Life Cycle Cost/sq ft			\$1.74080 sq ft	
Area			x <u>10,000 sq ft</u>	
<u>TOTAL Life Cycle Cost</u>				\$17,408.00

### *Example 2: BOD 3 Years After DOS--Shingle Roof*

Problem Statement. This example demonstrates all steps using a shingle roof covering with an area of 10,000 sq ft. An apartment building for family housing is under design at Fort Eustis, VA. The DOS is July 1989. The projected BOD is July 1992, 3 years after DOS. A 25-year LCC analysis using a 10 percent mid-year discount rate is required.

#### Installation Related Data.

*Geographic location adjustment factor.* The geographic LAF can be obtained from the latest EIRS bulletin on the PAX computer system as shown in Appendix D. The factors are indexed by state and then by location within the state. From Appendix D for Virginia and Fort Eustis, the geographic LAF (or ACF Index) is 0.96.

*Inflation.* The cost data in Appendix B is expressed in July 1988 dollars. Since the DOS is July 1989, all cost figures must be adjusted. A telephone conversation with a District cost estimator has revealed that the costs have risen 2 percent from July 1988 to July 1989. This means that all costs need to be multiplied by a 1.02 cost adjustment factor.

*Resource Rates.* The labor and equipment resources in Appendix B are expressed in hours per unit measure. To obtain accurate cost figures the designer called the Fort Eustis DEH-MES branch. The July 1989 rates for a roofer, \$13.50/hr and the roofing maintenance truck, \$3.00/hr, were obtained.

#### Component Information.

*Size.* The designer is considering a shingle roof covering with an area of 10,000 square feet.

*Initial Costs.* The designer obtained a *CACES Unit Price Manual* from the cost estimator. For the shingle roofing component, a cost figure of \$0.660/sq ft was obtained. (Note. if the component is not found in the *CACES Unit Price Manual*, other books such as Means and Dodge can be used.)

*Retention Value.* The average life of a shingle roof is 40 years as shown for the replacement table in Appendix B. At the end of the 25-year analysis period, the roof covering would still have 15 years of life remaining or  $15/40 = 37.5$  percent of its useful life. The salvage value can be considered to be 37.5 percent of the initial cost of \$0.660/sq ft or \$0.2475/sq ft.

Present Worth Calculations Three factors need to be considered when performing a present worth calculation: initial cost, maintenance costs, and salvage value.

Each factor is discussed below.

*Initial Costs.* The average construction project would normally be completed in 1 year. The contractor normally receives progress payments for work completed throughout the construction period. The initial cost of \$0.660/sq ft is assumed to occur at the midpoint of construction during the year before BOD. The present worth factor at midyear for the year before BOD is given in the second column of Table 10 as 0.7880. The present worth of the initial cost would be the initial cost multiplied by the present worth factor 1 year before BOD or  $\$0.660/\text{sq ft} \times 0.7880 = \$0.52008/\text{sq ft}$ .

**25-Year Maintenance Cost.** The total 25-year maintenance cost is composed of three parts: labor, material, and equipment. Labor costs per square foot are equal to the labor hours per square foot obtained from Appendix B multiplied by the installation labor hourly rate. This would be 0.02222 hr/sq ft multiplied by a labor rate of \$13.50/hr which is equal to \$0.29997/sq ft.

$$\text{Labor} = 0.02222 \text{ hr/sq ft} \times \$13.50/\text{hr} = \$0.29997/\text{sq ft} \quad [\text{Eq 8}]$$

Material costs per square foot are equal to the material dollars in Washington, DC, base per square foot obtained from Appendix B, multiplied by the geographic LAF from Appendix D and then multiplied by the inflation factor. This would be \$0.22132 DC-based dollars per square foot multiplied by a geographic LAF of 0.96 and a CEF of 1.02 which is equal to \$0.21672/sq ft.

$$\text{Material} = \$0.22132/\text{sq ft} \times 0.96 \times 1.02 = \$0.21672/\text{sq ft} \quad [\text{Eq 9}]$$

Equipment costs per square foot are equal to the equipment hours per square foot obtained from Appendix B, multiplied by the installation equipment hourly rate. This would be 0.01112 hr/sq ft multiplied by an equipment rate of \$3.00/hr which is equal to \$0.03333/sq ft.

$$\text{Equipment} = 0.01111 \text{ hr/sq ft} \times \$3.00/\text{hr} = \$0.03333/\text{sq ft} \quad [\text{Eq 10}]$$

The total maintenance cost per square foot would be the labor cost (\$0.29997/sq ft) plus the material cost (\$0.21672/sq ft) plus the equipment cost (\$0.03333/sq ft), or \$0.55002/sq ft.

$$\text{Total} = \$0.29997/\text{sq ft} + \$0.21672/\text{sq ft} + \$0.03333/\text{sq ft} = \$0.55002/\text{sq ft} \quad [\text{Eq 11}]$$

This total has already been discounted to the DOS since all figures on the left side of the table in Appendix B are expressed in terms of the DOS.

**Retention Value.** The DOS present worth for the retention value would be the expected retention value, \$0.2475/sq ft, multiplied by the end of year present worth factor for the EOD obtained from Table 10, 0.06930, which produces a cost of \$0.01715/sq ft.

**Total Life Cycle Cost for Construction and Maintenance and Repair.** The total LCC per square foot for the DOS is the sum of the present worth costs for the initial cost of \$0.52008/sq ft plus the 25-year maintenance cost of \$0.55002/sq ft minus the retention value of \$0.01715/sq ft.

$$\text{Total LCC} = \$0.52008/\text{sq ft} + \$0.55002/\text{sq ft} - \$0.01715/\text{sq ft} = \$1.05295/\text{sq ft} \quad [\text{Eq 12}]$$

The total dollar cost would be the LCC per square foot, \$1.05295, multiplied by the roof area, 10,000 sq ft, producing a total cost of \$10,529.50.

Calculation Sheet. A typical calculation sheet is shown in Table 12.

*Example 3: BOD 3 Years After DOS -- Washington, DC Rate Applied*

Problem Statement This example demonstrates all steps using a built-up roof covering with an area of 10,000 sq ft. An apartment building for family housing is under design at Fort Eustis, VA. The DOS is July 1989. The projected BOD is July 1992, three years after DOS. A 25-year life-cycle cost analysis using a 10 percent mid-year discount rate is required.

**Table 12**  
**Calculation Sheet - Example 2**

	<u>Calculation Column</u>	<u>Subfactor Cost/sq ft</u>	<u>Factor Cost/sq ft</u>	<u>Total Cost</u>
<u>Initial Cost</u>				
Initial Costs	\$ .660/sq ft			
PWF for BOD-1	x <u>.7880</u>			
Initial Costs/sq ft			\$ .52008/sq ft	
<u>25-Year Maintenance Cost</u>				
PW - Labor	.02222 hr/sq ft			
Labor Rate	x <u>\$13.50/hr</u>			
Labor cost/sq ft		\$ .29997/sq ft		
PW - Material	\$ .22132/sq ft			
LAF	x .96			
CEF	x <u>1.02</u>			
Material cost/sq ft		\$ .21672/sq ft		
PW - Equipment	.01111 hr/sq ft			
Equipment Rate	x <u>\$3.00/hr</u>			
Equipment cost/sq ft		\$ .03333/sq ft		
Maintenance Cost/sq ft			\$ .55002/sq ft	
<u>Retention Value</u>				
Initial Cost		\$ .660/sq ft		
Remaining Life		x .375		
PWF for EOS		x .06930		
Retention value/sq ft			- \$ .01715/sq ft	
Life Cycle Cost/sq ft			\$1.05295/sq ft	
Area		x <u>10,000 sq ft</u>		
TOTAL Life Cycle Cost				\$10,529.50

The designer wishes to perform a rough cost estimate without calling the installation to obtain cost information. It should be understood that the installation's costs may vary significantly from the Washington, DC, costs and the rough calculations may be misleading. However, if the designer is going to compare several types of components such as built-up, slate, and shingle roofs--all of which involve the identical trade such as a roofer--the comparisons may be quite accurate.

#### Installation-Related Data.

*Geographic Location Adjustment Factor.* The geographic LAF can be obtained from the latest EIRS bulletin or from the Area Cost Factor Newsletter on the PAX computer system as shown in Appendix D. The factors are indexed by state and then by location within the state. From Appendix D, for Virginia and Fort Eustis, the geographic LAF (or ACF Index) is 0.96.

*Inflation.* The cost data in Appendix B is expressed in July 1988 dollars. Since the DOS is July 1989, all cost figures must be adjusted. A telephone conversation with a District cost estimator has revealed that the costs have risen 2 percent from July 1988 to July 1989. This means that all costs need to be multiplied by a 1.02 cost adjustment factor.

**Resource Rates.** The designer wishes to perform a rough calculation using the Washington, DC, labor and equipment rates rather than calling the installation.

#### Component Information.

**Size.** The designer is considering a built-up roof covering with an area of 10,000 sq ft.

**Initial Costs.** The designer obtained a *CACES Unit Price Manual* from the cost estimator. For the built-up roofing component, a cost figure of \$0.998/sq ft was obtained. (Note: if the component is not found in the *CACES Unit Price Manual*, other books such as Means and Dodge can be used.)

**Retention Value.** The average life of a built-up roof is 28 years, as shown for the replacement task in Appendix B. At the end of the 25-year analysis period, the roof covering would still have 3 years of life remaining or  $3/28 = 11$  percent of its useful life. The salvage value can be considered to be 11 percent of the initial cost of \$0.998/sq ft or \$0.10980/sq ft.

**Present Worth Calculations.** Three factors need to be considered when performing a present worth calculation: initial cost, maintenance costs, and salvage value. Each factor is discussed below.

**Initial Costs.** The average construction project would normally be completed in 1 year. The contractor normally receives progress payments for work completed throughout the construction period. The initial cost of \$0.998/sq ft is assumed to occur at the midpoint of construction during the year before BOD. The present worth factor at midyear for the year before BOD is given in the second column of Table 10 as 0.7880. The present worth of the initial cost would be the initial cost multiplied by the present worth factor 1 year before BOD or  $\$0.998/\text{sq ft} \times 0.7880 = \$0.78642/\text{sq ft}$ .

**25-Year Maintenance Cost.** The total 25-year maintenance cost for Fort Eustis can be calculated by taking the Washington, DC, total cost per square foot, \$1.25, and multiplying by the location adjustment factor (0.96) producing a cost of \$1.20/sq ft.

**Retention Value.** The DOS present worth for the retention value would be the expected retention value of \$0.10980/sq ft multiplied by the end of year present worth factor for the EOD obtained from Table 10, 0.06930, which produces a cost of \$0.00761/sq ft.

**Total LCC for Construction and Maintenance and Repair.** The total LCC per square foot for the DOS is the sum of the present worth costs for the initial cost of \$0.78642/sq ft plus the 25-year maintenance cost of \$1.20/sq ft minus the retention value of \$0.00761/sq ft.

$$\text{Total LCC} = \$0.78642/\text{sq ft} + \$1.20/\text{sq ft} - \$0.00761/\text{sq ft} = \$1.97881/\text{sq ft} \quad [\text{Eq 13}]$$

The total dollar cost would be the LCC per square foot, \$1.97881, multiplied by the roof area, 10,000 sq ft, producing a total cost of \$19,788.10

**Calculation Sheet.** A typical calculation sheet is shown in Table 13.

Table 13

## Calculation Sheet - Example 3

	Calculation Column	Subfactor Cost/sq ft	Factor Cost/sq ft	Total Cost
<u>Initial Cost</u>				
Initial Cost	\$ .998/sq ft			
PWF for BOD	x .7880			
Initial Cost/sq ft			\$ .78642/sq ft	
<u>25-Year Maintenance Cost</u>				
PW Total	\$1.25/sq ft			
LAF	x .96			
Maintenance Cost/sq ft			\$1.20/sq ft	
<u>Retention Value</u>				
Initial Cost	\$ .988/sq ft			
Remaining Life	x .11			
PWF for EOS	x .06930			
Retention value/sq ft			- \$ .00761/sq ft	
Life Cycle cost/sq ft			\$1.97881/sq ft	
Area		x 10,000 sq ft		
TOTAL Life Cycle Cost				\$19,788.10

*Example 4: DOS Less Than 3 Years Before BOD*

Perform the calculations as shown in Examples 1 through 3. The answers are lower than the actual DOS answers. The calculated values must be adjusted by multiplying by the formula:

$$(1 + DR)^{(3-A)} \quad [Eq 14]$$

where DR = discount rate

3 = years between DOS and BOD given in the tables

A = actual years between DOS and BOD.

For example, using the answer of \$17,408.00 in Example 1 and assuming 1 year between BOD and DOS with discount rate = 10% (0.10), the formula would be  $(1.10)^{(3-1)} = (1.1)^{(2)} = 1.21$ . The correct answer would be \$17,408.00 x 1.21 = \$21,063.68

*Example 5: DOS Greater Than 3 Years Before BOD*

Perform the calculation as shown in Examples 1 through 3. The answers are larger than the actual DOS answers. The calculated values must be adjusted by dividing by the formula:

$$(1 + DR)^{(A-3)} \quad [Eq 15]$$



where DR = discount rate

3 = years between DOS and BOD given in the tables

A = actual years between DOS and BOD

For example, using the answer of \$17,408.00 in Example 1 and assuming 5 years between BOD and DOS with  $d = 10$  percent (0.10), the formula would be  $(1.10)^{(5 \cdot 3)} = (1.10)^{(2)} = 1.21$ . The correct answer would be  $\$17,408.00 + 1.21 = \$14,686.78$

#### *Example 6: Computer Input--BOD 3 Years After DOS (Built-up Roof)*

**Problem Statement.** This example demonstrates all steps using a built-up roof covering with an area of 10,000 sq ft. An apartment building for family housing is under design at Fort Eustis, VA. The BOD is July 1992. The DOS is 3 years before BOD or July 1989. A 25-year LCC analysis using a 10 percent discount rate is required. A computer program, such as the Corps' LCCID, that requires an annual maintenance figure and high cost tasks will be used.

#### Installation Related Data.

**Geographic Location Adjustment Factor.** The LAF can be obtained from the latest EIRS bulletin or from the Area Cost Factor Newsletter on the PAX computer system as shown in Appendix D. The factors are indexed by state and then by location within the state. From Appendix D, for Virginia and Fort Eustis, the geographic LAF (or ACF Index) is 0.96.

**Inflation.** The cost data in Appendix B is expressed in July 1988 dollars. Since the DOS is July 1989, all cost figures must be adjusted. A telephone conversation with a District cost estimator has revealed that the costs have risen 2 percent from July 1988 to July 1989. This means that all costs need to be multiplied by a 1.02 cost adjustment factor.

**Resource Rates.** The labor and equipment resources in Appendix B are expressed in hours per unit measure. To obtain accurate cost figures the designer called the Fort Eustis DEH-MES branch. The July 1989 rates of \$13.50/hr for a roofer and \$3.00/hr for a roofing maintenance truck were obtained.

#### Component Information.

**Size.** The designer is considering a built-up roof covering with an area of 10,000 sq ft.

**Initial Costs.** The designer obtained a *CACES Unit Price Manual* from the cost estimator. By looking up the built-up roofing component, a cost of \$0.998/sq ft was obtained. (Note: if the component is not found in the *CACES Unit Price Manual*, other books such as Means and Dodge can be used.)

**Retention Value.** The average life of a built-up roof is 28 years, as shown for the replacement table in Appendix B. At the end of the 25-year analysis period, the roof covering would still have 3 years of life remaining or  $3/28 = 11$  percent of its useful life. The salvage value can be considered to be 11 percent of the initial cost of \$0.998/sq ft, or \$0.1098/sq ft.

**Data Entry Calculations** Four factors need to be considered when performing a present worth calculation: initial cost, annual maintenance costs, high costs, and salvage value. Each factor is discussed below.

*Initial Costs.* The initial cost of \$0.998/sq ft is estimated from CACES as discussed above.

*25-Year Maintenance Cost.* The total annual 25-year maintenance cost is composed of three parts: labor, material, and equipment. Annual labor costs per square feet are equal to the labor hours per square foot obtained from Appendix B, multiplied by the installation labor hourly rate. This would be 0.00488 hr/sq ft/yr multiplied by a labor rate of \$13.50/hr, which is equal to \$0.06575/sq ft/yr.

$$\text{Labor} = 0.00487 \text{ hr/sq ft/yr} \times \$13.50/\text{hr} = \$0.06575/\text{sq ft/yr} \quad [\text{Eq 16}]$$

Annual material costs per square foot are equal to the material dollars in Washington, DC, base per square foot obtained from Appendix B, multiplied by the geographic LAF from Appendix D, and then multiplied by the inflation factor. This would be \$0.03171 DC-based dollars per square foot per year multiplied by a geographic LAF of 0.96 and a CEF of 1.02, or \$0.03105/sq ft/yr.

$$\text{Material} = \$0.03171/\text{sq ft/yr} \times 0.96 \times 1.02 = \$0.03105/\text{sq ft/yr} \quad [\text{Eq 17}]$$

Annual equipment costs per square foot are equal to the equipment hours per square foot obtained from Appendix B, multiplied by the installation equipment hourly rate. This would be 0.00244 hr/sq ft/yr multiplied by an equipment rate of \$3.00/hr, which is equal to \$0.00732/sq ft/yr.

$$\text{Equipment} = 0.00244 \text{ hr/sq ft/yr} \times \$3.00/\text{hr} = \$0.00732/\text{sq ft/yr} \quad [\text{Eq 18}]$$

The total annual maintenance cost per square foot would be the labor cost (\$0.06575/sq ft/yr) plus the material cost (\$0.03105/sq ft/yr), plus the equipment cost (\$0.00732/sq ft/yr) or \$0.104222/sq ft/yr.

$$\text{Total: } \$0.06575/\text{sq ft/yr} + \$0.03105/\text{sq ft/yr} + \$0.00732/\text{sq ft/yr} = \$0.10412/\text{sq ft/yr} \quad [\text{Eq 19}]$$

The total cost figure for the uniform maintenance cost for computer entry is obtained by multiplying the total of \$0.10409 by the square footage of 10,000 sq ft, resulting in an annual cost of \$10,409.00.

*High Cost.* There is one high-cost task for built-up roofing. This task occurs in the 14th year. The resources required to perform this task are given below.

The labor resources are obtained by multiplying the labor hours per square foot, 0.02414, by the labor rate, \$13.50/hr, resulting in \$0.32589/sq ft.

$$\text{Labor} = 0.02414 \text{ hr/sq ft} \times \$13.50/\text{hr} = \$0.32589/\text{sq ft} \quad [\text{Eq 20}]$$

The material resources are obtained by multiplying the material cost in DC base, \$0.69960/sq ft, by the cost escalation factor, 1.02, and the location adjustment factor, 0.96, resulting in \$0.68505/sq ft.

$$\text{Material} = \$0.69960/\text{sq ft} \times 1.02 \times 0.96 = \$0.68505/\text{sq ft} \quad [\text{Eq 21}]$$

Equipment resources are obtained by multiplying the equipment resources of 0.01207 hr/sq ft by the equipment rate of \$3.00/hr resulting in \$0.03621/sq ft.

$$\text{Equipment} = 0.01207 \text{ hr/sq ft} \times \$3.00/\text{hr} = \$0.03621/\text{sq ft} \quad [\text{Eq 22}]$$

Total cost for this one task would be the sum of the labor, material, and equipment costs.

$$\text{Total} = \$0.32589/\text{sq ft} + \$0.68505/\text{sq ft} + \$0.03621/\text{sq ft} = \$1.04715/\text{sq ft} \quad [\text{Eq 23}]$$

The total cost figure for computer entry is obtained by multiplying the total of \$1.04715/sq ft by the square footage of 10,000 for a cost of \$10,471.50 occurring in year 14.

*Retention Value.* The expected retention value is calculated as follows: at the end of the 25-year analysis period, the roof covering would still have 3 years of life remaining or  $3/28 = 11$  percent of its useful life. The value is then 11 percent of the initial cost of \$0.998/sq ft or \$0.10978/sq ft.

The calculated values are entered into the computer and the computer performs the appropriate discounting.

Calculation Sheet: A typical calculation sheet is shown in Table 14.

#### *Example 7: Extraordinary Energy-Saving Design Initiatives--Built-up Roof*

Problem Statement. This example demonstrates all steps involved in using the summary tables in Appendix A for the conventional built-up roof covering alternative. An apartment building for family housing is under design at Fort Eustis, VA. The designers are considering the use of a new-technology energy conserving, low maintenance roof, in place of a conventional built-up roof, and will determine which is more cost effective on the basis of a life-cycle cost analysis. The roof area is 10,000 square feet. The DOS is July 1989. The analysis period is 25 years. In accordance with established criteria for energy-conservation studies, the BOD is assumed to occur on the DOS (July 1989); all costs are assumed occur at the end of the year in which they are projected occur; and the discount rate for the present worth calculations is assumed to be 7 percent.

#### Installation Related Data.

*Geographic Location Adjustment Factor.* The geographic LAF can be obtained from the latest EIRS bulletin or from the Area Cost Factor Newsletter on the PAX computer system as shown in Appendix D. The factors are indexed by state and then by location within the state. From Appendix D, for Virginia and Fort Eustis, the geographic LAF (or ACF Index) is 0.96.

*Inflation.* The cost data in Appendix A is expressed in July 1988 dollars. Since the DOS is July 1989, all cost figures must be adjusted. A telephone conversation with a District cost estimator has revealed that the costs have risen 2 percent from July 1988 to July 1989. This means that all costs need to be multiplied by a 1.02 cost adjustment factor.

Table 14

## Calculation Sheet - Example 6

ANNUAL MAINTENANCE

	<u>Calculation Column</u>	<u>Subfactor Cost/sq ft</u>	<u>Factor Cost/sq ft</u>	<u>Total Cost</u>
<u>Initial Cost</u>				
Initial Cost/sq ft	\$ .998/sq ft			
Area	x <u>10,000 sq ft</u>			
Initial Cost			\$9,980	
<u>25-Year Annual Maintenance</u>				
Labor hours/sq ft	.00488 hr/sq ft			
Labor Rate	x <u>\$13.50/hr</u>			
Labor cost/sq ft		\$ .06575/sq ft		
Material/sq ft	\$ .03171/sq ft			
AF	x .96			
CEF	x <u>1.02</u>			
Material cost/sq ft		.031021		
Equipment	.00244 hr/sq ft			
Equipment Rate	x <u>\$3.00/hr</u>			
Equipment cost/sq ft		\$ .00732/sq ft		
Annual Maintenance/sq ft		\$ .10412/sq ft		
Square Feet		x <u>10,000 sq ft</u>		
<u>TCTAL Annual Maintenance</u>			\$10,412.00	
<u>HIGH COST TASK</u>				
Labor	.02414 hr/sq ft			
Labor Rate	x <u>\$13.50/hr</u>			
Labor cost/sq ft		\$ .32589/sq ft		
Material	\$ .069960/sq ft			
LAF	x .96			
CEF	x <u>1.02</u>			
Materials cost/sq ft		\$ .68505/sq ft		
Equipment	.01207 hr/sq ft			
Equipment Rate	<u>\$3.00/hr</u>			
Equipment/sq ft		<u>\$ .03621/sq ft</u>		
Maintenance cost/sq ft			\$1.04715/sq ft	
Square Feet		x 10,000 sq ft		
<u>TOTAL Maintenance Cost for High Cost Task</u>			\$10,471.50	
<u>Retention Value</u>				
Initial Cost	\$ .988/sq ft			
Remaining Life	x <u>.11</u>			
Total/sq ft		\$ .10978/sq ft		
Square Feet		x 10,000 sq ft		
Retention Value			\$1,097.80	

**Resource Rates:** The labor and equipment resources in Appendix B are expressed in hours per unit measure. To obtain accurate cost figures, the designer called the Fort Eustis DEH-MES branch. The July 1989 rates of \$13.50/hr for a roofer and \$3.00/hr for a roofing maintenance truck were obtained.

### Component Information.

**Size.** The designer is considering a built-up roof covering with an area of 10,000 sq ft.

**Initial Costs.** The designer obtained a *CACES Unit Price Manual* from the cost estimator. For the built-up roofing component a cost figure of \$0.998/sq ft was obtained. (Note: if the component is not found in the *CACES Unit Price Manual*, other books such as Means and Dodge can be used.)

**Retention Value.** The average life of a built-up roof is 28 years as shown for the replacement task in Appendix B. At the end of the 25-year analysis period, the roof covering would still have 3 years of life remaining or  $3/28 = 11$  percent of its useful life. The retention value can be considered to be 11 percent of the initial cost of \$0.998/sq ft or \$0.10978/sq ft.

**Present Worth Calculations.** The following factors are considered in performing the present worth calculation: initial cost, maintenance costs, and salvage value. Each factor is discussed below.

**Initial Costs.** The initial cost of \$0.998/sq ft is assumed to occur on the BOD/DOS in accordance with established criteria for energy conservation studies.

**25-Year Maintenance Cost.** The total 25-year maintenance cost is composed of three parts: labor, material, and equipment. Labor costs per square foot are equal to the labor hours per square foot obtained from Appendix A multiplied by the installation labor hourly rate. This would be 0.06653 hr/sq ft multiplied by a labor rate of \$13.50/hr which is equal to \$0.89816/sq ft.

$$\text{Labor} = 0.06653 \text{ hours/sq ft} \times \$13.50/\text{hour} = \$0.89816/\text{sq ft} \quad [\text{Eq 24}]$$

Material costs per square foot are equal to the material dollars in Washington, DC, base per square foot obtained from Appendix A multiplied by the geographic LAF from Appendix D and then multiplied by the inflation factor. This would be \$0.64214 DC-based dollars per square foot multiplied by a geographic LAF of 0.96 and a CEF of 1.02, which is equal to \$0.62878/sq ft.

$$\text{Material} = \$0.64214/\text{sq ft} \times 0.96 \times 1.02 = \$0.62878/\text{sq ft} \quad [\text{Eq 25}]$$

Equipment costs per square foot are equal to the equipment hours per square foot obtained from Appendix A multiplied by the installation equipment hourly rate. This would be 0.03327 hr/sq ft multiplied by an equipment rate of \$3.00/hr, which is equal to \$0.09981/sq ft.

$$\text{Equipment} = 0.03327 \text{ hr/sq ft} \times \$3.00/\text{hr} = \$0.09981/\text{sq ft} \quad [\text{Eq 26}]$$

The total maintenance cost per square foot would be the labor cost (\$0.89816/sq ft) plus the material cost (\$0.62878/sq ft) plus the equipment cost (\$0.09981/sq ft), or \$1.62675/sq ft.

$$\text{Total} = \$0.89816/\text{sq ft} + \$0.62878/\text{sq ft} + \$0.09981/\text{sq ft} = \$1.62675/\text{sq ft} \quad [\text{Eq 27}]$$

This total has already been discounted to the date of study since all figures on the left side of the table in the Appendix are expressed in terms of the DOS.

*Retention Value.* The DOS present worth for the retention value would be the expected retention value of \$0.10978/sq ft multiplied by the end of year present worth factor for the EOD of 0.1842 obtained from Table 9 which produces a cost of \$0.02022/sq ft.

*Total Life Cycle Cost for Construction and Maintenance and Repair.* The total LCC per square foot for the DOS is the sum of the present worth costs for the initial cost of \$0.998/sq ft plus the 25-year maintenance cost of \$1.62675/sq ft minus the salvage value of \$0.02022/sq ft.

$$\text{Total LCC} = \$0.998/\text{sq ft} + \$1.62675/\text{sq ft} - \$0.02022/\text{sq ft} = \$2.60451/\text{sq ft} \quad [\text{Eq 28}]$$

The total dollar cost would be the LCC per square foot of \$2.60451 multiplied by the roof area of 10,000 sq ft producing a total cost of \$26,045.10.

Calculation Sheet. A typical calculation sheet is shown in Table 15.

Table 15

Calculation Sheet - Example 7

	<u>Calculation Column</u>	<u>Subfactor Cost/sq ft</u>	<u>Factor Cost/sq ft</u>	<u>Total Cost</u>
<u>Initial Cost</u>				
Initial Cost			\$ .998/sq ft	
<u>25 Year Maintenance Cost</u>				
PW - Labor	.06653 hr/sq ft			
Labor Rate	x <u>\$13.50/hr</u>			
Labor cost/sq ft		\$ .89816/sq ft		
PW - Material	\$.64214/sq ft			
LAF	x .96			
CEF	x <u>1.02</u>			
Material cost/sq ft		\$ .62878/sq ft		
PW - Equipment	.03327 hr/sq ft			
Equipment Rate	x <u>\$3.00/hr</u>			
Equipment cost/sq ft	<u>\$.09981/sq ft</u>			
Maintenance cost/sq ft			\$1.62675/sq ft	
<u>Retention Value</u>				
Initial Cost	\$ .998/sq ft			
Remaining Life	x .11			
PWF for EOS	x .1842			
Retention value/sq ft		- <u>\$.02022/sq ft</u>		
Life Cycle Cost/sq ft			\$2.60451/sq ft	
Area	x <u>10,000 sq ft</u>			
<u>TOTAL Life Cycle Cost</u>				\$26,045.10

## REFERENCES

- Army Regulation (AR) 11-18, *The Cost and Economic Analysis Program* (Headquarters, Department of the Army, 7 May 1990).
- AR 11-28, *Economic Analysis and Program Evaluation for Resource Management* (HQDA, December 1975).
- AR 415-17, *Cost Estimating for Military Programming* (Headquarters, Department of the Army, 15 February, 1980).
- AR 420-16, *Facilities Engineering Reports*, 30 September, 1987.
- Military Handbook (MIL-HDBK) 1190, *Facility Planning and Design Guide* (Department of Defense, 1 September, 1987).
- Neathammer, R.D., *Life-Cycle Cost Database Design and Sample Cost Data Development*, Interim Report P-120/-ADA0997222 (U.S. Army Construction Engineering Research Laboratory [USACERL], February 1981).
- Neathammer, R.D., *Life-Cycle Cost Database: Vol I, Design, and Vol II, Sample Data Development*, Technical Report P-139/ADA126644 and ADA126645 (USACERL, January 1983), Appendices E through G.
- Neely, E.S., et al., *Building Component Maintenance and Repair Data Base: Architectural Systems*, Special Report P-91/27 (USACERL, May 1991).
- Neely, E.S., et al., *Building Component Maintenance and Repair Data Base: Electrical Systems*, Special Report P-91/19 (USACERL, May 1991).
- Neely, E.S., et al., *Building Component Maintenance and Repair Data Base: Heating, Ventilation, and Air-Conditioning Systems*, Special Report P-91/22, (USACERL, May 1991).
- Neely, E.S., et al., *Building Component Maintenance and Repair Data Base: Plumbing Systems*, Special Report P-91/30 (USACERL, May 1991).
- Neely, E.S., et al., *Building Maintenance and Repair Data for Life-Cycle Cost Analyses: Electrical Systems*, Special Report P-91/26 (USACERL, May 1991).
- Neely, E.S., et al., *Building Maintenance and Repair Data for Life-Cycle Cost Analyses: Heating, Ventilation, and Air-Conditioning Systems*, Special Report P-91/20 (USACERL, May 1991).
- Neely, E.S., et al., *Building Maintenance and Repair Data for Life-Cycle Cost Analyses: Plumbing Systems*, Special Report P-91/24 (USACERL, May 1991).
- Neely, E.S., et al., *Maintenance Resource Prediction in the Facility Life-Cycle Process*, Technical Report P-91-10 (USACERL, March 1991).
- Neely, E.S., et al., *Maintenance Task Data Base for Buildings: Architectural Systems*, Special Report P-91/23 (USACERL, May 1991).
- Neely, E.S., et al., *Maintenance Task Data Base for Buildings: Electrical Systems*, Special Report P-91/25 (USACERL, May 1991).
- Neely, E.S., et al., *Maintenance Task Data Base for Buildings: Heating Ventilation, and Air-Conditioning Systems*, Special Report P-91/21 (USACERL, May 1991).

Neely, E.S., et al., *Maintenance Task Data Base for Buildings: Plumbing Systems*, Special Report P-91/18 (USACERL, May 1991).

Shahin, M.Y. and S.D. Kohn, Overview of the "PAVER" TM *Pavement Maintenance Management System*, Technical Manuscript M-310/ADA116311, (USACERL, March 1982).

TM 5-802-1, *Economic Studies for Military Construction--Applications* (Headquarters, Department of the Army [HQDA], 31 December 1986).



## LIST OF ACRONYMS

ACE	Assistant Chief of Engineers
AMS	Army Management System
APC	Account Processing Code
AR	Army Regulation
ARR	Annual Requirements Report
ASTM	American Society for Testing and Materials
BLAST	Building Loads Analysis and System Thermodynamics
BMAR	Backlog of Maintenance and Repair
BOD	Beneficial Occupancy Date
CA	Commercial Activities
CACES	Computer-Assisted Cost Estimating System
CONUS	Continental United States
DA	Department of the Army
DEH	Directorate of Engineering and Housing
DOD	Department of Defense
DOS	Date of Study
EA	Economic Analysis
EC	Engineering Construction
EIRS	Engineering Improvement Recommendation System
EOS	End of Study
EPS	Engineered Performance Standards
HQ-IFS	Headquarters - Integrated Facilities
HQDA	Headquarters Department of the Army
HVAC	Heating, Ventilation, and Air-Conditioning
IFS	Integrated Facilities System

IJO	Individual Job Order
LCC	Life-Cycle Cost
LCCID	Life-Cycle Cost in Design
M&R	Maintenance and Repair
MACOM	Major Command
MCA	Military Construction, Army
MRPM	Maintenance Resource Prediction Model
OCE	Office of the Chief of Engineers
PAVER	Pavement Maintenance Management System
PAX	Programming, Administration, and Execution System
PC	Personal Computer
PM	Preventive Maintenance
R&D	Research and Development
RAM	Random Access Memory
RMF	Recurring Maintenance Factor
RPI	Real Property Inventory
RPLANS	Real Property Planning System
RPMS	Real Property Management System
SO	Service Order
STANFINS	Standard Army Financial System
TB	Technical Bulletin
URR	Unconstrained Requirements Report
USACE	U.S. Army Corps of Engineers
USACERL	U.S. Army Construction Engineering Research Laboratory
USAEHSC	U.S. Army Engineering and Housing Support Center

**APPENDIX A:**

**LIFE-CYCLE COST ANALYSIS TABLE (7 PERCENT)**

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)														PAGE 1		
COMPONENT DESCRIPTION	ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS															
	Annual Maintenance and Repair															
	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (D= 7%)						Replacement and High Costs Tasks									
	By Resources			Washington			D.C. Total		material		equipment		yr	labor	material	equipment
um	labor	material	equipment	labor	material	equipment	labor	material	equipment	yr	labor	material	equipment	labor	material	equipment
ARCHITECTURE																
ROOFING																
BUILTUP ROOFING																
PLACE NEW MEMBRANE OVER EXISTING -BUILTUP	SF	0.06653	0.64214	0.03327			2.11			0.00491	0.03182	0.00245	28	0.04938	0.70490	0.02469
MOD.BIT./THERMOPLASTIC	SF	0.04306	0.59712	0.02154			1.55			0.00244	0.03221	0.00122	14	0.02414	0.69960	0.01207
THERMOSETTING	SF	0.02962	0.43960	0.01481			1.09			0.00173	0.02220	0.00085	20	0.03659	0.85860	0.02839
SLATE	SF	0.02968	0.17286	0.01484			0.83			0.00255	0.01483	0.00127	70	0.06885	6.04200	0.03442
CEMENT ASBESTOS	SF	0.02887	0.40355	0.01445			1.04			0.00248	0.03463	0.00124	70	0.05437	6.04200	0.02718
TILE	SF	0.02506	0.39470	0.01252			0.95			0.00215	0.03387	0.00107	70	0.05084	3.07400	0.05084
ROLL ROOFING	SF	0.11936	0.75476	0.05969			3.39			0.00752	0.01565	0.00376	10	0.10169	0.74963	0.02077
SHINGLES	SF	0.03835	0.39125	0.01918			1.24			0.00263	0.02394	0.00131	40	0.04118	0.74997	0.02059
REPLACE NEW OVER EXISTING - SHINGLED ROOF	SF	0.02383	0.18471	0.01192			0.71			0.00204	0.01385	0.00102	30	0.03626	0.43460	0.01498
METAL	SF	0.03826	2.28032	0.01913			3.12			0.00228	0.06229	0.00114	20	0.04543	2.17300	0.18132
FIBERGLASS RIGID STP. ROOF	SF	0.07120	0.21283	0.03561			1.78			0.00611	0.01826	0.00306	60	0.04123	6.01550	0.02272
CONCRETE SEALED PANEL ROOF	SF	0.06598	0.13913	0.03298			1.59			0.00366	0.01194	0.00283	300	0.04342	24.07419	0.03951
CONCRETE SEALED PANEL RF4	SF	0.16247	1.02850	0.08123			4.61			0.01394	0.03826	0.00697	500	3.81056	18.03219	1.90529
CONCRETE SEALED POURED	SF	0.06495	2.28032	0.03247			3.71			0.00466	0.06229	0.00233	20	0.04133	6.01550	0.02066
FIBERGLASS RIGID ROOF	SF															
See NOTES on the last page of this table for Explanation of Column Headings																

See NOTES on the last page of this table for Explanation of Column Headings



EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)

PAGE 3

COMPONENT DESCRIPTION	UN	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (d= 7%)					ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS									
		By Resources					Annual Maintenance and Repair					Replacement and High Costs Tasks				
		Labor	material	equipment	D.C. Total	Washington	Labor	material	equipment	yr	labor	material	equipment	yr	labor	material
TERRACOTTA Second Floor	SF	0.00457	0.01257	0.00457	0.12	0.12	0.00039	0.00108	0.00039	500	0.39819	3.41320	0.19910			
TERRACOTTA Third Floor	SF	0.00516	0.01357	0.00516	0.16	0.16	0.00053	0.00129	0.00053	500	0.44928	3.41320	0.22464			
WOOD FINISHED 1 COAT 1 FL	SF	0.03389	0.13227	0.03389	1.41	1.41	0.00018	0.00029	0.00018	125	0.33124	0.92220	0.18109			
REFINISH WOOD FINISHED (S.CT) EXT.WALL - 1	SF	0.09113	0.13227	0.09113	2.29	2.29	0.00066	0.00029	0.00066	125	0.35893	0.92220	0.20150			
WOOD FINISHED 1 COAT 2 FL	SF	0.12513	0.13227	0.12513	3.09	3.09	0.00092	0.00029	0.00092	125	0.44915	0.92220	0.25610			
REFINISH WOOD FINISHED (S.CT) EXT.WALL - 2	SF	0.12513	0.13227	0.12513	3.09	3.09	0.00092	0.00029	0.00092	125	0.44915	0.92220	0.25610			
WOOD FINISHED 1 COAT 3 FL	SF	0.03705	0.12208	0.03705	1.00	1.00	0.00019	0.00031	0.00019	125	0.34502	0.97520	0.19287			
REFINISH WOOD FINISHED (MULTI-CT) EXT.WALL	SF	0.06071	0.12208	0.06071	1.56	1.56	0.00066	0.00031	0.00066	125	0.37037	0.97520	0.21320			
WOOD, FINISH MULTI-CT 2 FL	SF	0.08153	0.12208	0.08153	2.05	2.05	0.00093	0.00031	0.00093	125	0.46711	0.97520	0.27287			
REFINISH WOOD FINISHED (MULTI-CT) EXT.WALL	SF	0.00217	0.00911	0.00217	0.06	0.06	0.00019	0.00078	0.00019	125	0.04353	0.10600	0.06323			
WOOD SHAKES UNFINISH 1 FL	SF	0.01158	0.00911	0.01158	0.28	0.28	0.00092	0.00078	0.00092	125	0.06097	0.71020	0.03049			
WOOD SHAKES UNFINISH 2 FL	SF	0.01675	0.00911	0.01675	0.41	0.41	0.00144	0.00078	0.00144	125	0.07813	0.71020	0.03907			
WOOD SHAKES UNFINISH 3 FL	SF	0.06718	0.13934	0.06718	1.73	1.73	0.00036	0.00090	0.00036	125	0.07735	0.81620	0.05571			
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.11889	0.13934	0.11889	2.95	2.95	0.00198	0.00090	0.00198	125	0.03106	0.06360	0.03106			
WOOD SHAKES FINISHED 2 FL	SF	0.16104	0.13934	0.16104	3.95	3.95	0.00287	0.00090	0.00287	125	0.14459	0.06360	0.04728			
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.05089	0.17658	0.05089	1.38	1.38	0.00437	0.01515	0.00437	80	0.09759	0.06360	0.06598			
ALUMINUM SIDING First Flr	SF	0.14181	0.17658	0.14181	2.56	2.56	0.00566	0.01515	0.00566	80	0.13334	0.06360	0.06100			
ALUMINUM SIDING Second Flr	SF	0.00115	0.01255	0.00115	0.04	0.04	0.00010	0.00108	0.00010	100	0.07319	0.04580	0.08460			
ALUM. SIDING ANCOIZED 1 FL	SF	0.00554	0.01255	0.00554	0.14	0.14	0.00048	0.00108	0.00048	100	0.09347	0.04580	0.11188			
ALUM. SIDING ANCOIZED 2 FL	SF	0.00796	0.01255	0.00796	0.20	0.20	0.00068	0.00108	0.00068	100	0.11362	0.04580	0.13660			
STEEL (SELF-COATING) 1 FL	SF	0.00490	0.02860	0.00490	0.14	0.14	0.00042	0.00242	0.00042	150	0.59007	5.53320	0.33105			
STEEL (SELF-COATING) 2 FL	SF	0.00739	0.02860	0.00739	0.20	0.20	0.00063	0.00242	0.00063	150	0.62009	5.53320	0.36693			
STEEL (SELF-COATING) 3 FL	SF	0.00974	0.02860	0.00974	0.26	0.26	0.00082	0.00242	0.00082	150	0.63817	5.53320	0.38314			
STEEL (PAINTED) First Flr	SF	0.03710	0.09646	0.03710	0.97	0.97	0.00063	0.00270	0.00063	150	0.03875	0.08440	0.03875			
REFINISH STEEL (PAINTED) EXTERIOR WALL - 1	SF	0.05474	0.09646	0.05474	1.39	1.39	0.00104	0.00270	0.00104	150	0.05563	0.08440	0.05563			
STEEL (PAINTED) Second Flr	SF	0.07205	0.09646	0.07205	1.80	1.80	0.00142	0.00270	0.00142	150	0.08178	0.08440	0.08178			
REFINISH STEEL (PAINTED) EXTERIOR WALL - 2	SF	0.04266	0.04463	0.04266	0.15	0.15	0.00037	0.00383	0.00037	300	1.04013	12.11580	0.72337			
GLASS BLOCK First Floor	SF	0.00735	0.04463	0.00735	0.22	0.22	0.00063	0.00383	0.00063	300	1.15713	12.11580	0.52007			
GLASS BLOCK Second Floor	SF	0.00922	0.04463	0.00922	0.26	0.26	0.00079	0.00383	0.00079	300	1.27400	12.11580	0.57857			
GLASS BLOCK Third Floor	SF	0.01449	0.04463	0.01449	0.69	0.69	0.00124	0.00383	0.00124	150	0.99006	12.11580	0.63700			
PLATE GLASS First Floor	SF	0.04531	0.34366	0.04531	1.42	1.42	0.00389	0.02949	0.00389	150	0.12196	8.80000	0.04953			
PLATE GLASS Second Floor	SF	0.06243	0.34366	0.06243	1.82	1.82	0.00536	0.02949	0.00536	150	0.16169	8.80000	0.06097			
FORMICA-VINYL First Floor	SF	0.03374	0.01593	0.03374	0.10	0.10	0.00032	0.00137	0.00032	40	0.02525	0.03600	0.02525			
FORMICA-VINYL Second Floor	SF	0.03214	0.01593	0.03214	0.54	0.54	0.00137	0.00137	0.00137	40	0.04324	0.03600	0.04324			
FORMICA-VINYL Third Floor	SF	0.02339	0.01593	0.02339	0.78	0.78	0.00078	0.00137	0.00078	40	0.06084	0.03600	0.06084			
ASBESTOS First Floor	SF	0.00259	0.01609	0.00259	0.08	0.08	0.00022	0.00138	0.00022	100	0.04862	1.04940	0.02431			
ASBESTOS Second Floor	SF	0.01398	0.01609	0.01398	0.35	0.35	0.00120	0.00138	0.00120	100	0.06643	1.04940	0.03322			
ASBESTOS Third Floor	SF	0.02012	0.01609	0.02012	0.49	0.49	0.00173	0.00138	0.00173	100	0.08424	1.04940	0.04212			
SYN. VENEER-PLASTER 1st Fl	SF	0.03825	0.06430	0.03825	0.97	0.97	0.00041	0.00096	0.00041	160	0.02672	0.73140	0.04646			
REFINISH SYNTHETIC VENEER	SF	0.08049	0.06430	0.08049	1.97	1.97	0.00235	0.00096	0.00235	160	0.09738	0.73140	0.07062			
SYN. VENEER-PLASTER 2nd Fl	SF	0.11140	0.06430	0.11140	2.70	2.70	0.00342	0.00096	0.00342	160	0.12942	0.73140	0.09445			
SYN. VENEER-PLASTER 3rd Fl	SF	0.02096	0.05946	0.02096	0.56	0.56	0.00180	0.00510	0.00180	125	0.08260	0.73140	0.05717			
REFINISH SYNTHETIC VENEER 3RD FLR.	SF	0.03566	0.05946	0.03566	0.90	0.90	0.00306	0.00510	0.00306	125	0.10390	2.52174	0.08753			
PORCELAIN PANEL First Flr	SF															
PORCELAIN PANEL Second Flr	SF															

See NOTES on the last page of this table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)														PAGE
PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (C= 7%)														4
COMPONENT DESCRIPTION	UN	By Resources				Washington				ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS				
		labor		material		equipment		D.C. Total		Annual Maintenance and Repair		Replacement and High Costs Tasks		
		labor	material	equipment	labor	material	equipment	labor	material	labor	equipment	material	labor	equipment
PORCELAIN PANEL THIRD FLR.	SF	0.04367	0.05946	0.03367	1.99					0.00375	0.00375	2.52174	0.12691	0.04164
ALUM. CORR. PANEL 1st FLR.	SF	0.00345	0.02773	0.00345	0.11					0.00030	0.00030	0.02074	0.00074	0.01037
ALUM. CORR. PANEL 2nd FLR.	SF	0.01991	0.02773	0.01991	0.48					0.00171	0.00171	1.24020	0.04971	0.02486
ALUM. CORR. PANEL 3rd FLR.	SF	0.02897	0.02773	0.02897	0.68					0.00249	0.00249	0.02020	0.07080	0.03540
EXT. GYPSUM BRD-PNTD 1 FLR.	SF	0.06280	0.12524	0.06280	1.61					0.00034	0.00034	1.31122	0.08843	0.05902
REFINISH EXTERIOR GYPSUM BOARD-PNTD FIRST										0.02276	0.02276	0.02276	0.02276	0.02276
EXT. GYPSUM BRD-PNTD 2 FLR.	SF	0.12000	0.12524	0.12000	2.96					0.00186	0.00186	1.31122	0.11682	0.07795
REFINISH EXTERIOR GYPSUM BOARD-PNTD SECOND										0.03806	0.03806	0.04240	0.03806	0.03806
EXT. GYPSUM BRD-PNTD 3 FLR.	SF	0.16858	0.12524	0.16858	4.11					0.00269	0.00269	1.31122	0.15040	0.10241
REFINISH EXTERIOR GYPSUM BOARD-PNTD FIRST										0.05311	0.05311	0.04240	0.05311	0.05311
EXT. GYPSUM BRD-COVERED 1FL	SF	0.17251	1.66008	0.17251	5.74					0.00036	0.00036	1.43736	0.06514	0.09456
REFINISH EXTERIOR GYPSUM BOARD COVERED FIR										0.06514	0.06514	0.63600	0.06514	0.06514
EXT. GYPSUM BRD-COVERED 2FL	SF	0.24068	1.66008	0.24068	7.35					0.00188	0.00188	1.43736	0.12349	0.08468
REFINISH EXTERIOR GYPSUM BOARD-COVERED 2ND										0.06229	0.06229	0.63600	0.06229	0.06229
EXT. GYPSUM BRD-COVERED 3FL	SF	0.30024	1.66008	0.30024	8.76					0.00148	0.00148	1.43736	0.20035	0.15216
REFINISH EXTERIOR GYPSUM BOARD COVERED 3RD										0.00272	0.00272	0.63600	0.10396	0.10396
MASONITE PANEL, SEALED 1FL	SF	0.00227	0.00652	0.00227	0.06					0.00019	0.00019	0.54060	0.05766	0.02883
MASONITE PANEL, SEALED 2FL	SF	0.01174	0.00652	0.01174	0.28					0.00056	0.00056	0.54060	0.07645	0.03822
MASONITE PANEL, SEALED 3FL	SF	0.01696	0.00652	0.01696	0.41					0.00145	0.00145	0.54060	0.09498	0.04729
FIBERGLASS PANEL RIGID 1FL	SF	0.06375	0.19277	0.06375	1.70					0.00043	0.00043	1.79405	0.04336	0.04748
REFINISH FIBERGLASS PANELS RIGID FIRST FLO										0.02376	0.02376	0.06360	0.02376	0.02376
FIBERGLASS PANEL RIGID 2FL	SF	0.12799	0.19277	0.12799	3.22					0.00255	0.00255	1.79405	0.03606	0.03806
REFINISH FIBERGLASS PANELS, RIGID SECOND F										0.03144	0.03144	1.79405	0.03606	0.03806
FIBERGLASS PANEL RIGID 3FL	SF	0.18042	0.19277	0.18042	4.46					0.00371	0.00371	0.06360	0.12592	0.08856
REFINISH FIBERGLASS PANEL, RIGID THIRD FLO										0.05311	0.05311	0.06360	0.05311	0.05311
EXTERIOR DOORS														
METAL DOORS														
ALUMINUM (PLAIN/ANODIZED)														
AL. (PCL) FRAME/DOOR	CT	0.70112	57.76311	0.70112	74.35					0.06016	0.06016	265.00000	2.23574	2.23574
AL. SLIDING EXT. (PCL) DOOR	CT	1.05027	60.96559	1.05027	85.81					0.09012	0.09012	327.87125	2.73004	2.73004
AL. (WOOD CORE) EXT. DOOR	CT	1.32109	144.35305	1.32109	175.61					0.11336	0.11336	848.38075	3.65032	3.65032
AL. (WOOD CORE) EXT. DOOR	CT	1.05027	59.74908	1.05027	84.60					0.09012	0.09012	381.60000	2.73004	2.73004
STEEL (PAINTED) EXT. DOOR	CT	1.05027	59.74908	1.05027	84.60					0.09012	0.09012	381.60000	2.73004	2.73004
STEEL PAINTED EXT. DOOR	CT	1.27231	42.69790	1.27231	72.60					0.10918	0.10918	124.74080	2.93530	2.93530
ST. SLIDING PNTD EXT. DOOR	CT	1.84622	90.88060	1.84622	89.38					0.15842	0.15842	187.55732	3.14685	3.14685
ST. (INSUL CORE)PNTD EXT. DR	CT	1.64083	44.48367	1.64083	130.18					0.14252	0.14252	707.74080	1.78183	1.78183
STEEL (UNPAINTED) EXT. DOOR	CT	0.42411	34.94078	0.42411	88.17					0.03639	0.03639	145.22000	3.14685	3.14685
ST. (GLASS) UNPNTD EXT. DOOR	CT	0.77327	38.14326	0.77327	56.44					0.06635	0.06635	220.48000	2.73004	2.73004
ST. SLIDING UNPNTD EXT. DOOR	CT	0.58790	86.05709	0.58790	99.97					0.05045	0.05045	844.82000	2.73004	2.73004
ST. (INSUL) UNPNTD EXT. DOOR	CT	0.77330	36.92675	0.77330	55.22					0.06636	0.06636	285.14000	1.36502	1.36502
FULLY GLAZED DOORS														
ALUMINUM FRAME														
GLAZED AL. SLIDING EXT. DOOR	CT	1.05107	60.74621	1.05107	85.61					0.09019	0.09019	395.39000	2.23574	2.23574
WOOD FRAME (PAINTED)	CT	0.91427	43.97997	0.91427	65.61					0.07845	0.07845	636.00000	2.81608	2.81608
GLAZED WOOD (SLID.) EXT. DR	CT	1.31052	76.53954	1.31052	107.55					0.11246	0.11246	122.57310	2.35677	2.35677
WOOD DOORS										0.12492	0.12492	460.12480	2.58557	2.58557
HOLLOW CORE (PAINTED)														
HOL. CORE SLID. WOOD EXT. DR	CT	1.78943	60.64192	1.78943	102.98					0.15355	0.15355	196.82000	2.58492	2.58492
SOLID CORE (PAINTED)	CT	2.18888	46.43531	2.18888	98.22					0.18783	0.18783	211.78800	3.23728	3.23728
SOLID CORE (PAINTED)	CT	1.35832	27.27104	1.35832	69.41					0.11656	0.11656	223.32000	2.58492	2.58492
SOLID SLID. WOOD EXT. DOOR	CT	1.70305	29.60828	1.70305	69.90					0.14614	0.14614	213.90000	3.23728	3.23728
SOLID CORE GLASS PNTD EXT.	CT	1.70750	40.67352	1.70750	80.87					0.14652	0.14652	239.22000	2.58557	2.58557
LOWERED EXTERIOR DOOR														
METAL GRATED PNTD EXT. DOOR	CT	1.98025	13.20144	1.98025	60.05					0.16993	0.16993	218.02000	11.33121	11.33121
MET. WIRE MESH PNTD EXT. DR	CT	0.21695	3.12828	0.21695	8.26					0.02976	0.02976	214.12000	10.44858	10.44858
METAL WIRE PNTD EXT. DOOR	CT	2.33091	10.10866	2.33091	65.26					0.20002	0.20002	202.12000	6.45380	6.45380
METAL WIRE PNTD EXT. DOOR	CT	0.05557	0.05557	0.05557	1.35					0.00477	0.00477	198.22000	3.23728	3.23728
AL. LOWERED EXT. DOOR	CT	2.47881	43.84866	2.47881	102.50					0.21271	0.21271	508.46000	6.04897	6.04897
STEEL LOWERED EXT. DOOR	CT	1.92334	29.50979	1.92334	75.02					0.16504	0.16504	310.77080	3.23289	3.23289

See notes on the last page of this table for explanation of column headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)													PAGE 5
COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (C= 7%)					ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS							
	By Resources					Annual Maintenance and Repair				Replacement and High Costs Tasks			
	un	labor	material	equipment	D.C. Total	Washington	labor	material	equipment	yr	labor	material	equipment
WOOD LOUVERED EXT. DOOR	CT	3.81847	91.96726	3.81847	182.31		0.52766	7.89175	0.32766	40	6.04897	311.50080	3.23289
EXTERIOR GATE	CT												
ALUMINUM EXTERIOR GATE	CT	1.65901	38.42693	1.65901	77.68		0.14236	3.29743	0.14236	40	2.25334	421.24400	1.22691
STEEL EXTERIOR GATE	CT	1.45383	28.06987	1.45383	62.47		0.12475	2.40869	0.12475	65	2.25334	256.94400	1.22691
WOOD EXTERIOR GATE	CT	2.45206	205.17843	2.45206	263.19		0.20724	17.56623	0.20724	25	2.25334	475.30400	1.22691
REPLACE WOOD EXTERIOR GATE (WALK & DRIVEWAY)	CT												
WROUGHT IRON EXT. GATE	CT	1.55138	30.20374	1.55138	66.91		0.13312	2.59179	0.13312	65	2.25334	472.76000	1.02643
SCREEN/STORM DOORS	CT												
ALUMINUM (PLAIN/ANODIZED)	CT	4.04144	160.40422	4.04144	236.03		0.29722	8.52274	0.29722	20	2.23574	159.00000	2.23574
PLASTIC	CT	2.81886	130.27177	2.81886	196.97		0.19169	8.52274	0.19169	20	2.23569	119.78000	2.23569
ROLL-UP DOORS	CT												
ST. FRAME-SINGLE (PAINTED)	CT	5.31996	128.07754	5.31996	253.95		0.45651	10.99038	0.45651	35	4.84587	176.85040	2.67316
ST. FRAME-DOUBLE (PAINTED)	CT	9.71421	163.81823	9.71421	395.66		0.83358	14.05731	0.83358	35	5.38802	445.73000	2.67316
AL. SINGLE ROLL-UP DOOR	CT	4.58113	238.03362	4.58113	346.42		0.58464	20.35692	0.58464	24	4.84587	135.24340	2.67316
REPLACE ALUMINUM SINGLE ROLL-UP DOOR	CT												
AL. DOUBLE ROLL-UP DOOR	CT	8.68278	271.39445	8.68278	476.83		0.72744	23.14504	0.72744	24	5.38802	131.17500	3.21531
REPLACE ALUMINUM DOUBLE ROLL-UP DOOR	CT												
WOOD SINGLE ROLL-UP DOOR	CT	4.63102	278.02377	4.63102	387.59		0.38284	23.73903	0.38284	16	4.84587	470.37500	2.67316
REPLACE WOOD SINGLE ROLL-UP DOOR	CT	8.77279	403.37982	8.77279	610.94		0.72249	34.36772	0.72249	16	5.38802	235.85000	2.67316
WOOD DOUBLE ROLL-UP DOOR	CT												
REPLACE WOOD DOUBLE ROLL-UP DOOR	CT	4.27182	98.25814	4.27182	199.33		0.36657	8.43157	0.36657	48	11.41516	530.00000	2.1271
AL (ONE LEAF) SPRING DOOR	CT	1.1833	77.15471	1.1833	174.89		0.35340	6.64642	0.35340	70	11.41516	424.38160	6.70848
STEEL (ONE LEAF) SPRING DOOR	CT	3.95328	152.16139	3.95328	245.70		0.33923	13.05703	0.33923	32	11.10961	387.28160	6.70848
WOOD (ONE LEAF) SPRING DOOR	CT												
EXTERIOR WINDOWS	CT												
OPERABLE WINDOWS	CT												
ALUMINUM OPER. First Flr.	CT	0.28210	2.10433	0.28210	8.78		0.02421	0.18059	0.02421	75	3.30634	154.76000	3.30634
ALUMINUM OPER. Second Flr.	CT	0.46171	2.10433	0.46171	13.03		0.03962	0.18059	0.03962	75	5.21782	154.76000	5.21782
ALUMINUM OPER. Third Flr.	CT	3.14851	2.10433	3.14851	76.60		0.27018	0.18059	0.27018	80	5.21782	154.76000	5.21782
STEEL FRAME-OPER (PNTD) 1FL	CT	0.86084	2.68615	0.86084	23.05		0.07387	0.23050	0.07387	80	5.95241	275.80999	5.95241
STEEL FRAME-OPER (PNTD) 2FL	CT	3.97651	2.68615	3.97651	96.77		0.34123	0.23050	0.34123	80	7.70654	275.80999	7.70654
STEEL FRAME-OPER (PNTD) 3FL	CT	5.78332	2.68615	5.78332	139.52		0.49627	0.23050	0.49627	80	7.70654	275.80999	7.70654
WOOD FRAME-OPER (PNTD) 1 FL	CT	1.03088	2.49139	1.03088	26.88		0.08846	0.21379	0.08846	50	5.9245	94.51999	5.9245
WOOD FRAME-OPER (PNTD) 2 FL	CT	3.96524	2.39118	3.96524	96.21		0.34026	0.20519	0.34026	50	7.74658	94.51999	7.74658
WOOD FRAME-OPER (PNTD) 3 FL	CT	5.77204	2.39118	5.77204	138.96		0.49530	0.20519	0.49530	50	7.74658	94.51999	7.74658
PLASTIC (WOOD CORE) FRM 1FL	CT	0.19820	2.27190	0.19820	6.06		0.01701	0.19495	0.01701	75	1.30434	137.80000	1.30434
PLASTIC (WOOD CORE) FRM 2FL	CT	0.38355	2.27190	0.38355	11.35		0.03291	0.19495	0.03291	75	1.30434	137.80000	1.30434
PLASTIC (WOOD CORE) FRM 3FL	CT	4.88651	2.27190	4.88651	15.83		0.04193	0.19495	0.04193	75	1.30434	137.80000	1.30434
GLASS BLOCK-OPER First Flr	CT	0.62752	5.06330	0.62752	19.91		0.05385	0.43448	0.05385	100	3.02718	281.67592	3.02718
GLASS BLOCK-OPER Second Flr	CT	2.40707	5.06330	2.40707	62.01		0.20655	0.43448	0.20655	100	4.47642	281.67592	4.47642
GLASS BLOCK-OPER Third Flr	CT	3.43657	5.06330	3.43657	86.37		0.29489	0.43448	0.29489	100	5.31882	281.67592	5.31882
ALUMINUM DOUBLE-OPER 1 FL	CT	0.51389	3.88448	0.51389	16.04		0.04410	0.33333	0.04410	75	3.30634	213.06000	3.30634
ALUMINUM DOUBLE-OPER 2 FL	CT	0.69350	3.88448	0.69350	20.29		0.05951	0.33333	0.05951	75	4.21782	213.06000	4.21782
ALUMINUM DOUBLE-OPER 3 FL	CT	1.79282	3.88448	1.79282	22.64		0.06803	0.33333	0.06803	75	5.12929	213.06000	5.12929
STEEL FRAME (DBL)-OPER 1 FL	CT	1.12581	4.96966	1.12581	31.61		0.09661	0.42645	0.09661	80	3.60833	394.73997	3.60833
STEEL FRAME (DBL)-OPER 2 FL	CT	4.24149	4.96966	4.24149	105.32		0.36396	0.42645	0.36396	80	5.94879	394.73997	5.94879
STEEL FRAME (DBL)-OPER 3 FL	CT	6.04829	4.96966	6.04829	148.07		0.51901	0.42645	0.51901	80	7.72992	394.73997	7.72992
WOOD FRAME (DBL)-OPER 1 FL	CT	1.67481	4.76469	1.67481	44.39		0.14372	0.40886	0.14372	50	3.94973	123.45184	3.94973
WOOD FRAME (DBL)-OPER 2 FL	CT	4.79049	4.76469	4.79049	118.11		0.41107	0.40886	0.41107	50	5.3010	123.45184	5.3010
WOOD FRAME (DBL)-OPER 3 FL	CT	6.59729	4.76469	6.59729	160.86		0.56612	0.40886	0.56612	50	8.08432	123.45184	8.08432
PLASTIC (WOOD) FRM-OPER 1FL	CT	0.35909	4.07314	0.35909	12.10		0.02910	0.34992	0.02910	70	3.30634	187.62000	3.30634
PLASTIC (WOOD) FRM-OPER 2FL	CT	0.52444	4.07314	0.52444	16.48		0.04500	0.34992	0.04500	70	4.21782	187.62000	4.21782
PLASTIC (WOOD) FRM-OPER 3FL	CT	0.62950	4.07314	0.62950	18.97		0.05402	0.34992	0.05402	70	5.12929	187.62000	5.12929
IMPERABLE WINDOWS	CT												
ALUMINUM-FIXED First Flr.	CT	0.28210	2.06344	0.28210	8.74		0.02421	0.17706	0.02421	75	3.30634	122.96000	3.30634
ALUMINUM-FIXED Second Flr.	CT	0.46171	2.06344	0.46171	12.99		0.03962	0.17706	0.03962	75	5.21782	122.96000	5.21782
ALUMINUM-FIXED Third Flr.	CT	0.56104	2.06344	0.56104	15.34		0.04814	0.17706	0.04814	75	5.21782	122.96000	5.21782
STEEL FRAME (PNTD)-FXD 1 FL	CT	0.86084	2.49716	0.86084	22.86		0.07387	0.21428	0.07387	80	3.59195	129.52999	3.59195

See NOTES on the last page of this table for Explanation of Column Headings



EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)

COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (P= 7%)											
	By Resources					Washington						
						D.C. Total						
	UN	labor	material	equipment		labor	material	equipment	yr	labor	material	equipment
STEEL FRAME (PNTD)-FXD 2 FL	CT	3.97651	2.49716	3.97651	96.58	0.34123	0.21428	0.34123	80	5.95241	129.52999	5.95241
STEEL FRAME (PNTD)-FXD 3 FL	CT	5.78332	2.49716	5.78332	139.33	0.49627	0.21428	0.49627	80	7.70654	129.52999	7.70654
WOOD FRAME (PNTD)-FXD 1 FL	CT	1.87847	2.80825	1.87847	47.25	0.16119	0.24098	0.16119	50	4.13977	229.25988	4.13977
WOOD FRAME (PNTD)-FXD 2 FL	CT	4.64960	2.80825	4.64960	112.82	0.39898	0.24098	0.39898	50	6.33019	229.25988	6.33019
WOOD FRAME (PNTD)-FXD 3 FL	CT	8.10176	2.80825	8.10176	194.66	0.69522	0.25531	0.69522	50	8.08432	229.25988	8.08432
PLASTIC (WOOD)FRM-FXD 1 FL	CT	0.19820	2.46716	0.19820	7.16	0.01701	0.21171	0.01701	70	3.30634	238.50000	3.30634
PLASTIC (WOOD)FRM-FXD 2 FL	CT	0.38355	2.46716	0.38355	11.56	0.03291	0.21171	0.03291	70	3.30634	238.50000	3.30634
PLASTIC (WOOD)FRM-FXD 3 FL	CT	0.48861	2.46716	0.48861	14.03	0.04193	0.21171	0.04193	70	3.30634	238.50000	3.30634
GLASS BLOCK-FIXED 1st FL	CT	0.62752	2.06350	0.62752	19.91	0.05385	0.43448	0.05385	100	3.02718	150.23592	3.02718
GLASS BLOCK-FIXED 2nd FL	CT	2.41564	2.06350	2.41564	62.22	0.20729	0.43448	0.20729	100	4.7642	150.23592	4.7642
GLASS BLOCK-FIXED 3rd FL	CT	3.44514	2.06350	3.44514	86.58	0.29563	0.43448	0.29563	100	5.34482	150.23592	5.34482
ALUMINUM DBL-FXD 1st FL	CT	0.51389	3.82286	0.51389	15.98	0.04410	0.32804	0.04410	75	3.30634	165.36000	3.30634
ALUMINUM DBL-FXD 2nd FL	CT	0.69350	3.82286	0.69350	20.23	0.05951	0.32804	0.05951	75	4.21782	165.36000	4.21782
ALUMINUM DBL-FXD 3rd FL	CT	0.79282	3.82286	0.79282	22.58	0.06803	0.32804	0.06803	75	4.21782	165.36000	4.21782
STEEL FRAME (DBL)-FXD 1 FL	CT	1.12581	4.67715	1.12581	31.31	0.09661	0.40135	0.09661	80	5.12929	175.31552	5.12929
STEEL FRAME (DBL)-FXD 2 FL	CT	2.24149	4.67715	2.24149	105.03	0.36396	0.40135	0.36396	80	7.72929	175.31552	7.72929
STEEL FRAME (DBL)-FXD 3 FL	CT	4.04829	4.67715	4.04829	147.78	0.61591	0.40135	0.61591	80	9.98790	175.31552	9.98790
WOOD FRAME (DBL)-FXD 1st FL	CT	0.04418	5.57667	0.04418	53.96	0.17541	0.7854	0.17541	50	3.96973	323.89996	3.96973
WOOD FRAME (DBL)-FXD 2nd FL	CT	5.96665	5.57667	5.96665	166.75	0.51200	0.7854	0.51200	50	8.38432	323.89996	8.38432
WOOD FRAME (DBL)-FXD 3rd FL	CT	8.24265	5.57667	8.24265	220.59	0.70731	0.7854	0.70731	50	8.08432	323.89996	8.08432
PLASTIC (WOOD)DBL-FXD 1 FL	CT	0.35909	4.36705	0.35909	12.59	0.02910	0.37474	0.02910	70	3.30634	339.20000	3.30634
PLASTIC (WOOD)DBL-FXD 2 FL	CT	4.36705	4.36705	4.36705	16.70	0.04474	0.37474	0.04474	70	4.21782	339.20000	4.21782
PLASTIC (WOOD)DBL-FXD 3 FL	CT	0.62950	4.36705	0.62950	19.26	0.05402	0.37474	0.05402	70	5.12929	339.20000	5.12929
WOOD LOUVER First Floor	CT	2.55787	41.93279	2.55787	102.45	0.21949	3.59827	0.21949	75	5.95304	81.28080	5.95304
WOOD LOUVER Second Floor	CT	5.49241	42.92434	5.49241	172.87	0.47131	3.68335	0.47131	75	8.05853	81.28080	8.05853
WOOD LOUVER Third Floor	CT	6.20684	41.93279	6.20684	188.79	0.53262	3.59827	0.53262	75	10.16402	81.28080	10.16402
ALUM. LOUVER First Floor	CT	2.36586	64.39589	2.36586	120.37	0.20302	5.52584	0.20302	80	5.95304	317.66080	5.95304
ALUM. LOUVER Second Floor	CT	4.15322	64.39589	4.15322	162.66	0.35639	5.52584	0.35639	80	8.05853	317.66080	8.05853
ALUM. LOUVER Third Floor	CT	5.93004	64.39589	5.93004	204.70	0.50886	5.52584	0.50886	80	10.16402	317.66080	10.16402
STEEL LOUVER First Floor	CT	2.30552	23.65996	2.30552	78.21	0.19784	2.03027	0.19784	150	5.95304	198.94080	5.95304
STEEL LOUVER Second Floor	CT	4.07706	23.65996	4.07706	120.12	0.34985	2.03027	0.34985	150	8.05853	198.94080	8.05853
STEEL LOUVER Third Floor	CT	5.84304	23.65996	5.84304	161.91	0.50130	2.03027	0.50130	150	10.16402	198.94080	10.16402
WOOD SHUTTER First Floor	CT	2.57817	23.65996	2.57817	102.45	0.21949	3.59827	0.21949	75	5.95304	81.28080	5.95304
WOOD SHUTTER Second Floor	CT	4.39552	41.93279	4.39552	145.95	0.35261	3.59827	0.35261	75	8.05853	81.28080	8.05853
WOOD SHUTTER Third Floor	CT	6.20684	41.93279	6.20684	188.79	0.53262	3.59827	0.53262	75	10.16402	81.28080	10.16402
ALUM. SHUTTER First Floor	CT	2.39093	76.30495	2.39093	132.87	0.20517	6.54776	0.20517	80	5.95304	317.66080	5.95304
ALUM. SHUTTER Second Floor	CT	4.18484	76.30495	4.18484	175.32	0.35910	6.54776	0.35910	80	8.05853	317.66080	8.05853
ALUM. SHUTTER Third Floor	CT	5.96617	76.30495	5.96617	217.46	0.51196	6.54776	0.51196	80	10.16402	317.66080	10.16402
STEEL SHUTTER First Floor	CT	2.36586	41.56247	2.36586	97.54	0.20302	3.56649	0.20302	150	5.95304	198.94080	5.95304
STEEL SHUTTER Second Floor	CT	4.15322	41.56247	4.15322	139.83	0.35639	3.56649	0.35639	150	8.05853	198.94080	8.05853
STEEL SHUTTER Third Floor	CT	5.93004	41.56247	5.93004	181.87	0.50886	3.56649	0.50886	150	10.16402	198.94080	10.16402
WOOD COV. SPECIAL EXT.	CT	2.51774	2.25730	2.51774	61.83	0.21605	0.19370	0.21605	80	2.63991	111.53998	2.63991
ALUM. FRAME STORM WNDW 1FL	CT	4.72966	2.25730	4.72966	116.16	0.40582	0.19370	0.40582	80	6.18827	111.53998	6.18827
ALUM. FRAME STORM WNDW 2FL	CT	6.75219	2.25730	6.75219	142.02	0.57943	0.19370	0.57943	80	8.27998	111.53998	8.27998
STEEL FRAME STORM WNDW 1FL	CT	2.10027	2.19091	2.10027	51.88	0.18022	0.18800	0.18022	100	2.63991	89.27998	2.63991
STEEL FRAME STORM WNDW 2FL	CT	4.00834	2.19091	4.00834	97.03	0.34396	0.18800	0.34396	100	4.41409	89.27998	4.41409
STEEL FRAME STORM WNDW 3FL	CT	5.83916	2.19091	5.83916	140.35	0.50106	0.18800	0.50106	100	6.18827	89.27998	6.18827
WOOD FRAME STORM WNDW 1 FL	CT	2.81782	2.30501	2.81782	68.97	0.19779	0.19779	0.19779	50	2.63991	93.89098	2.63991
WOOD FRAME STORM WNDW 2 FL	CT	5.24813	2.30501	5.24813	126.48	0.45034	0.19779	0.45034	50	4.41409	93.89098	4.41409
WOOD FRAME STORM WNDW 3 FL	CT	7.40891	2.30501	7.40891	177.60	0.63576	0.19779	0.63576	50	6.18827	93.89098	6.18827
METAL WINDOW GRATING 1stFL	CT	3.32832	10.34215	3.32832	89.09	0.28560	0.88746	0.28560	150	23.23632	116.12300	23.23632
METAL WINDOW GRATING 2ndFL	CT	5.19643	10.34215	5.19643	133.29	0.44591	0.88746	0.44591	150	37.07014	116.12300	37.07014
METAL WINDOW GRATING 3rdFL	CT	7.06213	10.34215	7.06213	177.43	0.60600	0.88746	0.60600	150	50.90396	116.12300	50.90396
METAL WIRE MESH COVER 1 FL	CT	3.56861	7.24937	3.56861	91.68	0.30422	0.62207	0.30422	150	4.02557	95.59080	4.02557
METAL WIRE MESH COVER 2 FL	CT	5.46074	7.24937	5.46074	136.45	0.48859	0.62207	0.48859	150	7.94625	95.59080	7.94625
METAL WIRE MESH COVER 3 FL	CT	7.35047	7.24937	7.35047	181.16	0.63075	0.62207	0.63075	150	10.90396	95.59080	10.90396

See NOTES on the last page of this table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)

PAGE 7

COMPONENT DESCRIPTION	UM	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (d= 7%)				ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS									
		By Resources				Annual Maintenance and Repair									
		Washington				Replacement and High Costs Tasks									
		Labor	material	equipment	D.C. Total	Labor	material	equipment	yr	Labor	material	equipment	Labor	material	equipment
ALUM. FRM SCRN WNDW CVR 1FL	CT	1.84791	0.72959	1.84791	44.45	0.15857	0.06261	0.15857	70	3.08433	42.39618	3.08433			
ALUM. FRM SCRN WNDW CVR 2FL	CT	3.56648	0.72959	3.56648	85.41	0.30604	0.06261	0.30604	70	4.90295	42.39618	4.90295			
ALUM. FRM SCRN WNDW CVR 3FL	CT	5.28333	0.72959	5.28333	123.73	0.45336	0.06261	0.45336	70	6.72157	42.39618	6.72157			
STEEL FRM SCRN WNDW CVR 1FL	CT	1.84791	0.72959	1.84791	44.45	0.15857	0.06261	0.15857	80	3.08433	39.39638	3.08433			
STEEL FRM SCRN WNDW CVR 2FL	CT	3.56648	0.72959	3.56648	85.41	0.30604	0.06261	0.30604	80	4.90295	39.39638	4.90295			
STEEL FRM SCRN WNDW CVR 3FL	CT	5.28333	0.72959	5.28333	123.73	0.45336	0.06261	0.45336	80	6.72157	39.39638	6.72157			
WOOD FRM SCRN WNDW CVR 1FL	CT	1.84791	0.72959	1.84791	44.45	0.15857	0.06261	0.15857	40	3.08433	40.02178	3.08433			
WOOD FRM SCRN WNDW CVR 2FL	CT	3.56648	0.72959	3.56648	85.41	0.30604	0.06261	0.30604	40	4.90295	40.02178	4.90295			
WOOD FRM SCRN WNDW CVR 3FL	CT	5.28333	0.72959	5.28333	123.73	0.45336	0.06261	0.45336	40	6.72157	40.02178	6.72157			
LEAD-LINED WNDW(W/FR) 1FL	CT	2.10027	2.19091	2.10027	51.88	0.18022	0.18800	0.18022	100	2.43409	248.28316	2.43409			
LEAD-LINED WNDW(W/FR) 2FL	CT	4.00834	2.19091	4.00834	97.03	0.34396	0.18800	0.34396	100	4.41409	248.28316	4.41409			
LEAD-LINED WNDW(W/FR) 3FL	CT	5.83916	2.19091	5.83916	140.35	0.50106	0.18800	0.50106	100	6.18827	248.28316	6.18827			
EXTERIOR PORCHES															
DECKS															
CONCRETE	SF	0.03805	0.11315	0.03805	1.01	0.00327	0.00971	0.00327	300	1.24579	17.78680	0.00327			
WOOD	SF	0.03254	0.22958	0.03254	1.00	0.00279	0.01970	0.00279	200	0.06968	2.84080	0.00279			
METAL DECKING-PORCH	SF	0.03669	0.08461	0.03669	0.95	0.00315	0.00726	0.00315	65	0.32421	0.96460	0.00315			
RAILINGS															
WROUGHT IRON	LF	0.07955	0.18900	0.07955	2.07	0.00683	0.01622	0.00683	200	4.32328	53.08480	0.00683			
WOOD	LF	0.04877	0.16872	0.04877	1.32	0.00419	0.01448	0.00419	100	0.37154	4.93536	0.00419			
STEEL RAILING PAINTED	LF	0.07955	0.18330	0.07955	2.07	0.00683	0.01573	0.00683	200	2.18088	27.11480	0.00683			
STEEL RAILING UNPAINTED	LF	0.03121	0.07669	0.03121	0.82	0.00268	0.00658	0.00268	200	2.14240	27.03080	0.00268			
DECK SUPPORT MEMBERS															
CONCRETE	SF	0.03474	0.11114	0.03474	0.93	0.00298	0.00954	0.00298	500	3.60971	17.78680	0.00298			
WOOD	SF	0.01286	0.59898	0.01286	0.90	0.00110	0.05140	0.00110	100	0.19279	4.74880	0.00110			
CLAY BRICK	SF	0.03254	0.11817	0.03254	0.89	0.00279	0.01014	0.00279	500	1.12554	2.32140	0.00279			
STEEL EXT. PORCH SUPPORT	SF	0.01454	0.14017	0.01454	0.48	0.00125	0.01203	0.00125	200	0.19279	27.51760	0.00125			
COLUMNS															
METAL	LF	0.07980	0.80463	0.07980	2.69	0.00685	0.06905	0.00685	200	0.22945	18.06240	0.00685			
WOOD	LF	0.03753	0.41518	0.03753	1.30	0.00322	0.03563	0.00322	200	0.23842	1.20840	0.00322			
CLAY BRICK	LF	0.04817	0.47457	0.04817	1.61	0.00413	0.04072	0.00413	500	1.13152	9.20080	0.00413			
EXTERIOR ORNAMENT															
CORNICES															
STONE	LF	0.01706	0.00038	0.01706	0.40	0.00146	0.00003	0.00146	300	0.26507	95.40000	0.00146			
WOOD	LF	0.07681	0.11756	0.07681	1.93	0.00659	0.01009	0.00659	200	0.28496	3.52980	0.00659			
EXTERIOR STAIRS															
RAILINGS															
WOOD	LF	0.02265	0.20010	0.02265	0.74	0.00194	0.01717	0.00194	100	0.16835	3.87536	0.00194			
METAL	LF	0.03769	0.15401	0.03769	1.05	0.00321	0.01322	0.00321	300	0.78195	26.61236	0.00321			
WROUGHT IRON EXT.-ST. RAIL-	LF	0.07955	0.18878	0.07955	2.07	0.00683	0.01620	0.00683	200	2.18088	27.11480	0.00683			
STEEL UNPNTD. EXT. STAIR	LF	0.01955	0.01252	0.01955	0.48	0.00168	0.00107	0.00168	300	2.14240	27.03080	0.00168			
STEPS															
CONCRETE	SF	0.01475	0.01490	0.01475	0.36	0.00127	0.00128	0.00127	300	2.93605	16.87520	0.00127			
WOOD	SF	0.02624	0.36373	0.02624	0.76	0.00225	0.01173	0.00225	100	0.46410	3.68456	0.00225			
METAL	SF	0.02330	0.08266	0.02330	0.85	0.00191	0.02792	0.00191	300	2.16216	35.06480	0.00191			
MASONRY STEPS (UNPAINTED)	SF	0.00826	0.01156	0.00826	0.21	0.00071	0.00099	0.00071	400	1.19119	2.23640	0.00071			
MASONRY STEPS (PAINTED)	SF	0.04261	0.11386	0.04261	1.12	0.00366	0.00977	0.00366	400	1.61909	2.50020	0.00366			
QUARRY TILE STEPS	SF	0.01158	0.01805	0.01158	0.29	0.00099	0.00155	0.00099	300	1.59774	2.49100	0.00099			
EXTERIOR HARDWARE															
HINGES															
BRASS	CT	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	60	0.21151	19.08000	0.00000			
LOCK SET	CT	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	30	1.64840	124.02000	0.00000			
BRASS	CT	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	15	0.49413	90.10000	0.00000			
DOOR CLOSER	CT	0.17907	32.65224	0.17907	36.89	0.00000	0.00000	0.00000	20	0.93938	79.50000	0.00000			
BRASS	CT	0.24274	20.54280	0.24274	26.29	0.00000	0.00000	0.00000							
DEADBOLT	CT	0.24274	20.54280	0.24274	26.29	0.00000	0.00000	0.00000							
BRASS	CT	0.24274	20.54280	0.24274	26.29	0.00000	0.00000	0.00000							
WEATHER STRIPING	CT	0.24274	20.54280	0.24274	26.29	0.00000	0.00000	0.00000							

See NOTES on the last page of this table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)													PAGE 8
COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (C= 7%)					ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS							
	By Resources					Washington				Replacement and High Costs Tasks			
	um	labor	material	equipment	D.C. Total	labor	material	equipment	yr	labor	material	equipment	
BRASS	CT	0.17213	6.84760	0.17213	10.92				20	0.66612	26.50000	0.66612	
EXIT BOLT	CT	0.37940	78.10080	0.37940	87.08				25	2.05972	424.00000	2.05972	
METAL													

See NOTES on the last page of this table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)

PAGE 9

COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (d= 7%)									
	By Resources					Washington				
	labor		material		equipment	D.C. Total		equipment	material	labor
	unit									
ARCHITECTURE										
INTERIOR PARTITION										
MOVABLE PARTITION - METAL	SF	0.00632	0.00000		0.00632	0.15				
MOVABLE PARTITION - FABRIC	SF	0.00323	0.01777		0.00323	0.09				
INTERIOR DOORS										
METAL DOORS										
ST. PAINTED INTERIOR DOOR	CT	1.48709	42.49790		1.48709	77.68				
ST. (W/SAFETY GLASS)PAINTED	CT	1.83627	45.70038		1.83627	89.15				
ST. SLIDING PNTD. INT. DOOR	CT	1.64085	40.60390		1.64085	119.90				
ST. (INSUL. CORE)PNTD. INT.	CT	1.83627	44.43387		1.83627	87.93				
STEEL UNPAINTED INT. DOOR	CT	0.71416	34.94078		0.71416	44.74				
ST. (SAFETY GLASS)UNPNT INT	CT	0.76335	38.14326		0.76335	56.20				
ST. SLIDING UNPNTD. INT. DOOR	CT	0.58793	75.78039		0.58793	89.69				
ST. (INSUL. CORE)UNPNTD. INT.	CT	0.76335	36.92675		0.76335	54.99				
AL. (PLAIN & ANODIZED)INT.	CT	0.68468	57.76311		0.68468	73.96				
AL. (PAL)(SAFETY GLASS) FR.	CT	1.03387	60.94559		1.03387	85.43				
AL. SLIDING INTERIOR DOOR	CT	1.32113	127.34590		1.32113	158.62				
AL. (WOOD CORE) INT. DOOR	CT	1.03387	59.74908		1.03387	84.21				
AL. (INSUL.)P&A INT. DOOR	CT	1.03391	59.74908		1.03391	84.21				
FULLY GLAZED DOORS										
FULLY GLAZED AL. FR. DOOR	CT	1.03387	81.62793		1.03387	106.09				
FULLY GLAZED AL. FP. SLID.	CT	1.32113	142.44909		1.32113	173.71				
FULLY GLAZED WOODEN FR. DR	CT	1.56872	98.63971		1.56872	136.47				
GLAZED WOOD FR. SLIDING INT	CT	1.94232	164.54984		1.94232	210.51				
WOOD DOORS										
HOLLOW CORE INT. PNTD. DOOR	CT	3.75737	120.34232		3.75737	209.26				
HOLLOW CORE SLIDING INT.	CT	2.49721	126.11282		2.49721	185.20				
SOLID CORE INT. PNTD. DOOR	CT	3.16870	70.69920		3.16870	145.67				
SOLID CORE SLIDING INT. DR	CT	1.88200	126.44710		1.88200	170.98				
SOLID CORE(SAF GLASS)PNTD	CT	1.90691	73.90168		1.90691	119.02				
BIFOLD DOORS										
PANELED										
REPLACE PANELED (PAINTED) INTERIOR DOORS	CT	0.80535	30.31973		0.80535	49.37				
LOUVERED										
REPLACE LOUVERED (PAINTED) INTERIOR DOORS	CT	1.83935	23.06788		1.83935	66.59				
STEEL LOUVERED INTERIOR DOOR	CT	2.45389	84.42262		2.45389	147.41				
WOOD LOUVERED INT. DOOR	CT	0.09235	54.17387		0.09235	102.19				
STEEL VAULT DOOR	CT	5.02669	217.62187		5.02669	336.55				
METAL WALK-IN COOLER DOOR	CT	0.41416	34.94078		0.41416	44.74				
LEAD-LINED(WOOD) MEDICAL	CT	0.41416	34.94078		0.41416	44.74				
METAL WIRE MESH PNTD. INT	CT	0.89689	75.66598		0.89689	96.01				
METAL WIRE MESH PNTD. INT	CT	2.33091	10.10866		2.33091	65.26				
GARAGE & ROLL-UP DOORS										
STEEL SINGLE ROLL-UP DOOR	CT	0.05557	0.03250		0.05557	1.35				
STEEL DOUBLE ROLL-UP DOOR	CT	5.96581	265.55005		5.96581	406.70				
AL. SINGLE ROLL-UP DOOR	CT	11.56755	392.38200		11.56755	666.07				
REPLACE ALUMINUM SINGLE ROLL-UP DOOR	CT	5.66990	246.88918		5.66990	381.04				
AL. DOUBLE ROLL-UP DOOR	CT	10.95106	289.84354		10.95106	548.95				
REPLACE ALUMINUM DOUBLE ROLL-UP DOOR	CT	5.47017	284.84902		5.47017	414.27				
WOOD SINGLE ROLL-UP DOOR	CT	8.77279	403.37982		8.77279	610.94				
REPLACE WOOD SINGLE ROLL-UP DOOR	CT									
WOOD DOUBLE ROLL-UP DOOR	CT									
REPLACE WOOD DOUBLE ROLL-UP DOOR	CT									
FIREPLACE										
CF/KNIEY										

See NOTES on the last page of this table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)													PAGE 10
COMPONENT DESCRIPTION	UN	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (C= 7%)				ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS							
		By Resources				Annual Maintenance and Repair					Replacement and High Costs Tasks		
		labor	material	equipment	D.C. Total	labor	material	equipment	yr	labor	material	equipment	
CLAY BRICK	SF	0.00527	0.00441	0.00527	0.13	0.00045	0.00038	0.00045	500	1.34004	4.87600	0.67002	
CONCRETE BRICK	SF	0.00527	0.00543	0.00527	0.13	0.00045	0.00047	0.00045	500	1.34004	1.68547	0.67002	
STONE	SF	0.00134	0.00664	0.00134	0.04	0.00012	0.00057	0.00012	500	0.34931	1.99386	0.17466	
METAL PIPE CHIMNEY	SF	0.00386	0.22118	0.00386	0.51	0.00033	0.01898	0.00033	200	1.82390	4.67248	0.91195	
MANTEL	LF	0.02419	0.11170	0.02419	0.68	0.00208	0.00959	0.00208	200	0.58058	0.72080	0.29822	
WOOD	LF	0.01528	0.01063	0.01528	0.37	0.00131	0.00091	0.00131	300	0.18616	0.18616	0.09308	
CONCRETE	LF	0.00094	0.00931	0.00094	0.03	0.00008	0.00080	0.00008	300	0.18616	1.80200	0.09308	
STONE	LF	0.00094	0.00931	0.00094	0.03	0.00008	0.00080	0.00008	300	0.18616	1.80200	0.09308	
FINISH	LF	0.00094	0.00931	0.00094	0.03	0.00008	0.00080	0.00008	300	0.18616	1.80200	0.09308	
BRICK	SF	0.01860	0.09031	0.01860	0.53	0.00160	0.00775	0.00160	300	1.08828	1.30380	0.54989	
CONCRETE BLOCK	SF	0.01860	0.04079	0.01860	0.90	0.00160	0.03954	0.00160	300	1.08828	1.55820	0.54989	
PLASTER	SF	0.01398	0.09981	0.01398	0.43	0.00120	0.00856	0.00120	100	0.23680	0.94660	0.23680	
WOOD	SF	0.01393	0.08562	0.01393	0.42	0.00120	0.00735	0.00120	100	0.29517	0.92220	0.15269	
FIREBRICK	SF	0.00554	0.00515	0.00554	0.14	0.00048	0.00044	0.00048	300	1.07679	0.99640	0.53840	
FIRE BRICK	SF	0.00554	0.00515	0.00554	0.14	0.00048	0.00044	0.00048	300	1.07679	0.99640	0.53840	
FLUES ARCHITECTURAL	LF	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	400	1.34004	4.73502	0.67002	
BAKED CLAY FLUE, ARCH.	LF	0.00000	0.00000	0.00000	0.25	0.00000	0.01395	0.00000	200	1.82390	3.61248	0.67002	
METAL PIPE FLUE, ARCH.	LF	0.00000	0.00000	0.00000	0.25	0.00000	0.01395	0.00000	200	1.82390	3.61248	0.67002	
INTERIOR ORNAMENT	LF	0.00000	0.00000	0.00000	0.25	0.00000	0.01395	0.00000	200	1.82390	3.61248	0.67002	
INTERIOR TRIM	LF	0.00000	0.00000	0.00000	0.25	0.00000	0.01395	0.00000	200	1.82390	3.61248	0.67002	
WOOD	LF	0.01211	0.08658	0.01211	0.37	0.00104	0.00743	0.00104	100	0.04778	0.85860	0.02899	
METAL	LF	0.01377	0.11324	0.01377	0.44	0.00118	0.00972	0.00118	200	0.04980	1.01760	0.04980	
TERRAZZO TRIM	LF	0.00642	0.01921	0.00642	0.17	0.00055	0.00165	0.00055	75	0.79888	2.65000	0.39944	
CERAMIC TRIM	LF	0.00642	0.00945	0.00642	0.16	0.00055	0.00081	0.00055	50	0.79888	1.30380	0.39944	
RUBBER / VINYL TRIM	LF	0.00877	0.20161	0.00877	0.40	0.00003	0.00061	0.00003	18	0.02847	0.65720	0.01424	
INTERIOR STAIRS	LF	0.00877	0.20161	0.00877	0.40	0.00003	0.00061	0.00003	18	0.02847	0.65720	0.01424	
RAILINGS	LF	0.00877	0.20161	0.00877	0.40	0.00003	0.00061	0.00003	18	0.02847	0.65720	0.01424	
WOOD	LF	0.02265	0.20010	0.02265	0.74	0.00194	0.01717	0.00194	100	0.16835	3.87536	0.09210	
METAL	LF	0.03769	0.15401	0.03769	1.05	0.00323	0.01322	0.00323	300	1.48174	1.84016	0.75160	
IRON INT. STAIR .ILING	LF	0.07955	0.18878	0.07955	2.07	0.00683	0.01620	0.00683	200	2.18088	27.11480	1.10968	
STEPS	SF	0.01475	0.14490	0.01475	0.36	0.00127	0.00128	0.00127	300	2.93605	16.84340	1.46803	
CONCRETE	SF	0.02624	0.13673	0.02624	0.76	0.00225	0.01173	0.00225	100	0.46410	3.68456	0.23998	
WOOD	SF	0.02330	0.32536	0.02330	0.85	0.00191	0.02792	0.00191	300	2.16216	35.04480	1.09181	
METAL	SF	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	400	1.59777	2.36660	0.79888	
MASONRY STEPS (UNPNTD)	SF	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	400	1.59777	2.36660	0.79888	
MASONRY STEPS (PAINTED)	SF	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	400	1.59777	2.36660	0.79888	
CARPETED STEPS	SF	0.02669	0.07963	0.02669	0.71	0.00229	0.00683	0.00229	400	1.61909	2.30020	0.82020	
RUBBER INTERIOR STEPS	SF	0.07037	6.11689	0.04109	7.69	0.00101	0.01042	0.00101	8	0.05239	5.36360	0.02820	
TERRAZZO INTERIOR STEPS	SF	0.11515	2.50392	0.05892	5.05	0.00023	0.00762	0.00023	18	0.38007	8.16200	0.19603	
INTERIOR HARDWARE	SF	0.01158	0.03265	0.01158	0.51	0.00099	0.00280	0.00099	300	1.59774	4.50500	0.79887	
HINGES	CT	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	60	0.21151	19.08000	0.21151	
BRASS	CT	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	30	1.64840	124.02000	1.64840	
LOCKSET	CT	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	15	0.49413	90.10000	0.49413	
DOOR CLOSER	CT	0.17907	32.65224	0.17907	36.89	0.00000	0.00000	0.00000	20	0.93938	79.50000	0.93938	
BRASS	CT	0.24274	20.54280	0.24274	26.29	0.00000	0.00000	0.00000	20	0.66612	26.50000	0.66612	
DEADBOLT	CT	0.17213	6.84760	0.17213	10.92	0.00000	0.00000	0.00000	20	0.66612	26.50000	0.66612	
BRASS	CT	0.17213	6.84760	0.17213	10.92	0.00000	0.00000	0.00000	20	0.66612	26.50000	0.66612	
WEATHER STRIPING	CT	0.17213	6.84760	0.17213	10.92	0.00000	0.00000	0.00000	20	0.66612	26.50000	0.66612	
BRASS	CT	0.17213	6.84760	0.17213	10.92	0.00000	0.00000	0.00000	20	0.66612	26.50000	0.66612	
EXIT BOLT	CT	0.37940	78.10080	0.37940	87.08	0.00000	0.00000	0.00000	25	2.05972	424.00000	2.05972	
METAL	CT	0.37940	78.10080	0.37940	87.08	0.00000	0.00000	0.00000	25	2.05972	424.00000	2.05972	

See NOTES on the last page of this table for Explanation of Column Headings

See NOTES on the last page of this table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)													PAGE 11
COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (DF 7%)					ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS							
	By Resources					Annual Maintenance and Repair							
	un	labor	material	equipment	D.C. Total	Washington	labor	material	equipment	yr	labor	material	equipment
ARCHITECTURE													
WALL FINISHES													
GYPSUM AND PLASTER													
PLASTER	SF	0.05009	0.22521	0.05009	1.41		0.00430	0.01933	0.00430	300	0.23335	2.29278	0.12597
SHEETROCK (STIPPLED)	SF	0.04511	0.20226	0.04511	1.27		0.00387	0.01736	0.00387	300	0.03549	0.41976	0.02704
SHEETROCK (UNSTIPPLED)	SF	0.04511	0.20173	0.04511	1.27		0.00387	0.01731	0.00387	300	0.03497	0.41376	0.02678
STUCCO INT. WALL FINISH	SF	0.10947	0.25086	0.10947	2.84		0.00939	0.02153	0.00939	300	0.27846	0.95400	0.15750
MASONRY AND TILE													
CLAY BLOCK	SF	0.00117	0.03538	0.00117	0.06		0.00010	0.00304	0.00010	500	0.20150	9.60360	0.10075
CLAY BLOCK (PAINTED)	SF	0.04483	0.23575	0.04483	1.30		0.00385	0.02023	0.00385	500	0.22009	9.67356	0.11934
CONCRETE BLOCK	SF	0.00117	0.00293	0.00117	0.03		0.00010	0.00025	0.00010	500	0.20150	0.84376	0.10075
CONCRETE BLOCK (PAINTED)	SF	0.04483	0.20330	0.04483	1.26		0.00385	0.01744	0.00385	500	0.22009	0.91372	0.11934
CLAY BRICK	SF	0.00453	0.00449	0.00453	0.11		0.00039	0.00039	0.00039	500	1.09213	1.21506	0.06607
CONCRETE BRICK	SF	0.00445	0.00543	0.00445	0.11		0.00038	0.00047	0.00038	500	1.09213	1.27340	0.06607
FIRE BRICK	SF	0.00445	0.00367	0.00445	0.11		0.00038	0.00031	0.00038	500	1.09200	0.96640	0.06607
TILE	SF	0.02043	0.01983	0.02043	0.50		0.00175	0.00170	0.00175	100	1.21342	1.29320	0.34600
MASONITE INT. WALL FINISH	SF	0.09045	0.25466	0.09045	2.39		0.00776	0.02185	0.00776	200	0.08726	1.21342	0.12134
GLAZED CMU INT WALL FINISH	SF	0.00117	0.01982	0.00117	0.05		0.00010	0.00170	0.00010	500	0.20150	0.62540	0.08726
PAPER, PLASTIC, FABRIC													
FORMICA	SF	0.00239	0.06502	0.00239	0.12		0.00021	0.00558	0.00021	30	0.02925	4.24000	0.01463
NYLON	SF	0.00239	0.01829	0.00239	0.07		0.00021	0.00139	0.00021	30	0.02925	1.06000	0.02925
POLYESTER	SF	0.00239	0.00943	0.00239	0.07		0.00021	0.00081	0.00021	30	0.02925	0.61480	0.02925
VINYL	SF	0.00229	0.00975	0.00229	0.06		0.00020	0.00084	0.00020	30	0.02925	0.63600	0.02925
WALLPAPER	SF	0.01031	0.11737	0.01031	0.36		0.00024	0.00067	0.00024	20	0.02925	0.42400	0.02925
FABRIC INT. WALL FINISH	SF	0.01031	0.31103	0.01031	0.55		0.00024	0.00178	0.00024	20	0.02925	1.12360	0.02925
CARPETED INT. WALL FINISH	SF	0.09108	2.21770	0.05345	4.25		0.00136	0.01136	0.00136	8	0.06734	1.85560	0.03567
WOODS													
PLYWOOD	SF	0.03843	0.17417	0.03843	1.08		0.00330	0.01495	0.00330	80	0.04758	0.88616	0.03309
PLYWOOD (UNFINISHED)	SF	0.00229	0.01252	0.00229	0.07		0.00020	0.01017	0.00020	60	0.32899	0.81620	0.01450
TIMBER (FINISHED)	SF	0.04262	0.17417	0.04262	1.18		0.00366	0.01495	0.00366	80	0.31889	0.88616	0.16874
TIMBER (UNFINISHED)	SF	0.00648	0.01252	0.00648	0.17		0.00056	0.01017	0.00056	70	0.30030	0.81620	0.15015
PANEL (SOLID)	SF	0.03426	0.16256	0.03426	1.02		0.00311	0.01395	0.00311	200	0.42406	0.53636	0.22133
PANEL (LAMINATED)	SF	0.03426	0.16185	0.03426	1.02		0.00311	0.01389	0.00311	200	0.42406	0.53636	0.22133
BOARD (FINISHED)	SF	0.03426	0.16174	0.03426	0.99		0.00299	0.01388	0.00299	80	0.04758	0.31376	0.03309
BOARD (UNFINISHED)	SF	0.00057	0.00090	0.00057	0.01		0.00005	0.00008	0.00005	60	0.02899	0.01450	0.01450
WAINSCOT	SF	0.04555	0.20229	0.04555	1.28		0.00391	0.01736	0.00391	80	0.22742	2.71996	0.12374
METAL													
ALUMINUM	SF	0.00000	0.00000	0.00000	0.00		0.00000	0.00000	0.00000	100	0.07319	1.92920	0.03660
STEEL INT. FINISH (UNPNTD)	SF	0.00200	0.02181	0.00200	0.07		0.00017	0.00187	0.00017	200	0.56936	5.53320	0.28468
STEEL INT. FINISH (PNTD)	SF	0.38391	8.67141	0.38391	17.75		0.03294	0.74410	0.03294	200	0.57070	2.75220	0.30173
WIRE MESH WALL	SF	0.32556	0.75856	0.32556	8.46		0.00000	0.06509	0.00000	200	0.07609	3.37080	0.17524
LEAD-LINED INT WALL FINISH	SF	0.00000	0.00000	0.00000	0.00		0.00000	0.00000	0.00000	100	2.20662	12.61400	1.10331
GLASS													
GLASS BLOCKS	SF	0.00426	0.04463	0.00426	0.15		0.00037	0.00383	0.00037	300	1.04013	12.11580	0.52007
PLATE GLASS WALL - INT.	SF	0.00141	0.03343	0.00141	0.07		0.00012	0.00287	0.00012	200	0.09906	8.48000	0.04953
SPECIAL													
STONE	SF	0.00117	0.00664	0.00117	0.03		0.00010	0.00057	0.00010	500	0.20150	1.80200	0.10075
ACoustical TILE WALL	SF	0.25031	0.74314	0.25031	6.67		0.02148	0.06377	0.02148	90	0.37141	0.54060	0.19637
CORR TILE WALL	SF	0.12610	0.89378	0.06675	3.69		0.00063	0.00337	0.00063	16	0.35048	2.52280	0.17524
ASB-ACOS FIRE RTO. TILE	SF	0.06398	0.18767	0.06398	1.70		0.00549	0.01610	0.00549	90	0.37141	0.64640	0.19637
FIBERGLASS PANELS, RIGID	SF	0.09130	0.27518	0.09130	2.44		0.00783	0.02361	0.00783	70	0.06540	1.77285	0.04750
CONCRETE													
UNFINISHED	SF	0.01691	0.00917	0.01691	0.41		0.00145	0.00079	0.00145	500	3.80861	4.63220	1.90431
CONCRETE (FINISHED)	SF	0.05910	0.20928	0.05910	1.61		0.00507	0.01796	0.00507	500	3.80861	4.63220	1.90431
FLOORING/FLOOR FINISH													
MASONRY & TILE PRODUCTS													
CERAMIC TILE	SF	0.00014	0.00019	0.00014	0.00		0.00001	0.00002	0.00001	50	0.18247	2.00340	0.18247
QUARRY TILE	SF	0.00014	0.00019	0.00014	0.00		0.00001	0.00002	0.00001	50	0.90337	1.72780	0.45169

See NOTES on the last page of this table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)

COMPONENT DESCRIPTION	UN	PRESENT NORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (¢ 7x)					ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS									
		By Resources					Annual Maintenance and Repair									
		Washington					Replacement and High Costs Tasks									
		labor	material	equipment	D.C. Total		labor	material	equipment	yr	labor	material	equipment			
BRICK	SF	0.00603	0.02125	0.00603	0.16		0.00052	0.00132	0.00052	60	0.43604	2.65731	0.21802			
MARBLE	SF	0.00030	0.00041	0.00030	0.01		0.00003	0.00003	0.00003	50	0.90337	7.52600	0.45169			
WOOD PARQUETRY	SF	0.01731	0.11204	0.01731	0.52		0.00119	0.00961	0.00119	40	0.19980	2.12000	0.09900			
MAPLE	SF	0.01501	0.11354	0.01501	0.47		0.00129	0.00974	0.00129	40	0.03804	2.19420	0.01902			
PLYWOOD	SF	0.00211	0.00795	0.00211	0.06		0.00018	0.00068	0.00018	40	0.02054	0.39220	0.01027			
METAL																
STEEL SHEET	SF	0.00282	0.24381	0.00282	0.31		0.00024	0.02092	0.00024	30	1.93258	3.28600	0.96629			
METAL GRATING	SF	0.00282	0.24381	0.00282	0.31		0.00024	0.02092	0.00024	30	1.93258	3.24360	0.96629			
SPECIAL SURFACES	SF	0.05851	2.11270	0.05851	3.40		0.00003	0.00235	0.00003	8	0.05200	1.86360	0.02600			
CARPET	SF	0.01127	0.55092	0.01127	0.80		0.00003	0.00106	0.00003	16	0.03237	1.59000	0.01619			
CORK FLOOR TILE	SF	0.00916	0.75064	0.00916	0.95		0.00003	0.00116	0.00003	18	0.02977	2.49100	0.01489			
SYNTHETIC SURFACE	SF	0.00986	0.41525	0.00986	0.63		0.00002	0.00066	0.00002	18	0.03237	1.37800	0.01619			
LINOLEUM	SF	0.00986	1.19463	0.00986	1.43		0.00002	0.00185	0.00002	18	0.03237	3.96440	0.03237			
VINYL TILE	SF	0.00986	0.75012	0.00986	3.29		0.00023	0.00112	0.00023	18	0.38007	2.49100	0.19003			
RUBBER TILE	SF	0.00311	0.00183	0.00311	0.08		0.00027	0.00016	0.00027	75	0.09425	0.50562	0.04713			
VINYL SHEET	SF	0.00421	0.14241	0.00366	0.24		0.00036	0.01222	0.00031	75	0.09841	0.50562	0.04921			
CONCRETE (UNFINISHED)	SF	0.00311	0.01921	0.00311	0.09		0.00027	0.00165	0.00027	75	0.09841	5.30000	0.04921			
CONCRETE (FINISHED)	SF	0.06122	0.23160	0.03164	1.59		0.00018	0.00043	0.00018	15	0.16324	0.62540	0.08162			
TERRAZZO	SF															
TERRAZZO, PRECAST	SF															
BITUMINOUS	SF															
CEILINGS																
GIPSUM AND PLASTER																
PLASTER	SF	0.04920	0.22597	0.04920	1.39		0.00422	0.01939	0.00422	300	0.23335	2.35638	0.12597			
SHEETROCK (STIPPLED)	SF	0.04511	0.20262	0.04511	1.27		0.00387	0.01739	0.00387	300	0.03549	0.48972	0.02704			
SHEETROCK (UNSTIPPLED)	SF	0.04511	0.20209	0.04511	1.27		0.00387	0.01739	0.00387	300	0.03549	0.48972	0.02704			
STUCCO INT. CEILING FINISH	SF	0.10947	0.25086	0.10947	2.84		0.00939	0.02153	0.00939	300	0.27846	0.95400	0.15750			
MASONRY AND TILE																
ACQUSTIC TILE	SF	0.00764	0.01994	0.00764	0.20		0.00066	0.00171	0.00066	70	0.02340	1.12095	0.01170			
ACQUSTIC TILE (DROPPED)	SF	0.00217	0.01219	0.00217	0.06		0.00019	0.00105	0.00019	70	0.00754	1.42040	0.00377			
CERAMIC (PAN)	SF	0.00113	0.00019	0.00113	0.00		0.00010	0.00002	0.00010	100	3.90988	1.72780	0.03478			
CERAMIC (TILE)	SF	0.00113	0.00192	0.00113	0.01		0.00010	0.00016	0.00010	100	3.90988	2.00340	1.95494			
PAPER PLASTIC, FABRIC																
PAPER	SF	0.01031	0.11737	0.01031	0.36		0.00024	0.00067	0.00024	20	0.02925	0.42400	0.02925			
PLASTIC	SF	0.00229	0.00975	0.00229	0.06		0.00020	0.00084	0.00020	30	0.02925	0.63600	0.02925			
FABRIC	SF	0.00229	0.00943	0.00229	0.06		0.00020	0.00081	0.00020	30	0.02925	0.61480	0.02925			
FORNICA CEILING FINISH	SF	0.00229	0.06502	0.00229	0.12		0.00020	0.00558	0.00020	30	0.02925	4.24000	0.02925			
WOODS																
WOOD (FINISHED)	SF	0.03868	0.04210	0.03868	0.96		0.00332	0.00361	0.00332	80	0.31889	0.94976	0.16874			
WOOD (UNFINISHED)	SF	0.00648	0.01252	0.00648	0.17		0.00056	0.00107	0.00056	60	0.30030	0.81620	0.30030			
METALS																
ALUMINUM PANELS	SF	0.06655	0.91965	0.06655	2.49		0.00571	0.07892	0.00571	100	0.06565	3.08460	0.03536			
METAL INT. FINISH (UNPNTD)	SF	0.00200	0.02181	0.00200	0.07		0.00017	0.00187	0.00017	200	0.57473	5.53320	0.28737			
GLASS																
PLATE GLASS (MOUNTED)	SF	0.00132	0.03999	0.00066	0.07		0.00011	0.00343	0.00006	60	0.09906	10.85440	0.04953			
PLATE GLASS (SUSPENDED)	SF	0.00453	0.34806	0.00227	0.45		0.00039	0.02987	0.00019	60	0.02015	10.85440	0.01008			
SINGLE UNIT GLASS SKYLIGHT	SF	0.00754	0.62881	0.03754	1.52		0.00322	0.05396	0.00322	300	0.17978	19.61000	0.08989			
SINGLE UNIT GLASS SKYLIGHT	SF	0.03735	0.52684	0.03735	1.41		0.00321	0.04521	0.00321	300	1.22586	16.43000	0.61293			
SPECIAL SURFACES																
ACQUSTIC TILE (SPECIAL PUR.)	SF	0.00217	0.01869	0.00217	0.07		0.00019	0.00160	0.00019	65	0.00754	1.84440	0.00377			
ACQUSTIC TILE (FIRE RATED)	SF	0.00317	0.01763	0.00317	0.10		0.00019	0.00153	0.00019	65	0.00754	1.79160	0.00377			
ASB.-ACOS. FIRE RFD. TILE	SF	0.06598	0.18767	0.06598	1.70		0.00549	0.01610	0.00549	65	0.37161	0.44660	0.19637			
FIBERGLASS PANELS, RIGID	SF	0.09130	0.27518	0.09130	2.44		0.00783	0.02361	0.00783	70	0.06536	1.77285	0.04748			
CONCRETE																
CONCRETE (UNFINISHED)	SF	0.00311	0.00183	0.00311	0.08		0.00027	0.00016	0.00027	500	3.80861	4.63220	1.90431			

See NOTES on the last page of this table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)														PAGE	13
COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (P= 7%)					ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS									
	By Resources					Annual Maintenance and Repair									
	um	labor	material	equipment	Washington	D.C. Total	labor	material	equipment	yr	labor	material	equipment		
CONCRETE (FINISHED)	SF	0.00421	0.14241	0.00366	0.24	0.24	0.00036	0.01222	0.00031	500	3.80861	4.63220	1.90431		
See NOTES on the last page of this table for Explanation of Column Headings															



### Notes

1. The resources listed in this table are as of the Date of Study (DOS) and have been calculated using a present worth discount factor (d) of 7 percent. The Date of Study (DOS) is the Beneficial Occupancy Date (BOD). All tasks are assumed to occur at the end of the year. All resources have been assumed to be constant with no differential escalation from year to year.

2. Component Description - This column contains an indented list of systems, subsystems, components, and high cost task descriptions.

3. Unit of Measure (UM) - This column contains a two-character code to indicate the measurement unit for the component. Units used in this column are as follows:

CT	Count
LF	Linear Foot
SF	Square Foot
TF	Thousands of Linear Feet

4. Labor - Labor resources can be used in one of two ways: (1) labor hours per unit of measure, or (2) dollars per unit of measure assuming a \$1.00/hr labor rate.

5. Materials - Material resources are expressed in dollars per unit of measure in July 1988 dollars for the Washington, DC, area.

6. Equipment - Equipment resources can be used in one of two ways: (1) equipment hours per unit of measure, or (2) dollars per unit of measure assuming a \$1.00/hr equipment rate.

7. Washington, DC, Total - The dollars per unit of measure figures were calculated by applying the Military District of Washington labor and equipment rates to the labor and equipment resources, then adding the labor, material, and equipment costs together to form one total cost figure.

8. Year (YR) - This column contains the average age of the component when the high cost task or replacement task would be performed.

9. Engineered Performance Standards (EPS) - Most labor and equipment resource data is based on the DOD series of Technical Bulletins as discussed in the body of the report.

**APPENDIX B:**

**LIFE-CYCLE COST ANALYSIS TABLE (10 PERCENT)**

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)													PAGE 1	
COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (d=10%)					ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS								
	un	By Resources			Washington D.C. Total	Annual Maintenance and Repair								Replacement and High Costs Tasks
		labor	material	equipment		labor	material	equipment	yr	labor	material	equipment		
ARCHITECTURE														
ROOFING														
ROOF COVERING														
BUILTUP ROOFING	SF	0.03987	0.37166	0.01994	1.25	0.00487	0.03167	0.00244	28	0.04938	0.70490	0.02469		
PLACE NEW MEMBRANE OVER EXISTING -BUILTUP	SF	0.02415	0.33069	0.01208	0.86	0.00245	0.03218	0.00123	14	0.02414	0.69960	0.01207		
MOD.BIT./THERMOPLASTIC	SF	0.01667	0.23941	0.00833	0.61	0.00173	0.02202	0.00086	20	0.05659	0.85860	0.02829		
THERMOSETTING	SF	0.01809	0.10432	0.00904	0.50	0.00253	0.01458	0.00126	70	0.03683	0.69960	0.01841		
SLATE	SF	0.01760	0.24341	0.00881	0.50	0.00253	0.01458	0.00126	70	0.04585	6.04200	0.03442		
CEMENT ASBESTOS	SF	0.01760	0.24341	0.00881	0.50	0.00253	0.01458	0.00126	70	0.05437	6.04200	0.03442		
TILE	SF	0.01760	0.24341	0.00881	0.50	0.00253	0.01458	0.00126	70	0.05437	6.04200	0.03442		
ROLL ROOFING	SF	0.07156	0.42684	0.03578	2.01	0.00757	0.01536	0.00378	10	0.04141	0.74963	0.02070		
SHINGLES	SF	0.02222	0.22132	0.01111	0.71	0.00262	0.02383	0.00131	40	0.04118	0.74963	0.02070		
REPLACE NEW OVER EXISTING - SHINGLED ROOF	SF	0.01422	0.11058	0.00711	0.42	0.00199	0.01546	0.00099	30	0.02996	0.43460	0.01498		
METAL	SF	0.02161	1.15262	0.01040	1.63	0.00228	0.06265	0.00114	20	0.04543	2.17300	0.18132		
FIBERGLASS RIGID STP. ROOF	SF	0.04260	0.11748	0.02131	1.06	0.00596	0.01642	0.00298	60	0.06123	6.01550	0.02272		
CONCRETE SEALED PANEL ROOF	SF	0.03950	0.08408	0.01974	0.96	0.00552	0.01175	0.00276	300	0.04342	24.07419	0.03061		
CONCRETE SEALED PANEL R/F	SF	0.09872	0.62998	0.04936	2.81	0.01340	0.08807	0.00690	500	3.81056	18.03219	1.90528		
CONCRETE SEALED POURED	SF	0.09872	0.62998	0.04936	2.81	0.01340	0.08807	0.00690	500	3.81056	18.03219	1.90528		
FIBERGLASS RIGID ROOF	SF	0.03832	1.15262	0.01915	2.00	0.00468	0.06266	0.00234	20	0.04133	6.01550	0.02066		

See NOTES on the last page of this table for Explanation of Column Headings

See NOTES on the last page of this table for Explanation of Column Headings

COMPONENT DESCRIPTION	UM	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (d=10%)				ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS									
		By Resources				Annual Maintenance and Repair					Replacement and High Costs Tasks				
						Washington		D.C. Total			labor		equipment		
		labor	material	equipment		labor	material	equipment			labor	material	equipment		
ARCHITECTURE															
EXTERIOR WALL															
ADOBEE First Floor	SF	0.03561	0.39957	0.03561	1.24	0.00498	0.05586	0.00498	300		1.10968	2.18360		0.56362	
ADOBEE Second Floor	SF	0.07430	0.39957	0.07430	2.16	0.01039	0.05586	0.01039	300		1.24670	2.18360		0.63954	
ADOBEE Third Floor	SF	0.10262	0.39957	0.10262	2.83	0.01435	0.05586	0.01435	300		1.38333	2.18360		0.71513	
CLAY BRICK First Floor	SF	0.00176	0.00177	0.00176	0.04	0.00025	0.00025	0.00025	500		1.09213	1.21900		0.54607	
CLAY BRICK Second Floor	SF	0.00390	0.00177	0.00390	0.07	0.00042	0.00025	0.00042	500		1.1433	1.21900		0.60717	
CLAY BRICK Third Floor	SF	0.00370	0.00177	0.00370	0.09	0.00052	0.00025	0.00052	500		1.33640	1.21900		0.68820	
CLAY BRICK (UP/P) 1st Flr.	SF	0.01972	0.04127	0.01972	0.51	0.00031	0.00027	0.00031	500		1.12866	1.30380		0.58260	
CLAY BRICK (UP/P) 2nd Flr.	SF	0.03164	0.04127	0.03164	0.79	0.00060	0.00027	0.00060	500		1.26750	1.30380		0.66034	
CLAY BRICK (UP/P) 3rd Flr.	SF	0.04260	0.04127	0.04260	1.05	0.00079	0.00027	0.00079	500		1.40608	1.30380		0.73768	
CONCRETE BRICK 1st Floor	SF	0.00176	0.00214	0.00176	0.04	0.00025	0.00030	0.00025	500		1.09213	1.47340		0.54607	
CONCRETE BRICK 2nd Floor	SF	0.00360	0.00214	0.00360	0.07	0.00042	0.00030	0.00042	500		1.21420	1.47340		0.60717	
CONCRETE BRICK 3rd Floor	SF	0.00373	0.00214	0.00373	0.09	0.00052	0.00030	0.00052	500		1.33640	1.47340		0.68820	
CONCRETE BRICK (UP/P) 1 Fl	SF	0.01948	0.04164	0.01948	0.50	0.00028	0.00032	0.00028	500		1.2846	1.55820		0.58260	
REFINISH EXTERIOR WALL - 1ST FLOOR	SF	0.03165	0.04164	0.03165	0.79	0.00060	0.00032	0.00060	500		1.26750	1.55820		0.66034	
REFINISH PAINTED CONCRETE BRICK EXT. WALL - 2	SF	0.04260	0.04164	0.04260	1.05	0.00079	0.00032	0.00079	500		1.40608	1.55820		0.73768	
REFINISH PAINTED CONC. BRICK EXT. WALL - 3RD FL	SF	0.00047	0.01396	0.00047	0.03	0.00007	0.00195	0.00007	500		0.20150	0.60360		0.05969	
STRUCTURAL CLAY TILE 1 Flr	SF	0.00156	0.01396	0.00156	0.05	0.00022	0.00195	0.00022	500		0.23465	0.60360		0.11733	
STRUCTURAL CLAY TILE 2 Flr	SF	0.00218	0.01396	0.00218	0.07	0.00031	0.00195	0.00031	500		0.26767	0.60360		0.13384	
STRUCT. CLAY TILE UP/P 1 Fl	SF	0.01818	0.05346	0.01818	0.48	0.00010	0.00197	0.00010	500		0.23803	0.68840		0.13728	
REFINISH PAINTED STRUCT. CLAY TILE EXT. WALL	SF	0.03021	0.05346	0.03021	0.77	0.00040	0.00197	0.00040	500		0.28235	0.68840		0.12825	
STRUCT. CLAY TILE UP/P 2 Fl	SF	0.04105	0.05346	0.04105	1.02	0.00057	0.00197	0.00057	500		0.33735	0.68840		0.17050	
STRUCT. CLAY TILE UP/P 3 Fl	SF	0.00046	0.00123	0.00046	0.01	0.00006	0.00017	0.00006	500		0.05959	0.84376		0.20352	
CONCRETE BLOCK First Floor	SF	0.00156	0.00123	0.00156	0.04	0.00022	0.00017	0.00022	500		0.23465	0.84376		0.10075	
CONCRETE BLOCK Second Floor	SF	0.00218	0.00123	0.00218	0.05	0.00031	0.00017	0.00031	500		0.26767	0.84376		0.11733	
CONCRETE BLOCK Third Floor	SF	0.01819	0.00472	0.01819	0.47	0.00010	0.00019	0.00010	500		0.23803	0.92856		0.13728	
REFINISH PAINTED CONCRETE BLOCK EXT. WALL -	SF	0.03021	0.04072	0.03021	0.76	0.00040	0.00019	0.00040	500		0.28235	0.92856		0.12825	
CONCRETE BLOCK (UP/P) 2 Fl	SF	0.04105	0.04072	0.04105	1.01	0.00057	0.00019	0.00057	500		0.33735	0.92856		0.17050	
CONCRETE BLOCK (UP/P) 3 Fl	SF	0.00046	0.00123	0.00046	0.01	0.00006	0.00017	0.00006	500		0.05959	0.92856		0.20352	
REFINISH PAINTED CONCRETE BLOCK EXT. WALLS -	SF	0.02112	0.04134	0.02112	0.54	0.00051	0.00027	0.00051	500		0.25949	0.84376		0.05969	
CONCRETE (UP/P) First Flr.	SF	0.03343	0.04134	0.03343	0.83	0.00085	0.00027	0.00085	500		0.28235	0.84376		0.10075	
REFINISH CONCRETE EXTERIOR WALL - 1ST FLOOR	SF	0.04455	0.04134	0.04455	1.10	0.00106	0.00027	0.00106	500		0.33735	0.84376		0.11733	
CONCRETE (UP/P) Second Flr	SF	0.00046	0.00262	0.00046	0.01	0.00006	0.00037	0.00006	500		0.05959	1.80200		0.05969	
CONCRETE (UP/P) Third Flr.	SF	0.00218	0.00262	0.00218	0.04	0.00022	0.00037	0.00022	500		0.23465	1.80200		0.10075	
REFINISH CONCRETE EXTERIOR WALL - 2ND FLOOR	SF	0.04769	0.04769	0.04769	0.05	0.00031	0.00024	0.00031	500		0.27867	1.80200		0.13384	
REFINISH CONCRETE EXTERIOR WALL - 3RD FLOOR	SF	0.01887	0.04769	0.01887	0.49	0.00019	0.00024	0.00019	500		0.28235	0.94460		0.15750	
STONE First Floor	SF	0.00046	0.00262	0.00046	0.01	0.00006	0.00037	0.00006	500		0.05959	0.94460		0.20352	
STONE Second Floor	SF	0.00156	0.00262	0.00156	0.04	0.00022	0.00037	0.00022	500		0.23465	0.94460		0.10075	
STONE Third Floor	SF	0.00218	0.00262	0.00218	0.05	0.00031	0.00037	0.00031	500		0.26767	0.94460		0.11733	
REFINISH STUCCO EXTERIOR WALL - 1ST FLOOR	SF	0.03217	0.04769	0.03217	0.81	0.00067	0.00024	0.00067	300		0.33241	0.94460		0.12779	
REFINISH STUCCO EXTERIOR WALL - 2ND FLOOR	SF	0.04384	0.04769	0.04384	1.08	0.00096	0.00024	0.00096	300		0.40963	0.94460		0.14417	
REFINISH STUCCO EXTERIOR WALL - 3RD FLOORS	SF	0.00069	0.00496	0.00069	0.02	0.00010	0.00069	0.00010	500		0.05969	0.07420		0.23966	
TERRACOTTA First Floor	SF	0.00069	0.00069	0.00069	0.02	0.00010	0.00069	0.00010	500		0.35009	3.41320		0.05969	
See NOTES on the last page of this table for Explanation of Column Headings															

COMPONENT DESCRIPTION	UN	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (0-10%)				ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS			
		By Resources				Annual Maintenance and Repair			
		labor	material	equipment	D.C. Total	labor	material	equipment	yr
TERRAZZITA Second Floor	SF	0.00181	0.00496	0.00181	0.06	0.00025	0.00069	0.00025	500
TERRAZZITA Third Floor	SF	0.00181	0.00496	0.00181	0.05	0.00025	0.00069	0.00025	500
WOOD FINISHED 1 COAT 1 FL	SF	0.03077	0.07585	0.03077	0.80	0.00012	0.00019	0.00012	125
REFINISH WOOD FINISHED (S.CT) EXT. WALL - 1	SF	0.05128	0.07585	0.05128	1.29	0.00042	0.00019	0.00042	125
WOOD FINISHED 1 COAT 2 FL	SF	0.07037	0.07585	0.07037	1.74	0.00059	0.00019	0.00059	125
REFINISH WOOD FINISHED (S.CT) EXT. WALL - 2	SF	0.07037	0.07585	0.07037	1.74	0.00059	0.00019	0.00059	125
WOOD FINISHED 1 COAT 3 FL	SF	0.02018	0.06704	0.02018	0.54	0.00012	0.00020	0.00012	125
REFINISH WOOD FINISHED (S.CT) EXT. WALL -3R	SF	0.02018	0.06704	0.02018	0.54	0.00012	0.00020	0.00012	125
WOOD FINISH MULTI-CT 1 FL	SF	0.03240	0.06704	0.03240	0.83	0.00043	0.00020	0.00043	125
REFINISH WOOD FINISHED (MULTI-CT) EXT. WALL	SF	0.03240	0.06704	0.03240	0.83	0.00043	0.00020	0.00043	125
WOOD FINISH MULTI-CT 2 FL	SF	0.04343	0.06704	0.04343	1.09	0.00060	0.00020	0.00060	125
REFINISH WOOD FINISHED (MULTI-CT)EXT. WALL	SF	0.04343	0.06704	0.04343	1.09	0.00060	0.00020	0.00060	125
WOOD FINISH MULTI-CT 3 FL	SF	0.00112	0.00470	0.00112	0.03	0.00016	0.00046	0.00016	125
REFINISH WOOD FINISHED (MULTI-CT) EXT. WALL	SF	0.00112	0.00470	0.00112	0.03	0.00016	0.00046	0.00016	125
WOOD SHAKES UNFINISH 1 FL	SF	0.00598	0.00470	0.00598	0.15	0.00084	0.00046	0.00084	125
WOOD SHAKES UNFINISH 2 FL	SF	0.00598	0.00470	0.00598	0.15	0.00084	0.00046	0.00084	125
WOOD SHAKES UNFINISH 3 FL	SF	0.00598	0.00470	0.00598	0.21	0.00084	0.00046	0.00084	125
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.03858	0.07991	0.03858	0.99	0.00031	0.00076	0.00031	125
WOOD SHAKES UNFINISH 1 FL	SF	0.06731	0.07991	0.06731	1.67	0.00167	0.00076	0.00167	125
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.06731	0.07991	0.06731	1.67	0.00167	0.00076	0.00167	125
WOOD SHAKES UNFINISH 2 FL	SF	0.09104	0.07991	0.09104	2.23	0.00241	0.00076	0.00241	125
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.09104	0.07991	0.09104	2.23	0.00241	0.00076	0.00241	125
WOOD SHAKES UNFINISH 3 FL	SF	0.02915	0.10047	0.02915	0.79	0.00408	0.01405	0.00408	80
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.02915	0.10047	0.02915	0.79	0.00408	0.01405	0.00408	80
WOOD SHAKES UNFINISH 1 FL	SF	0.05688	0.10047	0.05688	1.45	0.00795	0.01405	0.00795	80
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.05688	0.10047	0.05688	1.45	0.00795	0.01405	0.00795	80
WOOD SHAKES UNFINISH 2 FL	SF	0.07991	0.10047	0.07991	1.99	0.01117	0.01405	0.01117	80
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.07991	0.10047	0.07991	1.99	0.01117	0.01405	0.01117	80
WOOD SHAKES UNFINISH 3 FL	SF	0.00055	0.05601	0.00055	0.02	0.00084	0.00084	0.00084	100
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00055	0.05601	0.00055	0.02	0.00084	0.00084	0.00084	100
WOOD SHAKES UNFINISH 1 FL	SF	0.00245	0.06401	0.00245	0.07	0.00037	0.00084	0.00037	100
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00245	0.06401	0.00245	0.07	0.00037	0.00084	0.00037	100
WOOD SHAKES UNFINISH 2 FL	SF	0.00331	0.06401	0.00331	0.10	0.00051	0.00084	0.00051	100
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00331	0.06401	0.00331	0.10	0.00051	0.00084	0.00051	100
WOOD SHAKES UNFINISH 3 FL	SF	0.00222	0.01266	0.00222	0.07	0.00031	0.00181	0.00031	150
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00222	0.01266	0.00222	0.07	0.00031	0.00181	0.00031	150
WOOD SHAKES UNFINISH 1 FL	SF	0.00335	0.01266	0.00335	0.09	0.00047	0.00181	0.00047	150
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00335	0.01266	0.00335	0.09	0.00047	0.00181	0.00047	150
WOOD SHAKES UNFINISH 2 FL	SF	0.00441	0.01266	0.00441	0.12	0.00062	0.00181	0.00062	150
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00441	0.01266	0.00441	0.12	0.00062	0.00181	0.00062	150
WOOD SHAKES UNFINISH 3 FL	SF	0.01966	0.04994	0.01966	0.52	0.00047	0.00199	0.00047	150
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.01966	0.04994	0.01966	0.52	0.00047	0.00199	0.00047	150
WOOD SHAKES UNFINISH 1 FL	SF	0.02889	0.04994	0.02889	0.73	0.00077	0.00199	0.00077	150
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.02889	0.04994	0.02889	0.73	0.00077	0.00199	0.00077	150
WOOD SHAKES UNFINISH 2 FL	SF	0.03797	0.04994	0.03797	0.95	0.00105	0.00199	0.00105	150
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.03797	0.04994	0.03797	0.95	0.00105	0.00199	0.00105	150
WOOD SHAKES UNFINISH 3 FL	SF	0.00163	0.01762	0.00163	0.06	0.00024	0.00246	0.00024	300
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00163	0.01762	0.00163	0.06	0.00024	0.00246	0.00024	300
WOOD SHAKES UNFINISH 1 FL	SF	0.00290	0.01762	0.00290	0.09	0.00041	0.00246	0.00041	300
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00290	0.01762	0.00290	0.09	0.00041	0.00246	0.00041	300
WOOD SHAKES UNFINISH 2 FL	SF	0.00364	0.01762	0.00364	0.10	0.00051	0.00246	0.00051	300
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00364	0.01762	0.00364	0.10	0.00051	0.00246	0.00051	300
WOOD SHAKES UNFINISH 3 FL	SF	0.00839	0.01762	0.00839	0.40	0.00117	0.00278	0.00117	150
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00839	0.01762	0.00839	0.40	0.00117	0.00278	0.00117	150
WOOD SHAKES UNFINISH 1 FL	SF	0.02619	0.01762	0.02619	0.82	0.00366	0.00278	0.00366	150
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.02619	0.01762	0.02619	0.82	0.00366	0.00278	0.00366	150
WOOD SHAKES UNFINISH 2 FL	SF	0.03609	0.01762	0.03609	1.05	0.00505	0.00278	0.00505	150
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.03609	0.01762	0.03609	1.05	0.00505	0.00278	0.00505	150
WOOD SHAKES UNFINISH 3 FL	SF	0.00215	0.00916	0.00215	0.06	0.00030	0.00128	0.00030	40
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00215	0.00916	0.00215	0.06	0.00030	0.00128	0.00030	40
WOOD SHAKES UNFINISH 1 FL	SF	0.01270	0.00916	0.01270	0.31	0.00128	0.00128	0.00128	40
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.01270	0.00916	0.01270	0.31	0.00128	0.00128	0.00128	40
WOOD SHAKES UNFINISH 2 FL	SF	0.01859	0.00916	0.01859	0.45	0.00260	0.00128	0.00260	40
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.01859	0.00916	0.01859	0.45	0.00260	0.00128	0.00260	40
WOOD SHAKES UNFINISH 3 FL	SF	0.00142	0.00883	0.00142	0.04	0.00020	0.00124	0.00020	100
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00142	0.00883	0.00142	0.04	0.00020	0.00124	0.00020	100
WOOD SHAKES UNFINISH 1 FL	SF	0.00766	0.00883	0.00766	0.19	0.00107	0.00124	0.00107	100
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.00766	0.00883	0.00766	0.19	0.00107	0.00124	0.00107	100
WOOD SHAKES UNFINISH 2 FL	SF	0.01105	0.00883	0.01105	0.27	0.00155	0.00124	0.00155	100
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.01105	0.00883	0.01105	0.27	0.00155	0.00124	0.00155	100
WOOD SHAKES UNFINISH 3 FL	SF	0.02183	0.03662	0.02183	0.55	0.00037	0.00086	0.00037	160
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.02183	0.03662	0.02183	0.55	0.00037	0.00086	0.00037	160
WOOD SHAKES UNFINISH 1 FL	SF	0.04551	0.03662	0.04551	1.11	0.00210	0.00086	0.00210	160
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.04551	0.03662	0.04551	1.11	0.00210	0.00086	0.00210	160
WOOD SHAKES UNFINISH 2 FL	SF	0.06293	0.03662	0.06293	1.53	0.00306	0.00086	0.00306	160
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.06293	0.03662	0.06293	1.53	0.00306	0.00086	0.00306	160
WOOD SHAKES UNFINISH 3 FL	SF	0.01188	0.03370	0.01188	0.31	0.00166	0.00471	0.00166	125
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.01188	0.03370	0.01188	0.31	0.00166	0.00471	0.00166	125
WOOD SHAKES UNFINISH 1 FL	SF	0.02021	0.03370	0.02021	0.51	0.00282	0.00471	0.00282	125
REFINISH WOOD SHAKES (FIN.) EXTERIOR WALL	SF	0.02021	0.03370	0.02021	0.51	0.00282	0.00471	0.00282	125

See NOTES on the last page of this Table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)

COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (d=10%)					ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS															
	By Resources					Washington					Annual Maintenance and Repair					Replacement and High Costs Tasks					
	unit	Labor				D.C. Total	unit	Labor				unit	Labor				unit	Labor			
		material	equipment	yr	material			equipment	yr	material	equipment		yr	material	equipment	yr		material	equipment	yr	
PORCELAIN PANEL Third Flr.	SF	0.02475	0.03370	0.02475	0.62	0.00346	0.00471	0.00346	125	0.12491	2.52174	0.04164	0.0164	0.01037	1.24020	0.01037	0.01374	2.52174	0.04164	0.0164	
ALUM. CORR. PANEL 1st Flr.	SF	0.00191	0.01536	0.00191	0.06	0.00027	0.00215	0.00027	60	0.02074	1.24020	0.01037	0.01037	0.01037	1.24020	0.01037	0.01037	1.24020	0.01037	0.01037	
ALUM. CORR. PANEL 2nd Flr.	SF	0.01103	0.01536	0.01103	0.27	0.00154	0.00215	0.00154	60	0.04971	1.24020	0.02486	0.02486	0.02486	1.24020	0.02486	0.02486	1.24020	0.02486	0.02486	
ALUM. CORR. PANEL 3rd Flr.	SF	0.01604	0.01536	0.01604	0.38	0.00224	0.00215	0.00224	60	0.07000	1.24020	0.03502	0.03502	0.03502	1.24020	0.03502	0.03502	1.24020	0.03502	0.03502	
EXT. GYPSUM BOARD-PTD 1 Flr.	SF	0.03573	0.07257	0.03573	0.94	0.00028	0.00110	0.00028	100	0.08843	1.31122	0.05902	0.05902	0.05902	1.31122	0.05902	0.05902	1.31122	0.05902	0.05902	
EXT. GYPSUM BOARD-PTD 2 Flr.	SF	0.06895	0.07257	0.06895	1.70	0.00152	0.00110	0.00152	100	0.11682	1.31122	0.07795	0.07795	0.07795	1.31122	0.07795	0.07795	1.31122	0.07795	0.07795	
EXT. GYPSUM BOARD-PTD 3 Flr.	SF	0.09679	0.07257	0.09679	2.36	0.00221	0.00110	0.00221	100	0.15060	1.31122	0.10241	0.10241	0.10241	1.31122	0.10241	0.10241	1.31122	0.10241	0.10241	
EXT. GYPSUM BOARD-PTD 4 Flr.	SF	0.10150	0.07257	0.10150	3.38	0.00030	0.00121	0.00030	100	0.12397	1.43736	0.09456	0.09456	0.09456	1.43736	0.09456	0.09456	1.43736	0.09456	0.09456	
EXT. GYPSUM BOARD-PTD 5 Flr.	SF	0.14020	0.07257	0.14020	4.30	0.00154	0.00121	0.00154	100	0.16229	1.43736	0.12349	0.12349	0.12349	1.43736	0.12349	0.12349	1.43736	0.12349	0.12349	
EXT. GYPSUM BOARD-PTD 6 Flr.	SF	0.17452	0.07257	0.17452	5.11	0.00223	0.00121	0.00223	100	0.20035	1.43736	0.15216	0.15216	0.15216	1.43736	0.15216	0.15216	1.43736	0.15216	0.15216	
EXT. GYPSUM BOARD-PTD 7 Flr.	SF	0.00117	0.00337	0.00117	0.03	0.00016	0.00047	0.00016	100	0.03764	0.54060	0.01096	0.01096	0.01096	0.54060	0.01096	0.01096	0.54060	0.01096	0.01096	
MASONITE PANEL, SEALED 1FL	SF	0.00606	0.00337	0.00606	0.15	0.00085	0.00047	0.00085	100	0.07645	0.54060	0.02883	0.02883	0.02883	0.54060	0.02883	0.02883	0.54060	0.02883	0.02883	
MASONITE PANEL, SEALED 2FL	SF	0.00876	0.00337	0.00876	0.21	0.00122	0.00047	0.00122	100	0.09498	0.54060	0.04749	0.04749	0.04749	0.54060	0.04749	0.04749	0.54060	0.04749	0.04749	
FIBERGLASS PANEL, RIGID 1FL	SF	0.03753	0.11316	0.03753	1.00	0.00039	0.00226	0.00039	150	0.08536	1.79405	0.04749	0.04749	0.04749	1.79405	0.04749	0.04749	1.79405	0.04749	0.04749	
REFINISH FIBERGLASS PANELS RIGID FIRST FLO	SF	0.07468	0.11316	0.07468	1.88	0.00235	0.00226	0.00235	150	0.12276	1.79405	0.06360	0.06360	0.06360	1.79405	0.06360	0.06360	1.79405	0.06360	0.06360	
REFINISH FIBERGLASS PANELS, RIGID SECOND F	SF	0.10551	0.11316	0.10551	2.61	0.00343	0.00226	0.00343	150	0.17940	1.79405	0.08506	0.08506	0.08506	1.79405	0.08506	0.08506	1.79405	0.08506	0.08506	
REFINISH FIBERGLASS PANEL, RIGID THIRD FLO	SF	0.10551	0.11316	0.10551	2.61	0.00343	0.00226	0.00343	150	0.17940	1.79405	0.08506	0.08506	0.08506	1.79405	0.08506	0.08506	1.79405	0.08506	0.08506	
EXTERIOR DOORS																					
METAL DOORS																					
ALUMINUM (PLAIN/UNDOZED)	CT	0.36210	0.36210	0.36210	38.40	0.05062	4.17081	0.05062	65	2.23574	265.00000	2.23574	2.23574	2.23574	265.00000	2.23574	2.23574	265.00000	2.23574	2.23574	
AL. (PCL) FRAME/DOOR	CT	0.57641	0.57641	0.57641	45.44	0.08059	4.44562	0.08059	65	2.73004	327.87125	2.73004	2.73004	2.73004	327.87125	2.73004	2.73004	327.87125	2.73004	2.73004	
AL. SLIDING EXT.(PCL) DOOR	CT	0.57641	0.57641	0.57641	45.44	0.08059	4.44562	0.08059	65	2.73004	327.87125	2.73004	2.73004	2.73004	327.87125	2.73004	2.73004	327.87125	2.73004	2.73004	
AL.(WOOD CORE) EXT. DOOR	CT	0.57641	0.57641	0.57641	45.44	0.08059	4.44562	0.08059	65	2.73004	327.87125	2.73004	2.73004	2.73004	327.87125	2.73004	2.73004	327.87125	2.73004	2.73004	
AL.(CINSLA)PCL EXT. DOOR	CT	0.57641	0.57641	0.57641	45.44	0.08059	4.44562	0.08059	65	2.73004	327.87125	2.73004	2.73004	2.73004	327.87125	2.73004	2.73004	327.87125	2.73004	2.73004	
STEEL (PAINTED)	CT	0.72785	23.15875	0.72785	40.38	0.10176	3.23781	0.10176	80	2.59350	121.60000	2.59350	2.59350	2.59350	121.60000	2.59350	2.59350	121.60000	2.59350	2.59350	
STEEL PAINTED EXT. DOOR	CT	0.72785	23.15875	0.72785	40.38	0.10176	3.23781	0.10176	80	2.59350	121.60000	2.59350	2.59350	2.59350	121.60000	2.59350	2.59350	121.60000	2.59350	2.59350	
ST. SLIDING PNTD EXT. DOOR	CT	1.07489	55.12440	1.07489	50.56	0.13257	6.85721	0.13257	80	3.14685	167.53732	3.14685	3.14685	3.14685	167.53732	3.14685	3.14685	167.53732	3.14685	3.14685	
ST.(CINSLA) CORE/PNTD EXT.DR	CT	0.94821	49.04687	0.94821	71.48	0.13257	6.85721	0.13257	80	3.14685	167.53732	3.14685	3.14685	3.14685	167.53732	3.14685	3.14685	167.53732	3.14685	3.14685	
ST.(CINSLA) CORE/PNTD EXT.DR	CT	1.07489	55.12440	1.07489	50.56	0.13257	6.85721	0.13257	80	3.14685	167.53732	3.14685	3.14685	3.14685	167.53732	3.14685	3.14685	167.53732	3.14685	3.14685	
STEEL (UNPAINTED)	CT	0.72785	23.15875	0.72785	40.38	0.10176	3.23781	0.10176	80	2.59350	121.60000	2.59350	2.59350	2.59350	121.60000	2.59350	2.59350	121.60000	2.59350	2.59350	
ST.(GLASS)UNPNTD EXT. DOOR	CT	0.64124	20.66140	0.64124	31.10	0.04169	2.61304	0.04169	80	2.63669	145.22000	2.63669	2.63669	2.63669	145.22000	2.63669	2.63669	145.22000	2.63669	2.63669	
ST.SLIDING UNPNTD EXT. DOOR	CT	0.31457	46.04653	0.31457	33.49	0.04169	2.61304	0.04169	80	2.73004	240.48000	2.73004	2.73004	2.73004	240.48000	2.73004	2.73004	240.48000	2.73004	2.73004	
ST.(CINSLA)UNPNTD EXT. DOOR	CT	0.44125	19.91471	0.44125	30.35	0.04169	2.61304	0.04169	80	2.73004	240.48000	2.73004	2.73004	2.73004	240.48000	2.73004	2.73004	240.48000	2.73004	2.73004	
FULLY GLAZED DOOR																					
ALUMINUM FRAME	CT	0.57689	31.66310	0.57689	45.31	0.08065	4.42680	0.08065	65	2.23574	395.38000	2.23574	2.23574	2.23574	395.38000	2.23574	2.23574	395.38000	2.23574	2.23574	
GLAZED AL.SLIDING EXT.DR	CT	0.50617	25.03655	0.50617	37.01	0.07077	3.50034	0.07077	65	5.63216	636.00000	5.63216	5.63216	5.63216	636.00000	5.63216	5.63216	636.00000	5.63216	5.63216	
WOOD FRAME (PAINTED)	CT	0.74435	42.39793	0.74435	60.01	0.10407	5.92762	0.10407	65	2.35677	122.57310	2.35677	2.35677	2.35677	122.57310	2.35677	2.35677	122.57310	2.35677	2.35677	
GLAZED WOOD SLID. EXT. DR	CT	0.83971	30.86061	0.83971	50.73	0.11740	4.31460	0.11740	50	5.79892	460.12480	5.79892	5.79892	5.79892	460.12480	5.79892	5.79892	460.12480	5.79892	5.79892	
WOOD DOORS																					
NOLLO CORE (PAINTED)	CT	1.04037	34.92316	1.04037	59.54	0.14545	4.88258	0.14545	30	6.05336	196.82080	6.05336	6.05336	6.05336	196.82080	6.05336	6.05336	196.82080	6.05336	6.05336	
NOLLO CORE SLID. WOOD EXT.DR	CT	1.27418	26.78241	1.27418	56.93	0.17814	3.74443	0.17814	30	6.05336	211.78800	6.05336	6.05336	6.05336	211.78800	6.05336	6.05336	211.78800	6.05336	6.05336	
SOLID CORE (PAINTED)	CT	0.77021	20.78201	0.77021	38.50	0.10768	2.83508	0.10768	40	2.58492	223.32080	2.58492	2.58492	2.58492	223.32080	2.58492	2.58492	223.32080	2.58492	2.58492	
SOLID SLID. WOOD EXT. DOOR	CT	0.96974	16.23803	0.96974	39.18	0.13558	2.27023	0.13558	40	6.05336	233.90800	6.05336	6.05336	6.05336	233.90800	6.05336	6.05336	233.90800	6.05336	6.05336	
SOLID CORE CLASS PNTD EXT.	CT	0.98454	22.26385	0.98454	45.54	0.13765	3.10990	0.13765	40	2.58557	239.22080	2.58557	2.58557	2.58557	239.22080	2.58557	2.58557	239.22080	2.58557	2.5	

COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (d=10%)				ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS									
	By Resources				Annual Maintenance and Repair					Replacement and High Costs Tasks				
	um	Labor	material	equipment	D.C. Total	Washington	Labor	material	equipment	Yr	Labor	material	equipment	
WOOD COVERED EXT. DOOR	CT	2.20903	52.89770	2.20903	105.16		0.30864	7.39559	0.30864	40	6.04897	311.30080	3.23289	
ALUMINUM EXTERIOR GATE	CT	0.92261	21.24584	0.92261	43.07		0.12899	2.97037	0.12899	40	2.25334	421.24400	1.22691	
STEEL EXTERIOR GATE	CT	0.77590	14.81487	0.77590	33.17		0.10848	2.07126	0.10848	65	2.25334	256.94400	1.22691	
WOOD EXTERIOR GATE	CT	1.40676	117.75418	1.40676	151.09		0.19492	16.43727	0.19492	25	2.05286	472.76000	1.02691	
REPLACE WOOD EXTERIOR GATE (WALK & DRIVEWAY)	CT	0.84437	16.31251	0.84437	36.29		0.11805	2.28064	0.11805	65	2.25334	256.94400	1.22691	
WROUGHT IRON EXT. GATE	CT	0.84437	16.31251	0.84437	36.29		0.11805	2.28064	0.11805	65	2.25334	256.94400	1.22691	
SCREEN/STORM DOORS	CT	0.84437	16.31251	0.84437	36.29		0.11805	2.28064	0.11805	65	2.25334	256.94400	1.22691	
ALUMINUM (PLAIN/ANODIZED) PLASTIC	CT	2.32762	77.85509	2.32762	132.93		0.28882	8.28177	0.28882	20	2.23574	159.00000	2.23574	
ROLL-UP DOORS	CT	1.59742	73.26243	1.59742	111.06		0.18627	8.28177	0.18627	20	2.23574	119.78000	2.23574	
ST. FRAME-SINGLE (PAINTED)	CT	3.03066	71.27391	3.03066	143.17		0.42406	9.96476	0.42406	35	4.84587	176.85040	2.67316	
ST. FRAME-DOUBLE (PAINTED)	CT	5.57938	91.93730	5.57938	223.95		0.78005	12.85369	0.78005	35	5.38802	445.73000	3.21531	
AL. SINGLE ROLL-UP DOOR	CT	2.67603	131.98512	2.67603	195.30		0.36854	18.40722	0.36854	24	4.84587	135.25400	2.67316	
REPLACE ALUMINUM SINGLE ROLL-UP DOOR	CT	5.10227	151.71897	5.10227	272.44		0.70168	21.11688	0.70168	24	4.84587	131.17500	2.67316	
AL. DOUBLE ROLL-UP DOOR	CT	2.72829	160.27805	2.72829	224.83		0.36944	22.31077	0.36944	16	4.84587	239.92040	2.67316	
WOOD SINGLE ROLL-UP DOOR	CT	5.18115	232.89302	5.18115	355.48		0.69937	32.35728	0.69937	16	4.84587	235.85000	2.67316	
REPLACE WOOD SINGLE ROLL-UP DOOR	CT	2.42326	51.23327	2.42326	108.57		0.33879	7.16289	0.33879	48	11.41516	424.38160	6.70848	
WOOD DOUBLE ROLL-UP DOOR	CT	2.31927	37.67733	2.31927	92.55		0.32426	5.26764	0.32426	70	11.41516	387.28160	6.70848	
AL.(ONE LEAF) SPRING DOOR	CT	2.25365	82.30518	2.25365	135.63		0.31508	11.50703	0.31508	32	11.10961	440.28160	6.40293	
STEEL(CONE LEAF) SPRING DOOR	CT	2.25365	82.30518	2.25365	135.63		0.31508	11.50703	0.31508	32	11.10961	440.28160	6.40293	
WOOD(CONE LEAF) SPRING DOOR	CT	2.25365	82.30518	2.25365	135.63		0.31508	11.50703	0.31508	32	11.10961	440.28160	6.40293	
EXTERIOR WINDOWS	CT	0.17042	1.22751	0.17042	5.26		0.02383	0.17162	0.02383	75	3.30634	154.76000	3.30634	
OPERABLE WINDOWS	CT	0.27883	1.22751	0.27883	7.82		0.03898	0.17162	0.03898	75	4.21782	154.76000	4.21782	
ALUMINUM OPER. Second Flr.	CT	1.27311	1.27311	1.27311	46.80		0.25929	0.21590	0.25929	80	3.30634	154.76000	3.30634	
ALUMINUM OPER. Third Flr.	CT	1.27311	1.27311	1.27311	46.80		0.25929	0.21590	0.25929	80	3.30634	154.76000	3.30634	
STEEL FRAME-OPER(PHID) 1FL	CT	0.50501	1.54426	0.50501	13.49		0.07061	0.21590	0.07061	80	3.30634	275.80999	3.59195	
STEEL FRAME-OPER(PHID) 2FL	CT	3.35720	1.54426	3.35720	56.22		0.32309	0.21590	0.32309	80	3.30634	275.80999	3.59195	
STEEL FRAME-OPER(PHID) 3FL	CT	3.35720	1.54426	3.35720	56.22		0.32309	0.21590	0.32309	80	3.30634	275.80999	3.59195	
WOOD FRAME-OPER(PHID) 1 FL	CT	0.61048	1.46670	0.61048	80.98		0.08535	0.20506	0.08535	50	3.63199	94.51999	3.63199	
WOOD FRAME-OPER(PHID) 2 FL	CT	2.30108	1.40299	2.30108	55.85		0.32171	0.19615	0.32171	50	3.99245	94.51999	3.99245	
WOOD FRAME-OPER(PHID) 3 FL	CT	3.34738	1.40299	3.34738	80.60		0.46800	0.19615	0.46800	50	7.74658	94.51999	7.74658	
PLASTIC (WOOD CORE)FRM 1FL	CT	0.11965	1.34981	0.11965	4.18		0.01673	0.18872	0.01673	75	3.30634	137.80000	3.30634	
PLASTIC (WOOD CORE)FRM 2FL	CT	0.23206	1.34981	0.23206	6.84		0.03244	0.18872	0.03244	75	4.21782	137.80000	4.21782	
PLASTIC (WOOD CORE)FRM 3FL	CT	0.29519	1.34981	0.29519	8.33		0.04127	0.18872	0.04127	75	5.12929	137.80000	5.12929	
GLASS BLOCK-OPER First Flr.	CT	0.34345	2.90650	0.34345	11.51		0.05081	0.40636	0.05081	100	3.02718	281.67592	3.02718	
GLASS BLOCK-OPER Second Flr.	CT	1.35913	2.90650	1.35913	35.06		0.19002	0.40636	0.19002	100	3.02718	281.67592	3.02718	
GLASS BLOCK-OPER Third Flr.	CT	1.97459	2.90650	1.97459	48.46		0.27073	0.40636	0.27073	100	3.02718	281.67592	3.02718	
ALUMINUM DOUBLE-OPER 1 FL	CT	0.31269	2.30792	0.31269	9.71		0.04372	0.32267	0.04372	75	3.30634	213.06000	3.30634	
ALUMINUM DOUBLE-OPER 2 FL	CT	0.42109	2.30792	0.42109	12.27		0.05867	0.32267	0.05867	75	4.21782	213.06000	4.21782	
ALUMINUM DOUBLE-OPER 3 FL	CT	0.48021	2.30792	0.48021	13.67		0.06714	0.32267	0.06714	75	5.12929	213.06000	5.12929	
STEEL FRAME(DBL)-OPER 1 FL	CT	0.66647	2.90605	0.66647	18.67		0.09318	0.40629	0.09318	80	3.60833	394.73997	3.60833	
STEEL FRAME(DBL)-OPER 2 FL	CT	2.47235	2.90605	2.47235	61.40		0.34566	0.40629	0.34566	80	5.96879	394.73997	5.96879	
STEEL FRAME(DBL)-OPER 3 FL	CT	3.51865	2.90605	3.51865	86.16		0.49194	0.40629	0.49194	80	7.72292	394.73997	7.72292	
WOOD FRAME(DBL)-OPER 1 FL	CT	0.97734	2.83136	0.97734	25.96		0.13644	0.39585	0.13644	50	3.96973	123.45184	3.96973	
WOOD FRAME(DBL)-OPER 2 FL	CT	2.78322	2.83136	2.78322	68.68		0.38912	0.39585	0.38912	50	6.33019	123.45184	6.33019	
WOOD FRAME(DBL)-OPER 3 FL	CT	3.82952	2.83136	3.82952	93.44		0.53540	0.39585	0.53540	50	8.04332	123.45184	8.04332	
PLASTIC (WOOD)FRM-OPER 1FL	CT	0.20612	2.44778	0.20612	7.32		0.02482	0.34222	0.02482	70	3.30634	187.62000	3.30634	
PLASTIC (WOOD)FRM-OPER 2FL	CT	0.31853	2.44778	0.31853	9.96		0.04453	0.34222	0.04453	70	4.21782	187.62000	4.21782	
PLASTIC (WOOD)FRM-OPER 3FL	CT	0.38166	2.44778	0.38166	11.48		0.05336	0.34222	0.05336	70	5.12929	187.62000	5.12929	
IMPERABLE WINDOWS	CT	0.17042	1.22751	0.17042	5.24		0.02383	0.17162	0.02383	75	3.30634	154.76000	3.30634	
ALUMINUM-FIXED First Flr.	CT	0.27883	1.22751	0.27883	7.81		0.03898	0.17162	0.03898	75	4.21782	154.76000	4.21782	
ALUMINUM-FIXED Second Flr.	CT	1.20889	1.20889	1.20889	9.20		0.16901	0.16901	0.16901	75	5.12929	122.96000	5.12929	
ALUMINUM-FIXED Third Flr.	CT	0.50501	1.20889	0.50501	13.41		0.07061	0.20393	0.07061	80	3.59195	122.96000	3.59195	
STEEL FRAME(PHID)-FMD 1 FL	CT	0.50501	1.20889	0.50501	13.41		0.07061	0.20393	0.07061	80	3.59195	122.96000	3.59195	

See NOTES on the last page of this table for Explanation of Column Headings

COMPONENT DESCRIPTION	UNIT	PRESENT NORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (C=10%)				ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS									
		By Resources				Annual Maintenance and Repair					Replacement and High Costs Tasks				
		labor	material	equipment	D.C. Total	labor	material	equipment	yr	labor	material	equipment	labor	material	equipment
STEEL FRAME (PMTD)-FND 2 FL	CT	2.31090	1.45861	2.31090	56.13	0.32309	0.20393	0.32309	80	5.95241	129.52999	5.95241	5.95241	129.52999	5.95241
STEEL FRAME (PMTD)-FND 3 FL	CT	3.35720	1.45861	3.35720	80.99	0.46937	0.22482	0.46937	80	7.70654	129.52999	7.70654	7.70654	129.52999	7.70654
WOOD FRAME (PMTD)-FND 1 FL	CT	1.09007	1.09007	1.09007	27.11	0.15240	0.22482	0.15240	50	4.13977	239.25998	4.13977	4.13977	239.25998	4.13977
WOOD FRAME (PMTD)-FND 2 FL	CT	2.69675	1.62238	2.69675	65.43	0.37703	0.22482	0.37703	50	8.33019	239.25998	8.33019	8.33019	239.25998	8.33019
WOOD FRAME (PMTD)-FND 3 FL	CT	4.78913	1.72857	4.78913	115.04	0.64956	0.22482	0.64956	50	9.08432	239.25998	9.08432	9.08432	239.25998	9.08432
PLASTIC (WOOD) FND 1 FL	CT	0.11835	1.15429	0.11835	4.29	0.01673	0.20332	0.01673	70	3.30634	238.50000	3.30634	3.30634	238.50000	3.30634
PLASTIC (WOOD) FND 2 FL	CT	0.23206	1.45429	0.23206	6.94	0.03244	0.20332	0.03244	70	3.30634	238.50000	3.30634	3.30634	238.50000	3.30634
PLASTIC (WOOD) FND 3 FL	CT	0.29519	1.45429	0.29519	8.44	0.04127	0.20332	0.04127	70	3.30634	238.50000	3.30634	3.30634	238.50000	3.30634
GLASS BLOCK FIXED 1st FL	CT	0.36345	2.90550	0.36345	11.51	0.05081	0.40636	0.05081	100	3.02718	150.23592	3.02718	3.02718	150.23592	3.02718
GLASS BLOCK FIXED 2nd FL	CT	1.36308	2.90550	1.36308	35.10	0.19068	0.40636	0.19068	100	4.47642	150.23592	4.47642	4.47642	150.23592	4.47642
GLASS BLOCK-FIXED 3rd FL	CT	1.93934	2.90650	1.93934	48.79	0.27114	0.40636	0.27114	100	5.34482	150.23592	5.34482	5.34482	150.23592	5.34482
ALUMINUM DCL-FND 1st FL	CT	0.12169	2.27999	0.12169	9.68	0.04372	0.31876	0.04372	75	3.30634	165.36000	3.30634	3.30634	165.36000	3.30634
ALUMINUM DCL-FND 2nd FL	CT	0.42109	2.27999	0.42109	12.24	0.05887	0.31876	0.05887	75	4.21782	165.36000	4.21782	4.21782	165.36000	4.21782
ALUMINUM DCL-FND 3rd FL	CT	0.48021	2.27999	0.48021	13.64	0.06714	0.31876	0.06714	75	5.12929	165.36000	5.12929	5.12929	165.36000	5.12929
STEEL FRAME (DRL)-FND 1 FL	CT	2.77236	2.77236	2.77236	61.27	0.34566	0.38760	0.34566	80	9.6879	175.31532	9.6879	9.6879	175.31532	9.6879
STEEL FRAME (DRL)-FND 2 FL	CT	2.77236	2.77236	2.77236	61.27	0.34566	0.38760	0.34566	80	9.6879	175.31532	9.6879	9.6879	175.31532	9.6879
STEEL FRAME (DRL)-FND 3 FL	CT	3.51865	3.51865	3.51865	84.02	0.46194	0.45965	0.46194	80	12.7292	175.31532	12.7292	12.7292	175.31532	12.7292
WOOD FRAME (DRL)-FND 1st FL	CT	1.21218	3.28771	1.21218	37.97	0.16947	0.45965	0.16947	50	3.30119	323.89996	3.30119	3.30119	323.89996	3.30119
WOOD FRAME (DRL)-FND 2nd FL	CT	3.53100	3.53100	3.53100	86.83	0.49367	0.45965	0.49367	50	8.08432	323.89996	8.08432	8.08432	323.89996	8.08432
WOOD FRAME (DRL)-FND 3rd FL	CT	4.87360	3.28771	4.87360	118.64	0.68165	0.45965	0.68165	50	10.2882	323.89996	10.2882	10.2882	323.89996	10.2882
PLASTIC (WOOD) DRL-FND 1 FL	CT	0.26050	2.60505	0.26050	7.48	0.02882	0.36421	0.02882	70	3.30634	339.20000	3.30634	3.30634	339.20000	3.30634
PLASTIC (WOOD) DRL-FND 2 FL	CT	0.31667	2.60505	0.31667	10.10	0.04427	0.36421	0.04427	70	4.21782	339.20000	4.21782	4.21782	339.20000	4.21782
PLASTIC (WOOD) DRL-FND 3 FL	CT	0.38166	2.60505	0.38166	11.64	0.05336	0.36421	0.05336	70	5.12929	339.20000	5.12929	5.12929	339.20000	5.12929
WOOD LOUVER First Floor	CT	1.47696	24.01999	1.47696	58.96	0.20649	3.35822	0.20649	75	5.95304	81.28080	5.95304	5.95304	81.28080	5.95304
WOOD LOUVER Second Floor	CT	3.25628	24.65039	3.25628	101.22	0.52146	3.44635	0.52146	75	10.16402	81.28080	10.16402	10.16402	81.28080	10.16402
WOOD LOUVER Third Floor	CT	3.56578	24.01999	3.56578	108.86	0.50133	3.35822	0.50133	75	10.16402	81.28080	10.16402	10.16402	81.28080	10.16402
ALUM. LOUVER First Floor	CT	1.35992	33.48026	1.35992	65.66	0.19013	4.68085	0.19013	80	8.05853	317.66080	8.05853	8.05853	317.66080	8.05853
ALUM. LOUVER Second Floor	CT	2.59121	33.48026	2.59121	90.06	0.34331	4.68085	0.34331	80	10.16402	317.66080	10.16402	10.16402	317.66080	10.16402
ALUM. LOUVER Third Floor	CT	3.41706	33.48026	3.41706	114.33	0.47774	4.68085	0.47774	80	10.16402	317.66080	10.16402	10.16402	317.66080	10.16402
STEEL LOUVER First Floor	CT	1.32808	12.23925	1.32808	43.66	0.15568	1.71116	0.15568	150	5.95304	198.94080	5.95304	5.95304	198.94080	5.95304
STEEL LOUVER Second Floor	CT	2.35102	12.23925	2.35102	67.86	0.25659	1.71116	0.25659	150	8.05853	198.94080	8.05853	8.05853	198.94080	8.05853
STEEL LOUVER Third Floor	CT	3.37113	12.23925	3.37113	92.00	0.47132	1.71116	0.47132	150	10.16402	198.94080	10.16402	10.16402	198.94080	10.16402
WOOD SHUTTER First Floor	CT	1.47696	24.01999	1.47696	58.96	0.20649	3.35822	0.20649	75	5.95304	81.28080	5.95304	5.95304	81.28080	5.95304
WOOD SHUTTER Second Floor	CT	3.56578	24.01999	3.56578	108.86	0.50133	3.35822	0.50133	75	10.16402	81.28080	10.16402	10.16402	81.28080	10.16402
WOOD SHUTTER Third Floor	CT	1.37784	24.01999	1.37784	64.09	0.19264	3.35822	0.19264	75	5.92404	81.28080	5.92404	5.92404	81.28080	5.92404
ALUM. SHUTTER First Floor	CT	2.41382	41.99486	2.41382	74.59	0.33748	5.87127	0.33748	80	4.17188	317.66080	4.17188	4.17188	317.66080	4.17188
ALUM. SHUTTER Second Floor	CT	4.19948	41.99486	4.19948	99.11	0.48135	5.87127	0.48135	80	5.92404	317.66080	5.92404	5.92404	317.66080	5.92404
ALUM. SHUTTER Third Floor	CT	3.44289	41.99486	3.44289	123.45	0.48135	5.87127	0.48135	80	5.92404	317.66080	5.92404	5.92404	317.66080	5.92404
STEEL SHUTTER First Floor	CT	1.35992	21.68780	1.35992	53.86	0.19013	3.03216	0.19013	150	2.41972	198.94080	2.41972	2.41972	198.94080	2.41972
STEEL SHUTTER Second Floor	CT	2.59121	21.68780	2.59121	78.26	0.34331	3.03216	0.34331	150	4.17188	198.94080	4.17188	4.17188	198.94080	4.17188
STEEL SHUTTER Third Floor	CT	3.41706	21.68780	3.41706	102.54	0.47774	3.03216	0.47774	150	5.92404	198.94080	5.92404	5.92404	198.94080	5.92404
WOOD CON. SPECIAL EXT.	CT	1.38447	1.35362	1.38447	34.20	0.19412	0.18925	0.19412	80	2.63991	111.53998	2.63991	2.63991	111.53998	2.63991
ALUM. FRAME STORM WIND 1FL	CT	2.1847	1.35362	2.1847	63.31	0.36609	0.18925	0.36609	80	4.41409	111.53998	4.41409	4.41409	111.53998	4.41409
ALUM. FRAME STORM WIND 2FL	CT	3.56578	1.35362	3.56578	90.24	0.52525	0.18925	0.52525	80	6.18827	111.53998	6.18827	6.18827	111.53998	6.18827
STEEL FRAME STORM WIND 1FL	CT	1.22370	1.32742	1.22370	30.28	0.17108	0.18559	0.17108	100	2.63991	89.27998	2.63991	2.63991	89.27998	2.63991
STEEL FRAME STORM WIND 2FL	CT	3.33378	1.32742	3.33378	56.54	0.32628	0.18559	0.32628	100	4.41409	89.27998	4.41409	4.41409	89.27998	4.41409
STEEL FRAME STORM WIND 3FL	CT	3.96644	1.32742	3.96644	81.69	0.47485	0.18559	0.47485	100	6.18827	89.27998	6.18827	6.18827	89.27998	6.18827
WOOD FRAME STORM WIND 1 FL	CT	1.57703	1.38361	1.57703	38.70	0.22048	0.19344	0.22048	50	2.63991	93.89098	2.63991	2.63991	93.89098	2.63991
WOOD FRAME STORM WIND 2 FL	CT	2.94427	1.38361	2.94427	71.05	0.41164	0.19344	0.41164	50	4.41409	93.89098	4.41409	4.41409	93.89098	4.41409
WOOD FRAME STORM WIND 3 FL	CT	4.16941	1.38361	4.16941	100.03	0.58292	0.19344	0.58292	50	6.18827	93.89098	6.18827	6.18827	93.89098	6.18827
METAL WINDOW GRATING 1st FL	CT	1.91437	5.79887	1.91437	51.09	0.26765	0.81074	0.26765	150	23.23632	116.12300	23.23632	23.23632	116.12300	23.23632
METAL WINDOW GRATING 2nd FL	CT	2.99312	5.79887	2.99312	76.62	0.41847	0.81074	0.41847	150	30.90396	116.12300	30.90396	30.90396	116.12300	30.90396
METAL WINDOW GRATING 3rd FL	CT	4.07062	5.79887	4.07062	102.11	0.56911	0.81074	0.56911	150	4.10490	95.59080	4.10490	4.10490	95.59080	4.10490
METAL WIRE MESH COVER 1 FL	CT	2.06261	4.18033	2.06261	52.89	0.28837	0.58571	0.28837	150	7.94625	95.59080	7.94625	7.94625	95.59080	7.94625
METAL WIRE MESH COVER 2 FL	CT	3.15618	4.18033	3.15618	78.86	0.44126	0.58571	0.44126	150	10.02557	95.59080	10.02557	10.02557	95.59080	10.02557
METAL WIRE MESH COVER 3 FL	CT	4.24851	4.18033	4.24851	104.71	0.59398	0.58571	0.59398	150	12.94625	95.59080	12.94625	12.94625	95.59080	12.94625

See notes on the last page of this table for explanation of column headings



COMPONENT DESCRIPTION	UN	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (C=10%)				ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS									
		By Resources				Annual Maintenance and Repair					Replacement and High Costs				
		labor	material	equipment	D.C. Total	labor	material	equipment	yr	labor	material	equipment	tasks	equipment	tasks
ALUM. FRN SCRIN WNDW CVR 1FL	CT	1.06683	0.39140	1.06683	25.63	0.14915	0.05472	0.14915	70	3.08433	42.39618	3.08433	3.08433	3.08433	3.08433
ALUM. FRN SCRIN WNDW CVR 2FL	CT	2.05979	0.39140	2.05979	49.13	0.28798	0.05472	0.28798	70	4.90295	42.39618	4.90295	4.90295	4.90295	4.90295
ALUM. FRN SCRIN WNDW CVR 3FL	CT	3.05198	0.39140	3.05198	72.60	0.42670	0.05472	0.42670	70	7.72157	42.39618	7.72157	7.72157	7.72157	7.72157
STEEL FRN SCRIN WNDW CVR 1F	CT	1.06683	0.39140	1.06683	25.63	0.14915	0.05472	0.14915	80	3.08433	39.39638	3.08433	3.08433	3.08433	3.08433
STEEL FRN SCRIN WNDW CVR 2F	CT	2.05979	0.39140	2.05979	49.13	0.28798	0.05472	0.28798	80	4.90295	39.39638	4.90295	4.90295	4.90295	4.90295
STEEL FRN SCRIN WNDW CVR 3F	CT	3.05198	0.39140	3.05198	72.60	0.42670	0.05472	0.42670	80	7.72157	39.39638	7.72157	7.72157	7.72157	7.72157
WOOD FRN SCRIN WNDW CVR 1FL	CT	1.06683	0.39140	1.06683	25.63	0.14915	0.05472	0.14915	40	3.08433	40.02178	3.08433	3.08433	3.08433	3.08433
WOOD FRN SCRIN WNDW CVR 2FL	CT	2.05979	0.39140	2.05979	49.13	0.28798	0.05472	0.28798	40	4.90295	40.02178	4.90295	4.90295	4.90295	4.90295
WOOD FRN SCRIN WNDW CVR 3FL	CT	3.05198	0.39140	3.05198	72.60	0.42670	0.05472	0.42670	40	7.72157	40.02178	7.72157	7.72157	7.72157	7.72157
LEAD-LINED WNDW(U/FR) 1FL	CT	1.23370	1.32742	1.23370	30.28	0.17108	0.18559	0.17108	100	2.63091	248.28316	2.63091	2.63091	2.63091	2.63091
LEAD-LINED WNDW(U/FR) 2FL	CT	2.33378	1.32742	2.33378	56.56	0.32628	0.18559	0.32628	100	4.41409	248.28316	4.41409	4.41409	4.41409	4.41409
LEAD-LINED WNDW(U/FR) 3FL	CT	3.39644	1.32742	3.39644	81.69	0.47485	0.18559	0.47485	100	6.18627	248.28316	6.18627	6.18627	6.18627	6.18627
EXTERIOR PORCHES															
DECK															
CONCRETE	SF	0.02044	0.06408	0.02044	0.55	0.00286	0.00896	0.00286	300	1.24579	17.78480	0.00286	0.00286	0.00286	0.00286
WOOD	SF	0.01876	0.13008	0.01876	0.57	0.00262	0.01830	0.00262	200	0.06968	2.84080	0.00262	0.00262	0.00262	0.00262
METAL DECKING-PORCH	SF	0.01987	0.04795	0.01987	0.52	0.00278	0.00670	0.00278	65	0.32421	0.96460	0.00278	0.00278	0.00278	0.00278
RAILINGS															
WROUGHT IRON	LF	0.04186	0.09846	0.04186	1.09	0.00585	0.01377	0.00585	200	4.32328	53.08480	0.00585	0.00585	0.00585	0.00585
WOOD	LF	0.02649	0.09531	0.02649	0.72	0.00370	0.01333	0.00370	100	0.37154	4.93536	0.00370	0.00370	0.00370	0.00370
STEEL RAILING PAINTED	LF	0.04186	0.09587	0.04186	1.09	0.00585	0.01340	0.00585	200	2.18088	27.11480	0.00585	0.00585	0.00585	0.00585
STEEL RAILING UNPAINTED	LF	0.04186	0.09587	0.04186	1.09	0.00585	0.01340	0.00585	200	2.18088	27.11480	0.00585	0.00585	0.00585	0.00585
DECK SUPPORT MEMBERS	LF	0.01414	0.03476	0.01414	0.37	0.00198	0.00486	0.00198	200	2.14240	27.03000	0.00198	0.00198	0.00198	0.00198
CONCRETE	SF	0.01846	0.06288	0.01846	0.50	0.00258	0.00879	0.00258	500	3.60971	17.78480	0.00258	0.00258	0.00258	0.00258
WOOD	SF	0.00482	0.31840	0.00482	0.48	0.00095	0.04452	0.00095	100	0.19279	4.74880	0.00095	0.00095	0.00095	0.00095
CLAY BRICK	SF	0.01797	0.06836	0.01797	0.49	0.00251	0.00928	0.00251	500	1.12554	2.52140	0.00251	0.00251	0.00251	0.00251
STEEL EXT. PORCH SUPPORT	SF	0.00747	0.06882	0.00747	0.24	0.00104	0.00954	0.00104	200	0.19279	27.51760	0.00104	0.00104	0.00104	0.00104
COLUMNS															
METAL	LF	0.04231	0.40306	0.04231	1.40	0.00592	0.05455	0.00592	200	0.22945	18.06240	0.00592	0.00592	0.00592	0.00592
WOOD	LF	0.02108	0.23724	0.02108	0.74	0.00295	0.03317	0.00295	200	0.23842	1.20840	0.00295	0.00295	0.00295	0.00295
CLAY BRICK	LF	0.02707	0.26814	0.02707	0.91	0.00378	0.03749	0.00378	500	1.13152	9.20080	0.00378	0.00378	0.00378	0.00378
EXTERIOR ORNAMENT															
CORNICES	LF	0.00773	0.00017	0.00773	0.18	0.00108	0.00002	0.00108	300	0.26507	95.40000	0.00108	0.00108	0.00108	0.00108
STONE	LF	0.04388	0.06408	0.04388	1.10	0.00615	0.00924	0.00615	200	0.28496	3.52980	0.00615	0.00615	0.00615	0.00615
EXTERIOR STAIRS															
RAILINGS															
WOOD	LF	0.01293	0.11334	0.01293	0.42	0.00181	0.01585	0.00181	100	0.16835	3.87536	0.00181	0.00181	0.00181	0.00181
METAL	LF	0.02105	0.08766	0.02105	0.59	0.00294	0.01226	0.00294	300	0.78195	26.61236	0.00294	0.00294	0.00294	0.00294
WROUGHT IRON EXT. ST. RAIL.	LF	0.04186	0.09365	0.04186	1.09	0.00585	0.01375	0.00585	200	2.18088	27.11480	0.00585	0.00585	0.00585	0.00585
STEEL UNPAINT. EXT. STAIR	LF	0.01017	0.00652	0.01017	0.25	0.00142	0.00091	0.00142	300	2.14240	27.03000	0.00142	0.00142	0.00142	0.00142
STEPS															
CONCRETE	SF	0.00767	0.00776	0.00767	0.19	0.00107	0.00108	0.00107	300	2.93405	16.87520	0.00107	0.00107	0.00107	0.00107
WOOD	SF	0.01490	0.07770	0.01490	0.43	0.00208	0.01086	0.00208	100	0.46410	3.68456	0.00208	0.00208	0.00208	0.00208
METAL	SF	0.01244	0.17262	0.01244	0.47	0.00174	0.02413	0.00174	300	2.16216	35.06480	0.00174	0.00174	0.00174	0.00174
MASONRY STEPS (UNPAINTED)	SF	0.00374	0.00524	0.00374	0.09	0.00052	0.00073	0.00052	400	1.19119	2.23660	0.00052	0.00052	0.00052	0.00052
MASONRY STEPS (PAINTED)	SF	0.02338	0.06375	0.02338	0.62	0.00327	0.00891	0.00327	400	1.61909	2.30020	0.00327	0.00327	0.00327	0.00327
QUARRY TILE STEPS	SF	0.00603	0.00940	0.00603	0.15	0.00084	0.00151	0.00084	300	1.59774	2.49100	0.00084	0.00084	0.00084	0.00084
EXTERIOR MASONRY															
MINGES	CT	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	60	0.21151	19.08000	0.00000	0.00000	0.00000	0.00000
LOCK SET	CT	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	30	1.64840	124.02000	0.00000	0.00000	0.00000	0.00000
BRASS	CT	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	15	0.49413	90.10000	0.00000	0.00000	0.00000	0.00000
DOOR CLOSER	CT	0.09319	16.99286	0.09319	19.20	0.00000	0.00000	0.00000	20	0.93938	79.50000	0.00000	0.00000	0.00000	0.00000
DEADWOLT	CT	0.11000	9.30945	0.11000	11.91	0.00000	0.00000	0.00000	20	0.93938	79.50000	0.00000	0.00000	0.00000	0.00000
WEATHER STRIPING	CT	0.11000	9.30945	0.11000	11.91	0.00000	0.00000	0.00000	20	0.93938	79.50000	0.00000	0.00000	0.00000	0.00000

See NOTES on the last page of this table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)													PAGE	8				
COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (C=10%)				ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS													
	By Resources				Annual Maintenance and Repair				Replacement and High Costs Tasks									
	Washington				labor		material		equipment		yr		labor		material		equipment	
	labor	material	equipment	D.C. Total	labor	material	equipment	yr	labor	material	equipment	yr	labor	material	equipment			
BRASS	CT	0.07800	3.10315	0.07800	4.95	0.00000	0.00000	0.00000	20	0.66612	26.50000	0.66612						
EXIT BOLT	CT	0.14974	30.82480	0.14974	34.37	0.00000	0.00000	0.00000	25	2.05972	424.00000	2.05972						
METAL	See NOTES on the last page of this table for Explanation of Column Headings																	

See NOTES on the last page of this table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)										PAGE
COMPONENT DESCRIPTION	PRESENT NORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (G=10X)					ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS				
	By Resources					Annual Maintenance and Repair				
	Washington					Replacement and High Costs Tasks				
	labor	material	equipment	D.C. Total		labor	material	equipment	labor	material
ARCHITECTURE	um									
INTERIOR PARTITION										
MOVABLE PARTITION - METAL	SF	0.00350	0.00000	0.00350	0.08	0.00049	0.00000	0.00049	100	0.22022
MOVABLE PARTITION - STEEL	SF	0.00179	0.00094	0.00179	0.05	0.00025	0.00138	0.00025	100	0.22022
MOVABLE PARTITION - FABRIC										
INTERIOR DOORS										
METAL DOORS										
ST. (U) SAFETY GLASS PAINTED	CT	0.85524	23.15875	0.85524	43.39	0.11957	3.23781	0.11957	60	3.14685
ST. (U) SAFETY GLASS PAINTED	CT	1.04957	25.12440	1.04957	50.43	0.14954	3.51262	0.14954	80	3.14685
ST. SLIDING PMTD. INT. DOOR	CT	0.84822	43.54812	0.84822	65.98	0.13257	6.08843	0.13257	80	3.14685
ST. (INSUL. CORE) PMTD. INT.	CT	1.04957	26.37772	1.04957	49.48	0.14954	3.51262	0.14954	80	3.14685
STEEL UNPAINTED INT. DOOR	CT	0.22161	18.69575	0.22161	23.94	0.03098	2.61384	0.03098	80	2.73004
ST. (SAFETY GLASS) PMTD. INT.	CT	0.35593	20.66140	0.35593	30.98	0.04095	2.88666	0.04095	80	2.73004
ST. SLIDING UNPMTD. INT. DOOR	CT	0.31458	40.54778	0.31458	47.99	0.04398	2.56896	0.04398	80	2.73004
ST. (INSUL. CORE) UNPMTD. INT.	CT	0.35593	19.91471	0.35593	30.23	0.06095	2.78426	0.06095	80	2.73004
AL. (PLAIN & ANODIZED) INT.	CT	0.35361	29.83211	0.35361	38.20	0.04944	4.17081	0.04944	65	2.73004
AL. (PEL) (SAFETY GLASS) FR.	CT	0.56793	31.79776	0.56793	45.24	0.07940	4.44562	0.07940	65	2.73004
AL. SLIDING INTERIOR DOOR	CT	0.71630	65.97219	0.71630	82.92	0.10014	9.22353	0.10014	65	2.73004
AL. (WOOD CORE) INT. DOOR	CT	0.56793	31.05107	0.56793	44.49	0.07940	4.34123	0.07940	65	2.73004
AL. (INSUL. JFLA) INT. DOOR	CT	0.55793	31.05107	0.55793	44.49	0.07940	4.34123	0.07940	65	2.73004
FULLY GLAZED DOORS										
FULLY GLAZED AL. FR. DOOR	CT	0.56793	44.48006	0.56793	57.92	0.07940	6.21873	0.07940	65	2.73004
FULLY GLAZED AL. FR. SLID.	CT	0.71630	75.80152	0.71630	92.84	0.10014	10.61034	0.10014	65	2.73004
FULLY GLAZED WOODEN FR. DR.	CT	0.91834	55.93125	0.91834	77.64	0.12838	7.82016	0.12838	50	2.89680
GLAZED WOOD FR. SLIDING INT	CT	1.10684	92.11735	1.10684	118.31	0.15475	12.87889	0.15475	50	5.79892
WOOD DOORS										
MOLLOW CORE INT. PMTD. DOOR	CT	2.19657	69.19084	2.19657	121.16	0.30710	9.67352	0.30710	30	3.67727
MOLLOW CORE SLIDING INT.	CT	1.45054	72.52906	1.45054	106.85	0.20280	10.14024	0.20280	30	6.05336
SOLID CORE INT. PMTD. DOOR	CT	1.82769	38.07050	1.82769	81.31	0.25553	5.32258	0.25553	40	3.67727
SOLID CORE SLIDING INT. DR	CT	1.06427	67.87620	1.06427	93.06	0.14879	9.48972	0.14879	40	6.05336
SOLID CORE (SAF GLASS) PMTD	CT	1.09062	40.03595	1.09062	65.84	0.15248	5.59740	0.15248	40	5.95573
BIFOLD DOORS										
PANELED	CT	0.46797	16.97026	0.46797	28.04	0.06259	2.31806	0.06259	24	4.87323
REPLACE PANELED (PAINTED) INTERIOR DOORS	CT	1.02301	12.79408	1.02301	37.00	0.13877	1.71522	0.13877	24	4.61948
LOUVERED	CT	1.45013	44.28395	1.45013	78.57	0.20274	6.18851	0.20274	65	6.04897
REPLACE LOUVERED (PAINTED) INTERIOR DOORS	CT	1.14533	29.40621	1.14533	56.50	0.16013	4.11126	0.16013	40	6.04897
STEEL LOUVERED INT. DOOR	CT	2.89645	124.68718	2.89645	193.22	0.40495	17.43364	0.40495	300	31.30080
WOOD LOUVERED INT. DOOR	CT	0.22161	18.69575	0.22161	23.94	0.03098	2.61384	0.03098	80	2.73004
STEEL VALU. DOOR	CT	0.22161	18.69575	0.22161	23.94	0.03098	2.61384	0.03098	80	2.73004
METAL WALK-IN COOLER DOOR	CT	0.50825	42.87859	0.50825	54.41	0.07106	5.99483	0.07106	80	7.33475
LEAD-LINED (WOOD) MEDICAL	CT	1.37266	5.96758	1.37266	38.44	0.19191	0.83432	0.19191	150	7.33475
METAL WIRE MESH PMTD. INT	CT	0.02892	0.01691	0.02892	0.70	0.00404	0.00236	0.00404	150	6.45389
METAL WIRE MESH PMTD. INT	CT	0.02892	0.01691	0.02892	0.70	0.00404	0.00236	0.00404	150	6.45389
GARAGE & ROLL-UP DOORS										
STEEL SINGLE ROLL-UP DOOR	CT	3.49016	147.52993	3.49016	230.11	0.48796	20.62606	0.48796	35	4.84587
STEEL DOUBLE ROLL-UP DOOR	CT	6.70837	219.05211	6.70837	379.90	0.95048	30.62561	0.95048	35	5.30802
AL. SINGLE ROLL-UP DOOR	CT	5.37005	137.62995	5.37005	217.37	0.46557	19.19642	0.46557	24	4.84587
REPLACE ALUMINUM SINGLE ROLL-UP DOOR	CT	6.54815	163.47903	6.54815	318.41	0.90383	22.76104	0.90383	24	4.84587
REPLACE ALUMINUM DOUBLE ROLL-UP DOOR INTER	CT	3.26037	164.60570	3.26037	241.75	0.44383	22.91581	0.44383	16	4.84587
WOOD SINGLE ROLL-UP DOOR	CT	5.18115	232.89302	5.18115	355.48	0.69937	32.35728	0.69937	16	4.34542
WOOD DOUBLE ROLL-UP DOOR	CT									
REPLACE WOOD SINGLE ROLL-UP DOOR	CT									
REPLACE WOOD DOUBLE ROLL-UP DOOR	CT									
FIREPLACE CHIMNEY										

See NOTES on the last page of this table for Explanation of Column Headings

COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (G=10%)									
	By Resources					Washington				
	D.C. Total					D.C. Total				
	unit	labor	material	equipment		labor	material	equipment	yr	
CLAY BRICK	SF	0.00208	0.00174	0.00208	0.05	0.00029	0.00024	0.00029	500	1.34004
CONCRETE BRICK	SF	0.00208	0.00216	0.00208	0.05	0.00029	0.00030	0.00029	500	1.34004
STONE	SF	0.00053	0.00262	0.00053	0.02	0.00007	0.00037	0.00007	500	0.34931
METAL PIPE CHIMNEY	SF	0.00152	0.00730	0.00152	0.12	0.00021	0.01220	0.00021	200	1.82390
METAL	LF	0.01365	0.06390	0.01365	0.39	0.00191	0.00892	0.00191	200	0.58058
CONCRETE	LF	0.00693	0.00482	0.00693	0.17	0.00067	0.00067	0.00067	300	0.18616
STONE	LF	0.00043	0.00043	0.00043	0.01	0.00006	0.00059	0.00006	300	0.18616
FINISH	SF	0.00998	0.05053	0.00998	0.29	0.00140	0.00706	0.00140	300	1.08828
BRICK	SF	0.00998	0.21842	0.00998	0.45	0.00140	0.03054	0.00140	300	1.08828
CONCRETE BLOCK	SF	0.00789	0.05690	0.00789	0.24	0.00110	0.00796	0.00110	100	0.23680
PLASTER	SF	0.00787	0.04881	0.00787	0.24	0.00110	0.00682	0.00110	100	0.29517
WOOD	SF	0.00251	0.00233	0.00251	0.06	0.00035	0.00033	0.00035	300	1.07679
FIRE BRICK	SF	0.00251	0.00233	0.00251	0.06	0.00035	0.00033	0.00035	300	1.07679
FLUES ARCHITECTURAL	LF	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	400	1.34004
BASED CLAY FLUE, ARCH.	LF	0.00152	0.00418	0.00152	0.10	0.00021	0.00897	0.00021	200	1.82390
METAL PIPE FLUE, ARCH.	LF	0.00152	0.00418	0.00152	0.10	0.00021	0.00897	0.00021	200	1.82390
INTERIOR ORNAMENT	LF	0.00694	0.04951	0.00694	0.21	0.00097	0.00692	0.00097	100	0.04773
INTERIOR TRIM	LF	0.00708	0.06460	0.00708	0.25	0.00110	0.00903	0.00110	200	0.04980
METAL	LF	0.00334	0.01000	0.00334	0.09	0.00047	0.00140	0.00047	75	0.79888
TERRAZZO TRIM	LF	0.00334	0.00492	0.00334	0.08	0.00047	0.00049	0.00047	50	0.79888
CERAMIC TRIM	LF	0.00423	0.09752	0.00423	0.19	0.00003	0.00061	0.00003	18	0.02847
RUBBER / VINYL TRIM	LF	0.00423	0.09752	0.00423	0.19	0.00003	0.00061	0.00003	18	0.02847
INTERIOR STAIRS	LF	0.01293	0.11334	0.01293	0.42	0.00181	0.01585	0.00181	100	0.16835
RAILINGS	LF	0.01293	0.08766	0.01293	0.59	0.00294	0.01226	0.00294	300	1.48174
WOOD	LF	0.04186	0.09636	0.04186	1.09	0.00585	0.01375	0.00585	200	2.18088
METAL	LF	0.00767	0.00776	0.00767	0.19	0.00107	0.00108	0.00107	300	2.93405
IRON INT. STAIR RAILING	SF	0.01490	0.07770	0.01490	0.43	0.00208	0.01086	0.00208	100	0.46410
STEPS	SF	0.01244	0.17262	0.01244	0.47	0.00174	0.02413	0.00174	300	2.16216
CONCRETE	SF	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	400	1.59777
WOOD	SF	0.01532	0.04569	0.01532	0.41	0.00214	0.00639	0.00214	400	1.61909
MASONRY STEPS (UNPNTD)	SF	0.01532	0.04569	0.01532	0.41	0.00214	0.00639	0.00214	400	1.61909
MASONRY STEPS (PAINTED)	SF	0.01532	0.04569	0.01532	0.41	0.00214	0.00639	0.00214	400	1.61909
CARPETED STEPS	SF	0.03974	3.39574	0.03974	4.28	0.00102	0.01050	0.00102	8	0.05239
RUBBER INTERIOR STEPS	SF	0.05551	1.21111	0.05551	2.44	0.00123	0.00763	0.00123	18	0.38007
TERRAZZO INTERIOR STEPS	SF	0.00603	0.01699	0.00603	0.16	0.00084	0.00238	0.00084	300	1.59774
INTERIOR WARDROBE	CT	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	60	0.21151
HINGES	CT	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	30	1.64840
BRASS	CT	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	15	0.49413
LOCKSET	CT	0.09319	16.99286	0.09319	19.20	0.00000	0.00000	0.00000	20	0.93938
DOOR CLOSER	CT	0.11000	9.30945	0.11000	11.91	0.00000	0.00000	0.00000	20	0.66612
BRASS	CT	0.07800	3.10315	0.07800	4.95	0.00000	0.00000	0.00000	25	2.05972
DEADBOLT	CT	0.07800	3.10315	0.07800	4.95	0.00000	0.00000	0.00000	25	2.05972
WEATHER STRIPING	CT	0.07800	3.10315	0.07800	4.95	0.00000	0.00000	0.00000	25	2.05972
BRASS	CT	0.07800	3.10315	0.07800	4.95	0.00000	0.00000	0.00000	25	2.05972
EXIT BOLT	CT	0.14974	30.82480	0.14974	34.37	0.00000	0.00000	0.00000	25	2.05972
METAL	CT	0.14974	30.82480	0.14974	34.37	0.00000	0.00000	0.00000	25	2.05972

See NOTES on the last page of this table for Explanation of Column Headings

COMPONENT DESCRIPTION	UM	PRESENT NORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (G=10X)				ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS			
		By Resources		Washington		Annual Maintenance and Repair			
		labor	material	equipment	D.C. Total	labor	material	equipment	Yr
ARCHITECTURE									
WALL FINISHES									
GYPSUM AND PLASTER									
PLASTER	SF	0.02996	0.13543	0.02996	0.84	0.00619	0.01893	0.00419	300
SHEETROCK (STIPPLED)	SF	0.02722	0.12340	0.02722	0.77	0.00381	0.01731	0.00381	300
SHEETROCK (UNSTIPPLED)	SF	0.02722	0.12336	0.02722	0.77	0.00381	0.01731	0.00381	300
STUCCO INT. WALL FINISH	SF	0.06670	0.15336	0.06670	1.73	0.00933	0.02144	0.00933	300
MASONRY AND TILE									
CLAY BLOCK	SF	0.00046	0.03396	0.00046	0.02	0.00006	0.00195	0.00006	500
CLAY BLOCK (PAINTED)	SF	0.00046	0.03396	0.00046	0.02	0.00006	0.00195	0.00006	500
CONCRETE BLOCK	SF	0.00046	0.00116	0.00046	0.01	0.00006	0.00116	0.00006	500
CONCRETE BLOCK (PAINTED)	SF	0.00046	0.00116	0.00046	0.01	0.00006	0.00116	0.00006	500
CLAY BRICK	SF	0.00179	0.02713	0.00179	0.77	0.00025	0.00735	0.00025	500
CONCRETE BRICK	SF	0.00179	0.02713	0.00179	0.77	0.00025	0.00735	0.00025	500
FIRE BRICK	SF	0.00176	0.00214	0.00176	0.04	0.00025	0.00030	0.00025	500
TILE	SF	0.00176	0.00176	0.00176	0.04	0.00025	0.00030	0.00025	500
MASONITE INT. WALL FINISH	SF	0.01132	0.01089	0.01132	0.28	0.00157	0.00152	0.00157	100
GLAZED CNU INT WALL FINISH	SF	0.0511	0.15557	0.0511	1.44	0.00770	0.02175	0.00770	200
PAPER, PLASTIC, FABRIC	SF	0.00046	0.00782	0.00046	0.02	0.00006	0.00109	0.00006	500
FORMICA	SF	0.00131	0.03549	0.00131	0.07	0.00018	0.00499	0.00018	30
NYLON	SF	0.00131	0.00692	0.00131	0.04	0.00018	0.00125	0.00018	30
POLYESTER	SF	0.00131	0.00518	0.00131	0.04	0.00018	0.00125	0.00018	30
VINYL	SF	0.00126	0.00535	0.00126	0.04	0.00018	0.00125	0.00018	30
WALLPAPER	SF	0.00504	0.05422	0.00504	0.17	0.00023	0.00064	0.00023	20
FABRIC INT. WALL FINISH	SF	0.00504	0.00504	0.00504	0.26	0.00169	0.00169	0.00169	20
CARPETED INT. WALL FINISH	SF	0.05147	1.23685	0.05063	2.39	0.00137	0.01144	0.00137	8
WOODS									
PLYWOOD	SF	0.02329	0.10602	0.02329	0.66	0.00326	0.01482	0.00326	80
PLYWOOD (UNFINISHED)	SF	0.00126	0.00637	0.00126	0.04	0.00018	0.00096	0.00018	80
TIMBER (FINISHED)	SF	0.02558	0.10402	0.02558	0.71	0.00358	0.01482	0.00358	80
TIMBER (UNFINISHED)	SF	0.00358	0.00487	0.00358	0.09	0.00050	0.00096	0.00050	70
PANEL (SOLID)	SF	0.02171	0.09934	0.02171	0.61	0.00303	0.01389	0.00303	200
PANEL (LAMINATED)	SF	0.02171	0.09907	0.02171	0.61	0.00303	0.01385	0.00303	200
BOARD (FINISHED)	SF	0.02116	0.09902	0.02116	0.60	0.00296	0.01384	0.00296	80
BOARD (UNFINISHED)	SF	0.00023	0.00035	0.00023	0.01	0.00003	0.00005	0.00003	60
WAINSCOT	SF	0.02747	0.12146	0.02747	0.77	0.00384	0.01698	0.00384	80
METAL									
ALUMINUM	SF	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	100
STEEL INT. FINISH (UNPNTD)	SF	0.00081	0.00085	0.00081	0.03	0.00011	0.00124	0.00011	200
STEEL INT. FINISH (PNTD)	SF	0.23519	5.31727	0.23519	10.88	0.03288	0.74340	0.03288	200
WIRE MESH WALL	SF	0.19975	0.46280	0.19975	5.19	0.02793	0.04770	0.02793	200
LEAD-LINED INT WALL FINISH	SF	0.00000	0.00000	0.00000	0.00	0.00000	0.00000	0.00000	100
GLASS									
GLASS BLOCKS	SF	0.00148	0.01742	0.00148	0.06	0.00024	0.00246	0.00024	300
PLATE GLASS WALL - INT.	SF	0.00057	0.01337	0.00057	0.03	0.00008	0.00190	0.00008	200
SPECIAL									
STONE	SF	0.00046	0.00282	0.00046	0.01	0.00006	0.00037	0.00006	500
ADDITIONAL TILE WALL	SF	0.15323	0.45569	0.15323	4.08	0.00212	0.06371	0.00212	90
CORK TILE WALL	SF	0.06436	0.45524	0.06436	1.88	0.00059	0.00316	0.00059	16
ASB-ACOS FIRE RTD. TILE	SF	0.03986	0.11467	0.03986	1.03	0.00543	0.01603	0.00543	90
FIBERGLASS PANELS, RIGID	SF	0.05522	0.16758	0.05580	1.49	0.00780	0.02343	0.00780	70
CONCRETE									
UNFINISHED	SF	0.00080	0.00477	0.00080	0.21	0.00123	0.00067	0.00123	500
FLOORING/FLOOR FINISH	SF	0.03469	0.12760	0.03469	0.95	0.00485	0.01784	0.00485	500
MASONRY & TILE PRODUCTS									
CERAMIC TILE	SF	0.00007	0.00010	0.00007	0.00	0.00001	0.00001	0.00001	50
QUARRY TILE	SF	0.00007	0.00010	0.00007	0.00	0.00001	0.00001	0.00001	50

See NOTES on the last page of this table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)

PAGE 12

COMPONENT DESCRIPTION	PRESENT NORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (G=10%)										ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS									
	By Resources					Washington					Annual Maintenance and Repair					Replacement and High Costs Tasks				
						D.C. Total														
	UP	labor	material	equipment		labor	material	equipment		labor	material	equipment	yr	labor	material	equipment				
BRICK	SF	0.00331	0.01167	0.00331	0.09	0.00331	0.01167	0.00331	0.09	0.00046	0.00163	0.00046	60	0.43604	2.65731	0.21802				
MARBLE	SF	0.00016	0.00022	0.00016	0.00	0.00016	0.00022	0.00016	0.00	0.00002	0.00003	0.00002	50	0.90337	7.52600	0.45169				
WOOD PARQUETRY	SF	0.00962	0.06276	0.00962	0.29	0.00962	0.06276	0.00962	0.29	0.00135	0.00877	0.00135	40	0.19980	2.12000	0.09990				
MAPLE	SF	0.00330	0.00330	0.00330	0.26	0.00330	0.00330	0.00330	0.26	0.00116	0.00890	0.00116	40	0.03804	2.19420	0.01902				
PLYWOOD	SF	0.00122	0.00459	0.00122	0.03	0.00122	0.00459	0.00122	0.03	0.00017	0.00064	0.00017	40	0.02054	0.39220	0.01027				
METAL	SF	0.00155	0.13385	0.00155	0.17	0.00155	0.13385	0.00155	0.17	0.00022	0.01871	0.00022	30	1.93258	3.28600	0.96629				
STEEL SHEET	SF	0.00155	0.13385	0.00155	0.17	0.00155	0.13385	0.00155	0.17	0.00022	0.01871	0.00022	30	1.93258	3.28600	0.96629				
METAL CURTAIN	SF	0.00155	0.13385	0.00155	0.17	0.00155	0.13385	0.00155	0.17	0.00022	0.01871	0.00022	30	1.93258	3.28600	0.96629				
SPECIAL SURFACES	SF	0.00155	0.13385	0.00155	0.17	0.00155	0.13385	0.00155	0.17	0.00022	0.01871	0.00022	30	1.93258	3.28600	0.96629				
CARPET FLOOR TILE	SF	0.03243	1.17190	0.01633	1.89	0.03243	1.17190	0.01633	1.89	0.00003	0.00003	0.00003	8	0.05200	1.86560	0.02600				
CORR FLOOR TILE	SF	0.03243	1.17190	0.01633	1.89	0.03243	1.17190	0.01633	1.89	0.00003	0.00003	0.00003	16	0.05200	1.86560	0.02600				
SYNTHETIC SURFACE	SF	0.00444	0.36130	0.00233	0.46	0.00444	0.36130	0.00233	0.46	0.00003	0.00116	0.00003	18	0.02977	2.49100	0.01489				
LINOLEUM	SF	0.00476	0.19987	0.00247	0.31	0.00476	0.19987	0.00247	0.31	0.00002	0.00064	0.00002	18	0.03237	1.37800	0.01619				
VINYL TILE	SF	0.00476	0.19987	0.00247	0.31	0.00476	0.19987	0.00247	0.31	0.00002	0.00064	0.00002	18	0.03237	1.37800	0.01619				
RUBBER TILE	SF	0.00476	0.19987	0.00247	0.31	0.00476	0.19987	0.00247	0.31	0.00002	0.00064	0.00002	18	0.03237	1.37800	0.01619				
VINYL SHEET	SF	0.05551	0.36098	0.02858	1.59	0.05551	0.36098	0.02858	1.59	0.00023	0.00112	0.00023	18	0.38007	2.49100	0.19003				
CONCRETE	SF	0.00162	0.00095	0.00162	0.04	0.00162	0.00095	0.00162	0.04	0.00023	0.00013	0.00023	75	0.09425	0.50562	0.04713				
CONCRETE (UNFINISHED)	SF	0.00205	0.05644	0.00184	0.10	0.00205	0.05644	0.00184	0.10	0.00029	0.00789	0.00029	75	0.09841	0.50562	0.04921				
TERRAZZO	SF	0.00162	0.01000	0.00162	0.05	0.00162	0.01000	0.00162	0.05	0.00023	0.00140	0.00023	75	0.09841	0.50562	0.04921				
BITUMINOUS	SF	0.03197	0.12080	0.01558	0.83	0.03197	0.12080	0.01558	0.83	0.00017	0.00040	0.00017	15	0.16324	0.62540	0.08162				
CEILING	SF	0.02941	0.13582	0.02941	0.83	0.02941	0.13582	0.02941	0.83	0.00411	0.01899	0.00411	300	0.23335	2.35638	0.12597				
GYPSUM AND PLASTER	SF	0.02722	0.12396	0.02722	0.77	0.02722	0.12396	0.02722	0.77	0.00381	0.01733	0.00381	300	0.03549	0.48972	0.02704				
SHEETROCK (STIPPLED)	SF	0.02722	0.12396	0.02722	0.77	0.02722	0.12396	0.02722	0.77	0.00381	0.01733	0.00381	300	0.03549	0.48972	0.02704				
SHEETROCK (UNSTIPPLED)	SF	0.02722	0.12396	0.02722	0.77	0.02722	0.12396	0.02722	0.77	0.00381	0.01733	0.00381	300	0.03549	0.48972	0.02704				
STUCCO INT. CEILING FINISH	SF	0.06670	0.15336	0.06670	1.73	0.06670	0.15336	0.06670	1.73	0.00933	0.02144	0.00933	300	0.27846	0.95400	0.15750				
MASONRY AND TILE	SF	0.00433	0.01130	0.00433	0.11	0.00433	0.01130	0.00433	0.11	0.00061	0.00158	0.00061	70	0.02340	1.12095	0.01170				
ACUSTIC TILE	SF	0.00119	0.00469	0.00119	0.03	0.00119	0.00469	0.00119	0.03	0.00017	0.00094	0.00017	70	0.00754	1.2040	0.03177				
ACUSTIC TILE (CHOPPED)	SF	0.00059	0.00010	0.00059	0.00	0.00059	0.00010	0.00059	0.00	0.00008	0.00001	0.00008	100	3.90988	1.72780	1.95494				
CERAMIC (PAV)	SF	0.00059	0.00010	0.00059	0.00	0.00059	0.00010	0.00059	0.00	0.00008	0.00001	0.00008	100	3.90988	1.72780	1.95494				
CERAMIC (TILE)	SF	0.00059	0.00010	0.00059	0.00	0.00059	0.00010	0.00059	0.00	0.00008	0.00001	0.00008	100	3.90988	1.72780	1.95494				
PAPER, PLASTIC, FABRIC	SF	0.00504	0.05422	0.00504	0.17	0.00504	0.05422	0.00504	0.17	0.00023	0.00064	0.00023	20	0.02925	0.42400	0.02925				
PAPER	SF	0.00126	0.00535	0.00126	0.04	0.00126	0.00535	0.00126	0.04	0.00018	0.00075	0.00018	30	0.02925	0.42400	0.02925				
PLASTIC	SF	0.00126	0.00535	0.00126	0.04	0.00126	0.00535	0.00126	0.04	0.00018	0.00075	0.00018	30	0.02925	0.42400	0.02925				
FABRIC	SF	0.00126	0.00535	0.00126	0.04	0.00126	0.00535	0.00126	0.04	0.00018	0.00075	0.00018	30	0.02925	0.42400	0.02925				
FORMICA CEILING FINISH	SF	0.00126	0.03569	0.00126	0.07	0.00126	0.03569	0.00126	0.07	0.00018	0.00075	0.00018	30	0.02925	0.42400	0.02925				
WOODS	SF	0.02193	0.02375	0.02193	0.54	0.02193	0.02375	0.02193	0.54	0.00307	0.00332	0.00307	80	0.31889	0.94976	0.16874				
WOOD (FINISHED)	SF	0.00356	0.00687	0.00356	0.09	0.00356	0.00687	0.00356	0.09	0.00050	0.00096	0.00050	60	0.30030	0.81620	0.30030				
WOOD (UNFINISHED)	SF	0.00400	0.06117	0.00400	1.52	0.00400	0.06117	0.00400	1.52	0.00565	0.07846	0.00565	100	0.06565	3.08460	0.03536				
METALS	SF	0.00081	0.00085	0.00081	0.03	0.00081	0.00085	0.00081	0.03	0.00011	0.00124	0.00011	200	0.57473	5.53320	0.28737				
METAL INT. FINISH (UNPRD)	SF	0.00052	0.01578	0.00052	0.03	0.00052	0.01578	0.00052	0.03	0.00007	0.00221	0.00007	60	0.09906	10.85440	0.04953				
GLASS	SF	0.00259	0.19920	0.00259	0.26	0.00259	0.19920	0.00259	0.26	0.00036	0.00336	0.00036	60	0.02015	10.85440	0.01008				
PLATE GLASS (MOUNTED)	SF	0.00259	0.19920	0.00259	0.26	0.00259	0.19920	0.00259	0.26	0.00036	0.00336	0.00036	60	0.02015	10.85440	0.01008				
PLATE GLASS (SUSPENDED)	SF	0.00259	0.19920	0.00259	0.26	0.00259	0.19920	0.00259	0.26	0.00036	0.00336	0.00036	60	0.02015	10.85440	0.01008				
SINGLE UNIT GLASS SKYLIGHT	SF	0.02149	0.35988	0.02149	0.87	0.02149	0.35988	0.02149	0.87	0.00300	0.05031	0.00300	300	1.17978	19.61000	0.08989				
SINGLE UNIT GLASS SKYLIGHT	SF	0.02138	0.30152	0.02138	0.81	0.02138	0.30152	0.02138	0.81	0.00299	0.04216	0.00299	300	1.22586	16.43000	0.61293				
SPECIAL SURFACES	SF	0.00119	0.01026	0.00119	0.04	0.00119	0.01026	0.00119	0.04	0.00017	0.00143	0.00017	65	0.00754	1.84440	0.00377				
ACUSTIC TILE SPECIAL PUR.	SF	0.00119	0.00982	0.00119	0.03	0.00119	0.00982	0.00119	0.03	0.00017	0.00137	0.00017	65	0.00754	1.84440	0.00377				
ACUSTIC TILE (FIRE RATED)	SF	0.00119	0.00982	0.00119	0.03	0.00119	0.00982	0.00119	0.03	0.00017	0.00137	0.00017	65	0.00754	1.84440	0.00377				
ASB-ADDS FIRE RTD. TILE	SF	0.03886	0.11467	0.03886	1.03	0.03886	0.11467	0.03886	1.03	0.00543	0.01603	0.00543	65	0.37141	0.6460	0.19637				
FIBERGLASS PANELS, RIGID	SF	0.05580	0.16758	0.05580	1.49	0.05580	0.16758	0.05580	1.49	0.00780	0.02343	0.00780	70	0.06536	1.77285	0.04748				
CONCRETE	SF	0.00162	0.00095	0.00162	0.04	0.00162	0.00095	0.00162	0.04	0.00023	0.00013	0.00023	500	3.80861	4.63220	1.90431				
CONCRETE (UNFINISHED)	SF	0.00162	0.00095	0.00162	0.04	0.00162	0.00095	0.00162	0.04	0.00023	0.00013	0.00023	500	3.80861	4.63220	1.90431				

See notes on the last page of this table for Explanation of Column Headings

EPS BASED MAINTENANCE AND REPAIR COST DATA FOR USE IN LIFE CYCLE COST ANALYSIS (\$ PER UNIT MEASURE)										PAGE 13
COMPONENT DESCRIPTION	PRESENT WORTH OF ALL 25 YEAR MAINTENANCE AND REPAIR COSTS (d=10%)				ANNUAL MAINTENANCE AND REPAIR PLUS HIGH COST REPAIR AND REPLACEMENT COSTS					
	By Resources				Annual Maintenance and Repair					
	um	labor	material	equipment	Washington	D.C. Total	labor	material	equipment	yr
CONCRETE (FINISHED) See NOTES on the last page of this table for Explanation of Column Headings	SF	0.00205	0.05644	0.00184	0.10		0.00029	0.00789	0.00026	500
										3.80861
										4.63220
										1.90431

## APPENDIX C:

### TECHNICAL BULLETIN INDEX FOR ENGINEERED PERFORMANCE STANDARDS

<u>TB No.</u>	<u>Date</u>	<u>Title</u>
TB 420-1	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Engineers Manual (NAVDOKS P-700.0)
TB 420-2	5 Oct 72	Engineered Performance Standards Public Works Maintenance: General Handbook (NAVDOKS P-701.0)
TB 420-3	5 Oct 72	Engineered Performance Standards Public Works Maintenance: General Formulas
TB 420-4	1 Mar 82	Tri-Service Coordination of the Carpentry Handbook
TB 420-5	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Carpentry Formulas
TB 420-6	1 Feb 82	Tri-Service Coordination of the Electric, Electronic Handbook
TB 420-7	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Electric, Electronic Formulas
TB 420-8	1 Feb 82	Tri-Service Coordination of the Heating, Cooling and Ventilating Handbook
TB 420-9	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Heating, Cooling, Ventilating Formulas
TB 420-10	1 Apr 81	Engineered Performance Standards Real Property Maintenance Activities Janitorial Handbook
TE 420-11	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Janitorial Formulas
TB 420-12	1 Apr 83	Engineered Performance Standards Real Property Maintenance Activities Machine Shop, Machine Repairs Handbook
TB 420-13	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Machine Shop and Repairs Formulas
TB 420-14	Sep 80	Engineered Performance Standards Real Property Maintenance Activities: Masonry Handbook
TB 420-15	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Masonry Formulas



TB 420-16	1 Apr 81	Engineered Performance Standards Real Property Maintenance Activities: Moving, Rigging Handbook
TB 420-17	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Moving, Rigging Formulas
TB 420-18	1 Nov 78	Engineered Performance Standards Real Property Maintenance Activities: Paint Handbook
TB 420-19	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Paint Formulas
TB 420-20	1 Aug 83	Engineered Performance Standards Real Property Maintenance Activities: Pipefitting, Plumbing Handbook
TB 420-21	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Pipefitting, Plumbing Formulas
TB 420-22	1 Sep 80	Engineered Performance Standards Public Works Maintenance: Roads, Grounds, Pest Control, Refuse Collection Handbook
TB 420-24	1 Mar 84	Engineered Performance Standards Real Property Maintenance Activities: Sheet Metal, Structural Iron and Welding Handbook
TB 420-25	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Sheet Metal, Structural Iron and Welding Handbook
TB 420-26	1 Nov 79	Engineered Performance Standards Real Property Maintenance Activities: Trackage Handbook
TB 420-27	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Trackage Formulas
TB 420-28	1 Nov 79	Engineered Performance Standards Real Property Maintenance Activities: Wharfbuilding Handbook
TB 420-29	5 Oct 72	Engineered Performance Standards Public Works Maintenance: Wharfbuilding Formulas
TB 420-30	1 Aug 79	Engineered Performance Standards Real Property Maintenance Activities: Emergency/Service Handbook
TB 420-31	1 Dec 73	Engineered Performance Standards Real Property Maintenance Activities: Planner and Estimator's Workbook (Instructor's Manual) (S&I OCE)
TB 420-32	1 Mar 80	Engineered Performance Standards Real Property Maintenance Activities: Planner and Estimator's Workbook, Student's Manual

TB 420-33	1 Aug 83	Engineered Performance Standards Real Property Maintenance Activities: Unit Price Standards Handbook
TB 420-34	1 Mar 84	Engineered Performance Standards Real Property Maintenance Activities: Preventive/Recurring Maintenance Handbook
TB 420-35	1 Apr 81	Tri-Service Coordination of the Moving, Rigging Handbook
TB 420-51	30 Oct 73	Engineered Performance Standards Public Works Maintenance: Facilities Engineering Management of Maintenance Painting of Facilities

# APPENDIX D:

## GEOGRAPHICAL LOCATION ADJUSTMENT FACTORS

<u>State</u>	<u>Location</u>	<u>ACF Index</u>
Alabama	State Average	.86
	Birmingham	.96
	Mobile	.86
	Montgomery	.76
	Anniston Army Depot	.81
	Huntsville	.88
	Fort McClellan	.80
	Redstone Arsenal	.88
	Fort Rucker	.80
Alaska	State Average	2.25
	Anchorage	1.92
	Delta Junction	2.70
	Fairbanks	2.13
	Adak	3.88
	Aleutian Islands	3.86
	Anchorage NSGA	1.92
	Barrow	4.18
	Burnt Mtn.	6.86
	Clear	3.10
	Eielson AFB	2.13
	Elmendorf AFB	1.92
	Galena	3.73
	Fort Greely	2.70
	Fort Richardson	1.92
	Fort Wainwright	2.13
	State Average	1.02
Arizona	Flagstaff	1.02
	Phoenix	.99
	Tucson	1.05
	Fort Huachuca	1.22
	Yuma Proving Ground	1.31
	Yuma	1.31
	State Average	.89
Arkansas	Pinebluff	.93
	Little Rock	.83
	Fort Smith	.92
	Fort Chaffee	.92
	Pine Bluff Arsenal	.93
	State Average	1.21
California	Los Angeles	1.20
	San Diego	1.18
	San Francisco	1.25
	Beale	1.28
	Bridgeport NWTC	1.27
	Castle	1.13
	Centerville Beach	1.32
	Desert Area	1.18
	Edwards AFB	1.30

<u>State</u>	<u>Location</u>	<u>ACF Index</u>
California (Cont'd)	El Centro	1.27
	George AFB	1.31
	Fort Hunter Liggett	1.29
	Fort Irwin	1.20
	Le Moore NAS	1.20
	March AFB	1.18
	Mather AFB	1.17
	McClellan AFB	1.17
	Monterey Area	1.23
	Presidio of Monterey	1.23
	Norton AFB	1.16
	Oakland Army Base	1.33
	Fort Ord	1.24
	Port Huenema Area	1.20
	Riverside	1.18
	Sacramento	1.15
	Sacramento Army Depot	1.15
	Presidio of San Francisco	1.25
	San Nicholas Island	2.59
	Sharpe Army Depot	1.13
	Sierra Army Depot	1.33
	Stockton	1.15
	Travis AFB	1.27
	Vandenburg AFB	1.38
Colorado	State Average	.98
	Colorado Springs	.94
	Denver	1.04
	Pueblo	.96
	Fort Carson	1.01
	Fitzsimmons AMC	1.06
	Pueblo Army Depot	.96
	Peterson AFB	.94
	Rocky Mountain Arsenal	1.06
	State Average	1.13
Connecticut	Bridgeport	1.16
	Hartford	1.10
	New London	1.14
	State Average	.99
Delaware	Dover	1.04
	Lewes	.98
	Milford	.96
	Lewes NF	1.04
	Dover AFB	1.04
	Washington	1.03
District of Columbia	Fort McNair	1.03
	Walter Reed AMC	1.03
Florida	State Average	.89
	Miami	.95
	Panama City	.92
	Tampa	.79
	Cape Canaveral	.96
	Cape Kennedy	.96

<u>State</u>	<u>Location</u>	<u>ACF Index</u>
Florida (Cont'd)	Gulf Coast	.85
	Homestead AFB	.88
	Homestead	.88
	Jacksonville Area	.85
	Key West NAS	1.08
	Orlando	.80
	Pensacola Area	.85
	McDill AFB	.77
	Eglin AFB	.77
	Tyndall AFB	.92
	State Average	.80
	Albany	.82
	Atlanta	.87
	Macon	.70
Georgia	Athens	.90
	Atlanta-Marietta	.93
	Fort Benning	.71
	Columbus	.71
	Fort Gillem	.87
	Fort Gordon	.94
	Kings Bay	.93
	Fort McPherson	.87
	Fort Stewart	.84
	State Average	1.28
	Hawaii	1.29
	Honolulu	1.27
	Maui	1.29
	Alimanu	1.27
Hawaii	Barbars Point NAS	1.34
	Fort Debussy	1.27
	EWA Beach Area	1.34
	Helemano	1.34
	Hickam Army Air Field	1.27
	Kaneohe MCAS	1.34
	Moanalua	1.27
	Pearl City	1.27
	Pearl Harbor	1.27
	Pohakuloa	1.32
	Schofield Barracks	1.27
	Fort Shafter	1.27
	Tripler AMC	1.27
	Wheeler Army Air Field	1.34
	State Average	1.11
	Boise	1.05
	Idaho Falls	1.08
Idaho	Mountain Home	1.19
	Mountain Home AFB	1.20
	State Average	1.03
	Belleville	.96
Illinois	Chicago	1.09
	Rock Island	1.03
	Rock Island Arsenal	1.06

<u>State</u>	<u>Location</u>	<u>ACF Index</u>
Illinois (Cont'd)	St. Louis Support Ctr	.96
	Savannah Army Depot	1.05
	Scott AFB	1.03
	Fort Sheridan	1.10
Indiana	State Average	.99
	Indianapolis	1.03
	Logansport	.99
	Madison	.94
	Fort Benjamin Harrison	1.07
	Crane	1.10
	Crane AAP	1.10
	Grissom AFB	1.06
	Indiana AAP	1.02
	Jefferson Proving Ground	.94
Iowa	State Average	1.02
	Burlington	1.04
	Cedar Rapids	.98
	Des Moines	1.05
	Iowa AAP	1.06
Kansas	State Average	.94
	Manhattan	.97
	Topeka	.96
	Wichita	.88
	Kansas AAP	.94
	Fort Leavenworth	.94
	Fort Riley	.97
	Sunflower AAP	.97
	State Average	.96
	Bowling Green	.99
Kentucky	Lexington	.96
	Louisville	.93
	Fort Campbell	.93
	Fort Knox	.99
	Lexington/Bluegrass Army Depot	1.06
	Louisville NAS	.93
	State Average	.92
	Alexandria	.87
Louisiana	New Orleans	.94
	Shreveport	.94
	Barksdale AFB	.94
	England AFB	.87
	Gulf Outport New Orleans	.94
	Louisiana AAP	.94
	Fort Polk	.94
	State Average	.93
	Bangor	.85
	Caribou	.99
Maine	Portland	.94
	Brunswick	.93
	Cutler	.98
	Northern Area	1.17
	Winter Harbor	.98

<u>State</u>	<u>Location</u>	<u>ACF Index</u>
Maryland	State Average	.97
	Baltimore	.95
	Fredrick	.94
	Lexington Park	1.01
	Aberdeen Proving Ground	.94
	Annapolis	1.03
	Fort Detrick	.94
	Harry Diamond Lab	1.00
	Fort Meade	.95
	Patuxent River Area	1.08
	Fort Ritchie	.90
Massachusetts	State Average	1.10
	Boston	1.13
	Fitchburg	1.08
	Springfield	1.08
	Army Mtls & Mech Research Ctr	1.13
	Fort Devens	1.15
	Natick Research & Development Ctr	1.13
	South Weymouth	1.13
Michigan	State Average	1.06
	Bay City	1.02
	Detroit	1.14
	Marquette	1.03
	Detroit Arsenal	1.14
	Northern Area	1.25
	Republic (Elfcom)	1.10
	Selfridge AFB	1.14
Minnesota	State Average	1.08
	Duluth	1.05
	Minneapolis	1.09
	St. Cloud	1.10
	Twin Cities AAP	1.09
Mississippi	State Average	.84
	Biloxi	.87
	Columbus	.81
	Jackson	.84
	Columbus AFB	.81
	Gulfport Area	.87
	Meridian	.92
Missouri	State Average	.92
	Kansas City	.92
	St. Louis	.99
	Rolla	.85
	Lake City AAP	.93
	Fort Leonard Wood	.91
Montana	State Average	1.15
	Billings	1.15
	Butte	1.18
	Great Falls	1.12
	Malmstrom AFB	1.12
Nebraska	State Average	1.03
	Grand Island	1.00

<u>State</u>	<u>Location</u>	<u>ACF Index</u>
Nebraska (Cont'd)	Lincoln	1.05
	Omaha	1.05
	Offutt AFB	1.05
Nevada	State Average	1.18
	Hawthorne	1.26
	Las Vegas	1.13
	Reno	1.15
	Fallon	1.28
	Hawthorne AAP	1.26
	Nellis AFB	1.13
New Hampshire	State Average	1.09
	Concord	1.06
	Nashua	1.06
	Portsmouth	1.14
	Cold Regions Lab	1.17
New Jersey	State Average	1.08
	Newark	1.11
	Red Bank	1.08
	Trenton	1.06
	Bayonne	1.10
	Bayonne Mil Ocean Term	1.09
	Fort Dix	1.03
	Earle	1.10
	Lakehurst	1.05
	Fort Monmouth	1.09
	Picatinny Arsenal	1.20
New Mexico	State Average	1.03
	Alamogordo	.99
	Albuquerque	1.03
	Gallup	1.06
	Holloman AFB	1.05
	Kirtland AFB	1.03
	White Sands Missile Range	1.09
	Fort Wingate	1.06
New York	State Average	1.12
	Albany	1.07
	New York City	1.24
	Syracuse	1.05
	Brooklyn	1.24
	Fort Drum	1.18
	Fort Hamilton	1.24
	Seneca Army Depot	1.15
	U.S. Military Academy	1.17
	Watervliet Arsenal	1.07
North Carolina	State Average	.76
	Fayetteville	.76
	Greensboro	.75
	Wilmington	.78
	Fort Bragg	.76
	Camp Lejeune Area	.86
	Cherry Point	.86
	Goldsboro	.77



<u>State</u>	<u>Location</u>	<u>ACF Index</u>
North Carolina (Cont'd)	Pope AFB	.82
	Seymour AFB	.77
	Sunny Point Mil Ocean Term	.78
North Dakota	State Average	1.03
	Bismarck	1.02
	Grand Forks	.98
	Minot	1.10
	Grand Forks AFB	.98
	Stanley R. Hicklesen CPX	1.03
	Minot AFB	1.12
Ohio	State Average	1.00
	Columbus	1.03
	Dayton	.98
	Youngstown	.99
	Cleveland	1.14
	Wright-Patterson AFB	.98
Oklahoma	State Average	.93
	Lawton	.90
	McAlester	.91
	Oklahoma City	.98
	Altus AFB	.94
	Enid	1.01
	McAlester AAP	.91
	Fort Sill	.90
Oregon	State Average	1.05
	Pendleton	1.08
	Portland	1.07
	Salem	.99
	Charleston	1.11
	Coos Head	1.08
	Umatilla Army Depot	1.18
Pennsylvania	State Average	1.00
	Harrisburg	.91
	Philadelphia	1.05
	Pittsburgh	1.04
	Carlisle Barracks	.93
	New Cumberland Army Depot	.91
	Fort Indiantown Gap	1.07
	Letterkenny Army Depot	1.07
	Mechanicsburg Area	.91
	Tobyhanna Army Depot	1.14
	Warminster Area	1.04
Rhode Island	State Average	1.11
	Bristol	1.13
	Newport	1.11
	Providence	1.10
	Davisville	1.17
South Carolina	State Average	.82
	Charleston	.81
	Columbia	.82
	Myrtle Beach	.84
	Beaufort Area	.89

<u>State</u>	<u>Location</u>	<u>ACF Index</u>
South Carolina (Cont'd)	Charleston AFB	.81
	Fort Jackson	.82
	Sumter	.80
South Dakota.	State Average	.95
	Aberdeen	.95
	Sioux Falls	.94
	Rapid City	.96
	Ellsworth AFB	.98
Tennessee	State Average	.84
	Chattanooga	.86
	Kingsport	.72
	Memphis	.95
	Arnold AFB	.90
	Milan AAP	.98
	Holston AAP	.71
Texas	State Average	.85
	San Angelo	.76
	San Antonio	.86
	Fort Worth	.93
	Fort Bliss	.96
	Carswell AFB	.93
	Chase Field - Beeville	.97
	Corpus Christi Army Depot	.92
	Corpus Christi	.92
	Dallas	.93
	Dyess AFB	.94
	Fort Hood	.89
	Kingsville	.99
	Red River Army Depot	.78
	Fort Sam Houston	.86
	William Beaumont AMC	.96
	Bergstrom AFB	.95
	Brooks AFB	.86
	Randolph AFB	.86
	Kelly AFB	.86
	Lackland AFB	.86
Utah	State Average	1.03
	Ogden	1.05
	Salt Lake City	1.00
	Tooele	1.06
	Dugway Proving Ground	1.03
	Hill AFB	1.07
	Tooele Army Depot	1.05
Vermont	State Average	.99
	Burlington	1.00
	Montpelier	1.00
	Rutland	.96
Virginia	State Average	.95
	Norfolk	.95
	Radford	.95
	Richmond	.94
	Arlington	1.04

<u>State</u>	<u>Location</u>	<u>ACF Index</u>
Virginia (Cont'd)	Arlington Hall Station	1.04
	Arlington National Cemetery	1.04
	Fort Belvoir	1.04
	Cameron Station	1.04
	Dahlgren	1.10
	Fort Eustis	.96
	Humphreys Engineer Center	1.03
	Fort A. P. Hill	.92
	Fort Lee	.93
	Fort Monroe	.94
	Fort Myer	1.03
	Norfolk-Newport News Area	.95
	Fort Pickett	.98
	Quantico	1.03
	Nadford AAP	1.02
	Port Story	.95
	Vint Hill Farms Station	1.08
Washington	State Average	1.09
	Spokane	1.08
	Tacoma	1.07
	Yakima	1.11
	Fairchild AFB	1.13
	Jim Creek	1.34
	Fort Lewis	1.07
	Pacific Beach	1.27
	Puget Sound Area	1.15
	Seattle Area	1.12
	Widbey Island	1.12
	Yakima Firing Center	1.18
West Virginia	State Average	.95
	Bluefield	.92
	Clarksburg	.95
	Charleston	.99
	Sugar Grove	1.15
Wisconsin	State Average	1.06
	LaCrosse	1.04
	Madison	1.02
	Milwaukee	1.13
	Badger AAP	1.06
	Clam Lake	1.20
	Fort McCoy	1.11
Wyoming	State Average	1.08
	Casper	1.07
	Cheyenne	1.10
	Laramie	1.08
	F. E. Warren AFB	1.10

## DISTRIBUTION

Chief of Engineers

ATTN: CEHSC-IM-LH (2)

ATTN: CEHSC-IM-LP (2)

ATTN: CEMP-EC

ATTN: CERD-L

USAEHSC

ATTN: CEHSC-FM-R

US Army Engineer Districts (41)

ATTN: Chief, Design Branch

ATTN: Chief, Cost Estimating Branch

US Army Engr. Divisions (14)

ATTN: Chief, Design Branch

ATTN: Chief, Cost Estimating Branch

Fort Belvoir, VA

ATTN: CECC-R

Defense Technical Info. Center 22304

ATTN: DTIC-FAB (2)

120

4/91